

2025 Catalog



CANADA

Grey Goat Hardware

Frameless Shower Door | Railing Hardware | Storefront & Entrances | Door Rails & Architectural Hardware | Glazing Supplies | **goatobject**[®]



GGH GLAZING
SUPPLY
COMPANY

www.ggshardware.com

Grey Goat Hardware is a leading Canadian supplier of premium glass and architectural hardware. With over 5,500 products and nationwide distribution, we deliver innovative solutions for shower systems, glass railings, and commercial glazing—trusted by glaziers, architects, and designers across the country.

TORONTO | MONTREAL | CALGARY



Volume 2.0

Our Locations

Canada's Trusted [Glazing Hardware Distributor](#)

With distribution centers in Toronto, Montreal, and Calgary, Grey Goat Hardware ensures fast and efficient service - wherever your project takes you.



Contact Us

Trusted by [2,000+ glazing contractors](#) across North America

TORONTO WAREHOUSE

606 Rivermede Rd, UNIT #1 & 2, Concord,
ON L4K 2H6

Phone: 1-905-264-1600

Textline: 1-877-999-4628

Email: cs.toronto@ggshardware.com

Website: www.ggshardware.com

MONTREAL WAREHOUSE

8145 Avenue Marco-Polo, Montreal, QC
H1E 5Y8

Phone: 1-514-547-3422

Textline: 1-877-999-4628

Email: cs.montreal@ggshardware.com

Website: www.ggshardware.com

CALGARY WAREHOUSE

2880 45 Ave SE, Unit # 248, Calgary, AB
T2B 3M1

Phone: 1-905-264-1600

Textline: 1-877-999-4628

Email: cs.calgary@ggshardware.com

Website: www.ggshardware.com

www.ggshardware.com

Scan For Real-Time

Get instant access to key tools and info — right from your phone.

[Scan to Order](#) | [Real-Time Inventory](#) | [Custom Pricing](#) | [Volume Discounts](#) | [Orders Tracking](#)
| [3D CAD Models](#) | [Technical Drawings](#) | [Factory Order Programs](#) | [Full Product Catalog](#)



GGH GLAZING
SUPPLY
COMPANY

TORONTO • MONTREAL • CALGARY



GGH PRODUITS
VERRIERS

TORONTO • MONTREAL • CALGARY

Table Of Contents



01 Frameless Shower Door

13	Shower Hinges	56	Mirror L & J Channels	65	Shower Support Bar
30	Shower Sweeps	58	LED Mirrors	69	Sliding Door Kits
33	Shower Clamps	59	Header Kits	77	Stock Glass Doors
39	Handles & Towel Bars	62	Flat Bar For Grid Showers	83	GGH Color Sample Kit
54	Shower U Channels				

02 Railing Hardware

85	Arch-Loc Series	117	Pro Series - Engineered	146	Romeo Juliet Balcony System
93	Titan Series Spigots	126	Railing Mini Post	147	Handrail Brackets
101	Mood LED System	129	Partition Post	151	Aluminum Posts
103	Standoffs	133	G-AWS Aluminum Windscreen System	154	Goat Cable Rail System
113	Display Standoffs 3/4" & 1-1/4"	129	Railing Clamps	156	Hulk Series
113	Railing Glass Panels (1/2")	133	Handrails & Caprails	159	Pool Fencing Hardware

03 Storefront & Entrances

163	Assa Abloy	187	Glass Door Locks	213	Soft-Closing Sliding Door
171	Solidity Hydraulic Bottom Patch	191	Commercial Center Lock	216	EZY1 Sliding Door Kits
173	Patch Fittings & Transom	194	Striker Center Lock Series	217	EZY2 Sliding Door Kits
179	Mag lock	195	Commercial Ladder Pulls	219	Continuous Gear Hinge
181	Commercial U-Channels, Endcaps & Rubber	205	Mechanical U-Channels	221	Grey Goat - Samples
184	Hulk Series	209	Sliding Door Kits - LAG Series		

04 Door Rails & Architectural Hardware

223	DLUX 4" Door Rail	246	Architectural U-Channels	259	ADA Compliant Hardware
233	Smoke baffle	248	Commercial Spider Fittings	261	Railing Glass Panels (1/2")
238	Partition Sliding System	252	Glass Canopy Brackets	265	Stock Glass Doors
240	Continuous Gear Hinge	254	Window Hardware	269	Shower Glass Shelves (3/8")
242	Exposed Door Closer	256	Drive Thru Windows		
244	Rim Panic Device	258	Partition System		

05 Glazing Supplies

272	G.O.A.T Carbide Tip Drill Bits	275	Stainless Steel Cleaners & Adhesives	291	Tools
272	Spade Drill Bits (Tile)	277	Glass Silicone Sealants	296	Acrylic Mirror Plates
273	3M Very High Bond Tapes	281	Silicone & EPDM Setting Blocks		
274	Tremco® 440 Tape	285	Suction Cup		

Who We Are?

Grey Goat Hardware is a leading supplier of premium glass and architectural hardware solutions across North America. Built on a foundation of reliability, precision, and performance, we've become the trusted partner for glaziers, contractors, and designers who demand both form and function in every detail.

With decades of industry knowledge and hands-on experience, our team curates and delivers high-quality hardware—from shower hinges and sliding systems to railing components, door rails, patch fittings, and more. Every product we offer is carefully selected to meet the highest standards of durability, ease of installation, and design appeal.

We don't just sell hardware—we support your build from start to finish. Our focus is on providing dependable solutions, responsive service, and the technical expertise you need to complete your projects smoothly and successfully.


Driven by innovation, powered by partnership, and dedicated to craftsmanship—GGH Hardware is Built for the Job.



Introducing Grey Goat Hardware | Faster Shipping



Premium glass hardware meets better pricing and faster shipping. Get the quality you trust, delivered with speed and value that keeps your projects moving.



Check Our Website

Check our website at www.ggshardware.com for live inventory, product specs, and easy online ordering — available 24/7.



GGH In-house Fabrication

At GGH, we specialize in delivering premium glass hardware solutions—engineered and fabricated in-house to meet the demands of modern architectural systems. With full control over fabrication, Grey Goat Hardware ensures precision, consistency, and faster turnaround times. Every product is crafted with installers and end users in mind, offering durable performance, ease of installation, and seamless integration into today’s design standards.

GGH – Your Partner

We proudly collaborate with fabricators, OEMs, and project managers to source custom hardware solutions tailored to unique builds and site requirements. Whether it’s recommending an optimized standard product or finding specialized components, GGH helps bring your project to life.

Quality You Can Trust

At Grey Goat Hardware, quality is at the core of everything we do. Our products are engineered and professionally stamped to meet Canadian building standards. Trusted by thousands of installers across North America, our hardware is designed for ease of installation, backed by in-house support and continuous innovation.



TORONTO Location

606 Rivermede Rd UNIT #1 & 2, Concord,
ON L4K 2H6

Phone: 1-905-264-1600

Textline: 1-877-999-4628

Email: cs.toronto@ggshardware.com

Website: www.ggshardware.com

Hours of Operation:

Monday to Friday: 8:00 AM – 5:00 PM

Saturday: 9:00 AM – 1:00 PM

Sunday: Closed

MONTREAL Location

8145 Avenue Marco-Polo, Montreal, QC
H1E 5Y8

Phone: 1-514-547-3422

Textline: 1-877-999-4628

Email: cs.montreal@ggshardware.com

Website: www.ggshardware.com

Hours of Operation:

Monday to Friday: 7:30 AM – 4:00 PM

Saturday: Closed

Sunday: Closed

CALGARY Location

2880 45 Ave SE, Unit # 248 Calgary, AB
T2B 3M1

Phone: 1-905-264-1600

Textline: 1-877-999-4628

Email: cs.calgary@ggshardware.com

Website: www.ggshardware.com

Hours of Operation:

Monday to Friday: 8:00 AM – 5:00 PM

Saturday: Closed

Sunday: Closed

GGH Professional Industry Partners



At the heart of Grey Goat Hardware is GGH—our in-house family of brands created specifically to meet the evolving needs of today's glazing and architectural professionals. Developed from years of on-site experience, customer feedback, and a relentless pursuit of better, smarter hardware, GGH's Brands represent more than just product lines—they embody our commitment to craftsmanship, reliability, and innovation across every application.

Engineered for the Real World

GGH products are thoughtfully designed with the installer in mind. Every detail—from material selection to finish options and installation ease—is engineered for real-world performance and durability. Whether it's a frameless shower hinge, a sliding kit, or a railing component, our hardware is made to meet the demands of daily use while maintaining its clean, architectural appearance.



GGH (Grey Goat Hardware)

Our exclusive line of high-quality architectural and glass hardware. Designed with professionals in mind, GGH® products are engineered for durability, ease of installation, and refined aesthetics—trusted by glaziers, contractors, and designers alike.

Wood's Powr-Grip®

A world leader in vacuum lifting tools, Wood's Powr-Grip® delivers powerful, reliable solutions for handling glass and other materials safely and efficiently. A must-have for any serious installer.

Arch-Loc™

Combining style and strength, Arch-Loc™ offers a comprehensive range of fittings and locks for glass doors and partitions. Precision-made and performance-tested, Arch-Loc is known for quality without compromise.

TREMCO®

products are engineered for durability, flexibility, and long-term protection—making them the go-to choice for glass and glazing applications, façade systems, curtain walls, and structural joints.

ASSA ABLOY

ASSA ABLOY is synonymous with security, innovation, and precision. From mechanical locks and door closers to automated entrance systems and electronic access control, ASSA ABLOY offers comprehensive solutions trusted across industries worldwide.

Horton Automatics®

A leader in automated entrance systems, Horton Automatics specializes in sliding, swinging, and revolving door solutions that enhance both convenience and accessibility.

Parmer®

Parmer delivers a robust range of door hardware and accessories built for demanding environments. Known for combining simplicity with strength, Parmer products are perfect for high-traffic commercial spaces where function and form must go hand in hand.


goatobject® 3D Models

Goatobject is our 3D modeling tool, giving you detailed views of GGH products for accurate planning and presentation. Rotate, inspect, and download visual assets — right from our site.

GGH Customer Service

At Grey Goat Hardware, customer service is our priority. We know reliable support matters just as much as product quality, so we work hard to make your experience smooth, efficient, and hassle-free.

Direct Line
Email



1-905-264-1600 (Head Office)
cs.toronto@ggshardware.com
cs.montreal@ggshardware.com
cs.calgary@ggshardware.com
GGH Live Chat Online



What We Offer?

Technical Support

From product installation guidance to troubleshooting, our team of experts is here to help you with the technical details of every product we offer.

Product Recommendations

Not sure which product best suits your project? We provide in-depth consultations and expert recommendations to help you choose the right hardware for your needs.

Order Assistance

Need to place an order or track your shipment? Our team ensures a seamless ordering experience and can provide updates on inventory, delivery, and lead times.

Custom Solutions

For unique projects or specific needs, our team works directly with you to deliver customized hardware solutions—tailored to meet your exact specifications.



Tech Sales and Estimating Department

- Fast and accurate quotations for standard and custom hardware
- Review of drawings to recommend the right products
- Hardware guidance to ensure code compliance and performance
- Custom solutions for challenging site conditions or unique designs
- Responsive technical support to keep your job moving smoothly



Business Development Department

- Tailored partnership programs for dealers, resellers, and project clients
- Product and market insights to support your business growth
- Collaboration on large-scale or multi-phase projects
- Opportunities for co-marketing, training, and regional expansion



GGH Ordering Information

We make ordering simple, transparent, and efficient—because getting the right hardware, on time, should never be complicated. Whether you're placing a one-time order or managing a multi-phase project, Grey Goat Hardware provides the tools and support you need for a seamless experience from quote to delivery.

01 Account Setup

To streamline your orders and access online pricing, we encourage all professional customers to set up an account online at www.ggshardware.com/register.

To apply for an account:

- Visit: www.ggshardware.com/account
- Accounts typically activate within 30mins.
- Payment terms available with submission and approval of credit application (contact customer support for more details).

02 Placing an Order

You can place orders through any of the following channels:

Online:

- Browse our full catalog and shop 24/7 at www.ggshardware.com
- Fastest order entry, with real-time stock availability and shipping estimates

Email:

- Send purchase orders or inquiries to: orders@ggshardware.com
- Please include: company name, product SKUs, quantities, shipping address, and requested delivery timeline



Phone:

- Call our Sales Team directly at +1 905-264-1600
- Available Monday–Friday, 8:00 AM–5:00 PM (PST)
- Perfect for urgent orders, special requests, or personalized assistance

03 Payment Options

We accept the following payment methods:

- Credit Terms (Net 30) – for approved accounts
- Major Credit Cards – Visa, MasterCard, AMEX
- E-Transfers / ACH / Bank Wire – banking info available upon request
- Checks – Accepted for established accounts



04 Shipping & Delivery

We ship across North America with a variety of delivery options to meet your schedule:

Carriers:

- UPS, FedEx, DHL, Local Freight
- Dedicated LTL or courier for large shipments or glass/oversized items

Cut-off Time for Same-Day Shipping:

- Orders placed by 2:00 PM PST (in-stock items) usually ship same day

Shipping Options:

- Standard Ground (2–5 business days)
- Express & Overnight (available upon request)
- Will Call / Local Pickup (for nearby customers – call to schedule)

Tracking:

- Tracking numbers and delivery updates are emailed as soon as the order ships













GGH Finishes

At Grey Goat Hardware, we believe the finish is more than just surface-level—it's the final touch that defines the look, feel, and performance of your space. That's why GGH offers a curated selection of premium finishes across our product lines, designed to complement a wide range of architectural styles and applications.

The following finishes were available at the time this catalog was printed:

Chrome, Brushed Nickel, Matte Black, Satin Brass, Polished Nickel, Brushed Bronze, Gun Metal, Oil Rubbed Bronze, White, Antique Brass, Polish Brass, Brushed Stainless Steel, Polished Stainless Steel, Satin Anodized, and Custom Finishes.

Frameless Shower Hardware







					
CH Chrome	BN Brushed Nickel	MBL Matte Black	SB Satin Brass	PN Polished Nickel	BBRZ Brushed Bronze
					
GM Gun Metal	ORB Oil Rubbed Bronze	W White	AB Antique Brass	PB Polish Brass	Custom Finishes

This color tower was created for one-time distribution only. For the most up-to-date selection of available finishes, please visit our website at ggshardware.com.








Railing Hardware

					
BSS Brushed Stainless Steel	MBL Matte Black	SB Satin Brass	W White	PSS Polished Stainless Steel	Custom Finishes

Commercial Finishes

					
SA Satin Anodized	MBL Matte Black	BSS Brushed Stainless Steel	PSS Polished Stainless Steel	SB Satin Brass	Custom Finishes

Future Colors

						
ABC Antique Brushed Copper	BRG Brushed Rose Gold	SC Satin Chrome	RG Rose Gold	LSB Lacquered Satin Brass	PB Polish Brass	PVDB PVD Black

*These finishes aren't listed on our website yet — but they're available in our color chain. If you're interested, we'd be happy to provide upon request!




Check Our Website

www.ggshardware.com


Step 1: Visit <https://ggshardware.com/>

Please click on the **"Login" or "Register"** button located in the top right corner.




Step 2: Login or Sign-up

Enter your login credentials or register for a new account. If you have just registered, your account will be approved by a representative within the same business day, allowing you to make purchases.




Step 3: Search for your items and review the PDF / CAD Drawing

If you know the item SKU, please enter it into the search bar. Once your account is approved, you will also be able to access the CAD Drawing on the product page. Please remember to select your desired finish and then **click "Add to Cart."**




Step 4: Enter your PO# and NOTES and Special Instructions

If you know the item SKU, please enter it into the search bar. Once your account is approved, you will also be able to access the CAD Drawing on the product page. Please remember to select your desired finish and then **click "Add to Cart."**



Step 5: Confirm if delivery or pickup

Please choose whether you'd like to pick up your order or have it delivered from the nearest warehouse (Toronto or Montreal). After making your selection and updating your address details, just click **"Complete order."** We'll take care of everything from there!



Explore GGH 3D Models on **goatobject**[™] 3D Models



Visualize Before You Buy

Take the guesswork out of your next project. With **goatobject**, you can preview our shower doors and glass systems as 2D and 3D models—perfect for architects, designers, and contractors.

Visit Us on GOATOBJECT

Explore our product library online: 🖱️ www.ggshardware.com/goatobject
Search for GGH products and see how they'll integrate into your plans before making a purchase.

3D Preview



3D Preview





01 FRAMELESS SHOWER DOOR

Frameless Shower Door Hinges & Pivots



Jennifer Series	14	Valerie Series (Extra HD)	22	Junior Jenifer Series	28
Beverly Series	16	Betty Series (Extra HD)	23	Shower Hinge Accessories	29
Vivian Series (HD)	18	Cara Series / Heavy Duty	24	Replacement - Back Plates	29
Colette Series (HD)	20	Piper Series / Heavy Duty	26	Shower Sweeps	30



Jennifer Series


Shower Hinges - Square



INSTALLER'S
FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272



Faster & Easier
Installation!
Pre Glued Gaskets



Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online

Key Features

- **Material:** Durable, high-strength brass
- **Glass Fit:** 5/16" to 1/2" (8-12 mm)
- **Grip:** Pre-glued anti-slip gaskets for secure hold
- **Adjustability:** 5° reversible pin for easy alignment
- **Install:** Quick install with standard tools

**Designers
Selected**

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 Hinges	5/16" to 1/2"	28" (711mm)	80lbs. (36kg)
3 Hinges	(8 to 12 mm)	32" (813mm)	120lbs. (54kg)

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes



JEN037
Full Plate
Wall to Glass



JENH037
H Back Plate
Wall to Glass



JEN044
Offset Plate
Wall to Glass



JEN074
Short Back Plate
Wall to Glass



JEN280
Pony Plate
Wall to Glass



JEN180
Glass Mount 180°
Glass to Glass




JEN092
Glass Mount 90°
Glass to Glass



JEN045
Glass Mount 135°
Glass to Glass

Heavy Duty






JENT092

Glass to Glass 90° - T Shape



Note: Visit ggshardware.com
For Glass Fabrication & Product Information.



Adjustable – Jennifer Series

Our **NEW Adjustable Hinges** provide flexibility for setting any closed angle up to 90 degrees. Once the door is installed, simply loosen the Allen Set Screws, adjust the door to the desired closed position, and then tighten the screws to lock it in place. The door will automatically self-center to the new angle. These versatile hinges allow for smooth operation, swinging both inwards and outwards.



JENH337

H Plate
Wall to Glass / Adjustable



JEN345

Neo Angle 135°
Glass to Glass / Adjustable



JEN380

Adjustable Glass Mount 180°
Glass to Glass / Adjustable





JEN344 *

Adjustable Offset Plate
Wall to Glass



Beverly Series

Beveled Shower Hinges - Round



Key Features

- **Material:** Durable, high-strength brass
- **Glass Fit:** 5/16" to 1/2" (8-12 mm)
- **Grip:** Pre-glued anti-slip gaskets for secure hold
- **Adjustability:** 5° reversible pin for easy alignment
- **Install:** Quick install with standard tools

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 Hinges	5/16" to 1/2"	28" (711mm)	80lbs. (36kg)
3 Hinges	(8 to 12 mm)	32" (813mm)	120lbs. (54kg)

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online



BEV037
Beveled Full Plate
Wall to Glass



BEVH037
Beveled H Back Plate
Wall to Glass



BEV044
Beveled Offset Plate
Wall to Glass



BEV074
Beveled Short Back
Plate / Wall to Glass



BEV280
Beveled Pony Plate
Wall to Glass




BEV180
Beveled Glass Mount
180° / Glass to Glass



BEV092
Beveled Glass Mount
90° / Glass to Glass



BEV045
Beveled Glass Mount
135° / Glass to Glass



Adjustable – Beverly Series



BEVH337 *

Adjustable Beveled H Back Plate / Wall to Glass



BEV345 *

Adjustable Beveled Neo Angle 135° / Glass to Glass



Vivian Series

Shower Hinges - Square Heavy Duty



Key Features

- **Material:** Durable, corrosion-resistant brass
- **Glass Fit:** 3/8" to 1/2" (10-12 mm)
- **Grip:** Anti-slip, pre-glued gaskets for secure hold
- **Adjustability:** 5° reversible pin for easy alignment
- **Install:** Fast setup with standard tools

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 Hinges	3/8" to 1/2"	36" (914mm)	110lbs. (50kg)
3 Hinges	(10 to 12 mm)	36" (914mm)	140lbs. (63kg)

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online



VIV037
Square HD Full Plate
Wall to Glass



VIVH037
Square HD H Back
Plate / Wall to Glass



VIV044
Square HD Offset Plate
Wall to Glass



VIV074
Square HD Short
Back Plate / Wall to glass




VIV180
Square HD 180°
Glass to Glass



VIV092
Square HD 90°
Glass to Glass



VIV045
Square HD Neo Angle 135°
Glass to Glass



Adjustable – Vivian Series



Overview

Our **NEW Adjustable Hinges** provide flexibility for setting any closed angle up to 90 degrees. Once the door is installed, simply loosen the Allen Set Screws, adjust the door to the desired closed position, and then tighten the screws to lock it in place. The door will automatically self-center to the new angle. These versatile hinges allow for smooth operation, swinging both inwards and outwards.



VIV337 *
Adjustable Full Plate HD / Wall to Glass



VIV374 *
Adjustable Short Plate HD / Wall to Glass



VIV345 *
Adjustable Square 135° HD / Glass to Glass



VIV344 *
Adjustable Offset Plate HD / Wall to Glass




VIV380 *
Adjustable 180° HD / Glass to Glass



Colette Series

Shower Hinges - Beveled Heavy Duty



Key Features

- **Material:** High-strength, corrosion-resistant brass
- **Glass Fit:** Compatible with 3/8" to 1/2" (10-12 mm) glass
- **Grip:** Pre-glued Anti-Slip Gaskets for Secure Hold
- **Adjustability:** 5° Reversible Pin for Precise Alignment
- **Installation:** Quick and easy with standard tools

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 Hinges	3/8" to 1/2"	36" (914mm)	110 lbs (50 kg)
3 Hinges	(10 to 12mm)	36" (914mm)	140 lbs (63 kg)

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online



COLEH037
Beveled HD H Plate
Wall to Glass



COLE180
Beveled HD 180°
Glass to Glass



COLE092
Beveled HD 90°
Glass to Glass



COLE045
Beveled HD 135°
Glass to Glass



Adjustable – Colette Series



Overview

Our **NEW Adjustable Hinges** provide flexibility for setting any closed angle up to 90 degrees. Once the door is installed, simply loosen the Allen Set Screws, adjust the door to the desired closed position, and then tighten the screws to lock it in place. The door will automatically self-center to the new angle. These versatile hinges allow for smooth operation, swinging both inwards and outwards.



COLEH337 *

Adjustable - Beveled HD H Back Plate
Wall to Glass



COLE374 *

Adjustable - Beveled HD Short Back Plate
Wall to Glass



COLE345 *

Adjustable - Beveled HD 135°
Glass to Glass




COLE344 *

Adjustable - Beveled HD Offset Plate
Wall to Glass



Note: Visit ggshardware.com
For Glass Fabrication &
Product Information.



Valerie Series

Shower Hinges - Square Extra Heavy Duty



Finishes





Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Key Features

- **Material:** Solid brass for durability and corrosion resistance
- **Glass Fit:** 5/16" to 1/2" (8-12 mm)
- **Weight Capacity:** Up to 140 lbs (64 kg) with two hinges
- **Max Door Width:** Suitable for doors up to 39" (1000 mm)
- **Installation:** Easy setup using standard tools




Adjustable – Valerie Series



Overview

Our **NEW Adjustable Hinges** provide flexibility for setting any closed angle up to 90 degrees. Once the door is installed, simply loosen the Allen Set Screws, adjust the door to the desired closed position, and then tighten the screws to lock it in place. The door will automatically self-center to the new angle. These versatile hinges allow for smooth operation, swinging both inwards and outwards.



Betty Series

Shower Hinges - Round Extra Heavy Duty




Faster & Easier
Installation!
Pre Glued Gaskets

NEW



Finishes




For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Includes: Hinge, Glazing Gaskets, Wall Mounting Screws, Allen Head/Phillips Head Cover Plate Screws, and View Fabrication Template Online

Key Features

- **Material:** Solid brass for strength and corrosion resistance
- **Glass Fit:** 5/16" to 1/2" (8-12 mm)
- **Weight Capacity:** Holds up to 140 lbs (64 kg) with two hinges
- **Max Door Width:** Recommended up to 39" (1000 mm)
- **Installation:** Quick and easy with standard tools



Adjustable - Betty Series



Overview

Our **NEW Adjustable Hinges** provide flexibility for setting any closed angle up to 90 degrees. Once the door is installed, simply loosen the Allen Set Screws, adjust the door to the desired closed position, and then tighten the screws to lock it in place. The door will automatically self-center to the new angle. These versatile hinges allow for smooth operation, swinging both inwards and outwards.

Extra HD



BET344 *

Adjustable - Beveled Offset Plate
Wall to Glass

Extra HD




BET380 *

Adjustable - Beveled Glass
Mount 180° / Wall to Glass



Cara Series

Square Pivot



Key Features

- Materials:** Solid brass construction with stainless steel pins and spring for enhanced durability.
- Glass Compatibility:** Suitable for glass thicknesses of 5/16" to 3/8" (8 to 10 mm).
- Pivot Mechanism:** Smooth, reliable pivot action for easy door operation.
- Installation:** Easy installation with standard tools.

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 x Regular Duty	5/16" to 1/2"	31" (787mm)	100lbs. (45kg)
2 x Heavy Duty	(8 to 12mm)	36"(914mm)	145 lbs. (66 kg)

Note: Do not exceed either maximum weight or width when choosing proper quantity of hinges.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

CARA01
Square Pivot
Floor / Ceiling to Glass

NEW

CARA02
Square Pivot
Glass to Glass

CARA05L
Square Offset Pivot /
Left Hand Wall to Glass

CARA05R
Square Offset Pivot
Right Hand / Wall to Glass

NEW

CARA06 **
Adjustable Square
Header to Glass

NEW

CARA07
Top or Bottom Pivot
with Attached U-Clamp Hinge


PIV5PIN
Cara Series Pivot
Pin Set

Cara Series – Heavy Duty

Shower Hinges - Round Extra Heavy Duty



Heavy Duty



HDCARA01

Square HD Pivot - Floor/ Ceiling to Glass

Heavy Duty



HDCARA02

Square HD Pivot - Glass to Glass

NEW

Heavy Duty



HDCARA05L

Square Offset Top or Bottom Pivot / Left Hand

Heavy Duty



HDCARA05R


Square Offset Top or Bottom Pivot / Right Hand

Heavy Duty




HDPIV5PIN

Heavy Duty Cara Hinges Pivot Pin




Note: Visit ggshardware.com
For Glass Fabrication & Product Information.



Piper Series

Beveled Pivot



Key Features

- **Materials:** Solid brass construction with stainless steel pins and spring for enhanced durability.
- **Glass Compatibility:** Suitable for glass thicknesses of 5/16" to 3/8" (8 to 10 mm).
- **Pivot Mechanism:** Smooth, reliable pivot action for easy door operation.
- **Installation:** Easy installation with standard tools.

Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 x Regular Duty	5/16" to 1/2"	31" (787mm)	100lbs. (45kg)
2 x Heavy Duty	(8 to 12mm)	36"(914mm)	145 lbs. (66 kg)

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



PIPJR01

Beveled Pivot
Floor / Ceiling to Glass



PIP01


Beveled Pivot
Floor / Ceiling to Glass



PIP02

Beveled Pivot
Glass to Glass

NEW



PIP06

Adjustable Beveled
Header to Glass



PIP05L

Beveled Offset Pivot
Left Hand / Wall to Glass



PIP05R


Beveled Offset Pivot
Right Hand / Wall to Glass



Piper Series – Heavy Duty



Heavy Duty



HDPIP01

Beveled Pivot - Floor / Ceiling to Glass

Heavy Duty

NEW



HDPIP05R


HD Offset Pivot / Right Hand Wall to Glass

Heavy Duty



HDPIP05L

HD Offset Pivot / Left Hand Wall to Glass



Junior Jenifer Series

Shower Hinges - Square - Light Duty



Specification

NO. Hinges	Thickness	MAX. Door Width	MAX. Weight
2 Hinges	1/4" to 5/16"	28" (711mm)	62lbs. (28kg)
3 Hinges	(6 to 8mm)	32" (813mm)	92lbs. (42kg)

Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



JEN037JR
Square Full Plate Wall to Glass



JEN044JR
Square Offset Plate Wall to Glass



JEN180JR *
Glass Mount 180° / Glass to Glass



JEN092JR *
Glass Mount 90° / Glass to Glass



Shower Hinge Accessories & Back Plates



<p>Junior / Regular / Heavy Duty</p> <p>GASKET-JRHINGE, GASKET-HINGE & GASKET-HDHINGE Junior Shower Hinge Gaskets 1 mm Thick - Replacement Gaskets</p>	<p>GASKET-PIVOTHINGE * Shower Pivot Hinge 1 mm Thick - Replacement Gaskets</p>	<p>HA01 Shower Header Adapter Block</p>	<p>Heavy Duty</p> <p>HDHA01 HD Shower Header Adapter Block / Wall to Glass</p>
<p>SCREW-HINGE Set Screws For Shower Hinges</p>	<p>Regular / Heavy Duty</p> <p>SCREW-WALL HDSCREW-WALL * Wall Mount Screws For Shower Hinges</p>	<p>SCRAN Screws Anchors</p>	<p>5DPIN 5° Reversal Pin</p>
<p>Regular / Heavy Duty</p> <p>PIV5PIN HDPIV5PIN 5° Reversal Pin</p>	<p>BPJEN037 * Jennifer Replacement Full Back Plate</p>	<p>BPJENH037 * Jennifer Replacement "H" Back Plate</p>	<p>BPJEN074 * Jennifer Replacement Short Back Plate</p>
<p>BPVIV037 * Vivian Replacement Full Back Plate</p>	<p>BPVIVH037 * Vivian Replacement "H" Back Plate</p>	<p>BPVIV074 * Vivian Replacement Short Back Plate</p>	<p>BPVIV044 * Vivian Replacement Offset Back Plate</p>
<p>BPBEVH037 * Beverly Replacement "H" Back Plate</p>	<p>BPBEV074 * Beverly Replacement Short Back Plate</p>	<p>BPCOLEH037 * Colette Replacement "H" Back Plate</p>	<p>"H" Notch Allows for Tighter Wall Clearance of Glass Panel</p>









Shower Sweeps - Ultra Clear 3/8" (10mm) Glass



<p>Clear Black</p> <p>SWPBWDR Bottom Wipe with Drip Rail For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPH H Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPL L Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPHS Side/Bottom Seal For 3/8" Glass - 95" Length</p>
<p>Clear Black</p> <p>SWPY Y Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPS Slide Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPB Bulb Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWP90 * 90° Side-Strike Seal For 3/8" Glass - 95" Length</p>
<p>Pre applied tape</p> <p>GAPSWPB Bulb Side Gap Seal For 3/8" Glass - 95" Length</p>	<p>Clear Black</p> <p>SWPT T Seal - 2 Piece Sweep For 3/8" Glass - 95" Length</p>	<p>GAPSWPFIN Double Fin Gap Seal For 3/8" Glass - 95" Length</p>	<p>Pre applied tape</p> <p>GAPSWPG2G Clear Copolymer Strip - 180° For 3/8" Glass - 95" Length</p>

Shower Sweeps – Ultra Clear 1/2" (12mm) Glass



 <p>SWPBWDR12 Bottom Wipe With Drip Rail For 1/2" Glass - 95" Length</p>	 <p>SWPH12 H Seal For 1/2" Glass - 95" Length</p>	 <p>SWPL12 L Seal For 1/2" Glass - 95" Length</p>	 <p>SWPY12 Y Seal For 1/2" Glass - 95" Length</p>
 <p>GAPSWG2G12 Clear Copolymer Strip - 180° For 1/2" Glass - 95" Length</p>	 <p>SWPB12 Bulb Seal For 1/2" Glass - 95" Length</p>	 <p>SWPT12 T Seal - 2 Piece Sweep For 1/2" Glass - 95" Length</p>	 <p>SWPMWS Weather Strip Sweep For 1/2" Glass - 95" Length</p>




Use Grey Goat Hi-Bond Clear Adhesive Tape
For Sweeps Installation Page Number: ____

Shower Sweeps – Ultra Clear Magnetic Sweeps – 3/8" & 1/2" (10-12mm) Glass




Magnetic



SWPM10A *

45° Left Hand Magnetic Profile
For Glass-to-Glass Fits 3/8" to 1/2" Glass


Magnetic



SWPM10C *


90° Magnetic Profile
For Glass-to-Glass fits 3/8" to 1/2" Glass

Magnetic



SWPM10B *

45° Right Hand Magnetic Profile
For Glass-to-Glass fits 3/8" to 1/2" Glass



01 FRAMELESS SHOWER DOOR

Shower Glass Clamps

*Anti slip line from Jennifer Hinges

2"x2" Square Clamps 34


2"x2" Beveled Clamps 35

Transom Glass Clamps 36

1.75"x1.75" Glass Clamps 36

Wall Mount Bracket 37


Sleeve Over Glass Clamps 37



2"x2" Glass Clamps

Square Fixed Panel U-Clamp

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



Key Features

- **Material:** Solid brass for strength and durability
- **Glass Fit:** 3/8" to 1/2" (10-12 mm) tempered glass
- **Hole Size:** Requires 5/8" to 3/4" (16-19 mm) diameter
- **Installation:** Easy with standard tools
- **Adjustment:** Fixed (non-adjustable)
- **Warranty:** 5-year limited warranty

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes



SQU4

Hole-in-Glass Style
Wall Mount Clamp

Heavy Duty



SQU2H

Hole-in-Glass Style
Wall Mount Clamp - 2 Holes



SQC037

Short Offset Hole-in-Glass
Style Wall Mount Clamp



SQC039

Offset Hole-in-Glass Style
Wall Mount Clamp



SQC135

Hole-in-Glass Style
135° Glass to Glass




SQC90

Hole-in-Glass Style
90° Glass to Glass




SQC225

Hole-in-Glass Style
Neo Angle 225° Glass to Glass



SQUT90 *

Hole-in-Glass Style
90° Transom Clamp



2"x2" Glass Clamps

Beveled Fixed Panel U-Clamp

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.




BEVU4
Beveled Hole-in-Glass Style
Wall Mount Clamp



BEVU2H
Beveled Hole-in-Glass Style Wall
Mount Clamp -2 Holes




BEVU037 *
Beveled Short Offset Hole-in-Glass Style
Wall Mount Clamp



BEVU039 *
Beveled Offset Hole-in-Glass Style
Wall Mount Clamp




BEVU90 *
Beveled Hole-in-Glass Style
90° Glass to Glass



BEVU270 *
Beveled Hole-in-Glass Style
90° Glass to Glass



BEVU225 *
Beveled Hole-in-Glass Style
135° Glass to Glass




BEVUT90 *
Beveled Hole-in-Glass Style
90° Transom Clamp

Beveled Transom Glass Clamps

Beveled Movable Panel Clamp




INSTALLER'S
FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272




NEW

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	More Finishes Online



BEVC188
Beveled 180° Movable
Glass to Glass



BEVC186
Beveled 180° Movable Transom
Wall to Glass


Key Features

- Materials:** Constructed from durable solid brass for long-lasting performance.
- Glass Thickness Compatibility:** Suitable for 3/8" to 1/2" (10 to 12 mm) tempered glass.
- Design:** Allows for 180° movement, offering flexibility for various glass panel arrangements.
- Installation:** Easy installation with standard tools.

SQ-Transom Glass Clamps

Square Fixed Panel Clamp

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.




Key Features

- **Materials:** Constructed from durable solid brass for long-lasting performance.
- **Glass Thickness Compatibility:** Suitable for 3/8" to 1/2" (10 to 12 mm) tempered glass.
- **Design:** Allows for 180° movement, offering flexibility for various glass panel arrangements.
- **Installation:** Easy installation with standard tools.

Finishes


Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes



SQ188
180° Movable Transom
Glass to Glass



SQ180
180° Fixed Transom
Glass to Glass



SQ186
180° Movable Transom
Wall to Glass




SQCADJ188 *
Square Adjustable
Glass to Glass Clamp with Hinge

1.75"x1.75" Glass Clamps

Square Fixed Panel U-Clamp

- **Materials:** Made from solid brass for exceptional durability and strength.
- **Glass Thickness Compatibility:** Suitable for 5/16" to 1/2" (8 to 12 mm) tempered glass.
- **Installation:** Easy installation with standard tools.



Finishes

Chrome	Brushed Nickel	Matte Black	Satin Brass	Future Finishes Available
--------	----------------	-------------	-------------	---------------------------



SQU77
Square Hole-in-Glass Style Wall Mount Clamp



RDU77
Round Corner Hole-in-Glass Style Wall Mount Clamp


Wall & Glass Mount Bracket

- **Materials:** Made from solid brass for superior durability and strength.
- **Glass Thickness Compatibility:** Suitable for 5/16" to 1/2" (8 to 12 mm) tempered glass.
- **Design:** Available in Square & Beveled shape for a clean, modern look.
- **Installation:** Easy installation with standard tools



Chrome	Satin Brass	Polished Nickel	Gun Metal	Polished Brass	White
Brushed Nickel	Matte Black	Oil Rubbed Bronze	Brushed Bronze	Antique Brass	More Finishes Online

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



WMB90
Square Wall Mount Bracket - 90°



BEVWMB90
Beveled Wall Mount Bracket - 90°



BEVGMB90 *
Beveled Glass Mount Bracket - 90°



GMB90 *
Square Glass Mount Bracket - 90°

Sleeve Over Glass Clamps

Fixed & Adjustable

- **Material:** Solid brass for durability and corrosion resistance.
- **Glass Compatibility:** Fits 3/8"-1/2" (10-12mm) tempered glass.
- **Design:** Square, sleek design that complements modern shower enclosures.
- **Installation:** Easy to install with standard tools.



Chrome	Satin Brass	Polished Nickel	Gun Metal	Polished Brass	White
Brushed Nickel	Matte Black	Oil Rubbed Bronze	Brushed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.




SLOV092
Sleeve Over Glass Clamp
90° Fixed - Square



SLOV345
Sleeve Over Glass Clamp
90° Adjustable - Square




SLOV045
Sleeve Over Glass Clamp
135° Fixed - Square



SLOVT *
Sleeve Over Glass Clamp
90° "T" Glass Clamp



SLOV044R
Sleeve Over Glass Clamp
Wall to Glass 90° - Offset Right



SLOV044L
Sleeve Over Glass Clamp
Wall to Glass 90° - Offset Left



P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

01 Frameless Shower Door



01 FRAMELESS SHOWER DOOR

Handles & Towel Bars


6"x6" Shower Handles	40	Single sided Towel Bars	44	Tartarian & Atlantis Series	48	Handle Accessories	53
8"x8" Shower Handles	41	12"x12" Shower Handles	45	Single Sided Towel Bars	50		
6"x18" Handle / TB Combo	42	18"X18" Shower Towel Bars	46	Stylish, Slim & Champion Series	51		
6"x24" Handle / TB Combo	43	Sauna Handle	47	Shower Robe Hooks & Knobs	52		



Visit Page: 45
For feature new products.

6"x6" Shower Handles

Tubular / Square / Mitered / Ladder Pull



Key Features

- **Material:** Brass and Plated with anti corrosion
- **Glass Thickness:** 1/4" and 1/2" (6 to 12 mm)
- **Fabrication Required:** 2 X (Hole Size 1/2" (12 mm))
- **Installation:** Allen Key Provided in Box
- **Threading:** M6 X 1.0
- **Warranty:** 5 years



Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



R6X6

Tubular Handle
Back to Back



S6X6

Square Handle
Back to Back

Metal & Vinyl Gaskets Included




M6X6

Mitered Handle
Back to Back



L6X6

Ladder Pull Handle
Back to Back



LSQ6X6

Square Ladder Pull Handle
Back to Back



RNW6X6

Tubular Handle / No Washers
Back to Back



SSP6

Round Pull Handle
Single Sided



INSTALLER'S FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272




Use Only Monolithic Tempered Glass



8"x8" Shower Handles

Tubular / Square / Mitered / Ladder Pull



Key Features

- **Material:** Brass and Plated with anti corrosion
- **Glass Thickness:** 1/4" and 1/2" (6 to 12 mm)
- **Fabrication Required:** 2 X (Hole Size 1/2" (12 mm))
- **Installation:** Allen Key Provided in Box
- **Threading:** M6 X 1.0
- **Warranty:** 5 years



Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



R8X8

Tubular Handle
Back to Back



S8X8

Square Handle
Back to Back

Metal & Vinyl Gaskets Included




M8X8

Mitered Handle
Back to Back



L8X8

Ladder Pull Handle
Back to Back



LSQ8X8

Square Ladder Pull Handle
Back to Back



RNW8X8

Tubular Handle / No Washers
Back to Back




SSP8

Round Pull Handle
Single Sided



6"x18" & 8"x18" Shower Handle Towel Bar Combo

Tubular / Square / Mitered



Key Features

- **Material:** High-quality 1.5mm thick tubular brass construction for durability and corrosion resistance.
- **Dual Functionality:** 6" handle with 18" towel bar for added use.
- **Glass Compatibility:** Fits 6–12 mm (1/4"–1/2") glass panels.
- **Protective Design:** Plastic washers prevent metal-to-glass contact.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



R6X18
R8X18

Tubular Handle / Towel Bar Combo Back to Back



S6X18
S8X18

Square Handle / Towel Bar Combo Back to Back



M6X18
M8X18


Mitered Handle / Towel Bar Combo Back to Back

No Washer **NEW**




RNW6X18
RNW8X18

Tubular Handle / No washer Towel Bar Combo Back to Back



6"x24" Shower Handle Towel Bar Combo

Tubular / Square / Mitered



Key Features

- **Material:** 1.5mm thick tubular brass for durability and corrosion resistance.
- **Dual Functionality:** 6" handle with 24" towel bar for added use.
- **Glass Compatibility:** Fits 6–12 mm (1/4"–1/2") glass panels.
- **Protective Design:** Plastic washers prevent metal-to-glass contact.

Finishes

Chrome	Matte Black	Polished Nickel	Gun Metal	Custom Finishes
Brushed Nickel	Satin Brass	Brushed Bronze	Oil Rubbed Bronze	

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

R6X24

Tubular Handle / Towel Bar Combo Back to Back




S6X24

Square Handle / Towel Bar Combo Back to Back




M6X24 **

Mitered Handle / Towel Bar Combo Back to Back




Note: Visit ggshardware.com
For Glass Fabrication & Product Information.



Single Sided Towel Bars

Tubular / Square / Mitered

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



Key Features

- **Material:** Made from 3/4" (19 mm) diameter heavy brass tubing with a 1.5 mm thickness for enhanced durability.
- **Glass Compatibility:** Designed to fit glass thicknesses ranging from 1/4" to 1/2" (6 to 12 mm).
- **Hole Diameter Required:** Requires 2x 1/2" (12 mm) hole for installation.
- **Protective Design:** Includes 1-1/4" (32 mm) diameter metal washers and plastic washers to protect against glass-to-metal contact.

Finishes




Product	SKU
Tubular Single Sided Towel Bar 18" With No Washers	RNW18 / RNW30*
Square Single Sided Towel Bar 18"	S18
Mitered Single Sided Towel Bar 18"	M18
Square Single Sided Towel Bar 24"	S24
Mitered Single Sided Towel Bar 24"	M24
Tubular Single Sided Towel Bar 24"	R24 / R30*



12"x12" Shower Handles


Round / Square / Mitered

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



R12X12
Tubular Handle Back to Back

**BEST
SELLER**




S12X12
Square Handle Back to Back

Key Features

- **Materials:** High-quality brass construction for strength and corrosion resistance.
- **Design:** Tubular design with a decorative metal washer for a sleek and modern look.
- **Glass Compatibility:** Designed for 1/4" to 1/2" (6 to 12 mm) glass thickness.
- **Protection:** Includes plastic washers to prevent metal-to-glass contact, enhancing durability.

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes



Grey Goat Color Sample Tower
Available at ggshardware.com




18" X 18" Shower Towel Bars

Tubular / Square / Mitered / No Washer

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



Chrome Brushed Nickel Matte Black Satin Brass Polished Nickel Oil Rubbed Bronze Gun Metal Brushed Bronze Antique Brass Polished Brass White Custom Finishes



- **Construction:** 3/4" (19 mm) diameter brass tubing (1.5 mm thick) for maximum strength
- **Design:** Back-to-back towel bar, ideal for both residential and commercial use
- **Glass Compatibility:** Fits glass thicknesses from 1/4" to 1/2" (6 to 12 mm)
- **Hole Diameter:** Requires a 2x (1/2" (12 mm)) hole diameter for installation
- **Protection:** Includes metal washers and plastic washers to protect against glass-to-metal contact


R18X18

Tubular Towel Bar Combo Back to Back



S18X18

Square Towel Bar Back to Back



M18X18

Mitered Towel Bar Combo Back to Back



NEW

RNW18X18


Tubular Towel Bar With No Washers Back to Back



24" x 24" Shower Towel Bar

Tubular / Square / Mitered / No Washer

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



- **Construction:** 3/4" (19 mm) diameter brass tubing (1.5 mm thick) for maximum strength
- **Design:** Back-to-back towel bar, ideal for both residential and commercial use
- **Glass Compatibility:** Fits glass thicknesses from 1/4" to 1/2" (6 to 12 mm)
- **Hole Diameter:** Requires a 2x (1/2" (12 mm)) hole diameter for installation
- **Protection:** Includes metal washers and plastic washers to protect against glass-to-metal contact

BEST
SELLER

R24X24

Tubular Towel Bar With Washers - Back to Back



S24X24

Square Towel Bar - Back to Back



M24X24

Mitered Towel Bar - Back to Back



Sauna Handle

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



SAUN19LP12
Sauna Handle 12" - Square Ladder Pull Style

Key Features

- **Heat and Moisture Resistant:** Constructed from materials designed to thrive in sauna conditions.
- **Grip:** Ergonomic design for a secure, comfortable hold.
- **Sleek Design:** Perfectly suited for modern and traditional sauna aesthetics.
- **Hustle Free Installation:** Includes all necessary mounting hardware for easy installation.

Finishes



Don't Burn Your Hand!
Use Grey Goat Sauna Handles.



SAUN25LP12
Sauna Handle 12" Tubular Ladder Pull Handle



SAUN33R17
Sauna Handle 17" Tubular Ladder Pull Handle



SAUN30S19
Sauna Handle 19" Square Handle



SAUN19LP24
Sauna Handle 24" Square Ladder Pull Handle



SAUN25LP24
Sauna Handle 24" Tubular Ladder Pull Handle



SAUN38S31
Sauna Handle 31" Square Handle



SAUN39R31
Sauna Handle 31" Tubular Ladder Pull Handle



SAUN39R47
Sauna Handle 47" Tubular Ladder Pull Handle


Tartarian & Atlantis Series – Towel Bar

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.



Check our website




TART6X18 *
TART6X24 *
TART8X18 *
TART8X24 *

Tubular Handle Back to Back

Product Overview

- Decorative Design
- Available 6" or 8" Pull Handles, with 18" or 24" Towel Bars
- For Use with 1/4" to 1/2" Tempered Glass
- Requires Three 1/2" Diameter Holes for Installation
- Includes Decorative Metal Washers
- Solid Brass Material, with High Quality Plating

Finishes



Check our website




ATLA6X18 *
ATLA6X24 *
ATLA8X18 *
ATLA8X24 *

Square Handle Back to Back


Product Overview

- Heavy Duty 3/4" Diameter Tubular Construction
- For Use with 1/2" to 1/2" Tempered Glass
- Requires Three 1/2" Diameter Holes for Installation
- Available in Seven Popular Finishes
- No Metal Washers for a Seamless Look
- M6-1.0 Thread

Finishes



For glass fabrication details, CADfiles, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



**USE ONLY
MONOLITHIC
TEMPERED
GLASS**

Tartarian Series

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.




TART8X8 **

Ornate Back to Back
Pull Handles

Product Overview

- Designed for 1/4" to 1/2" (6 mm to 12 mm) Tempered Glass
- Includes Decorative Metal Washers
- Available in Seven Popular Finishes
- Requires Two 1/2" Diameter Holes for Installation

Finishes



Atlantis Series – Handle


Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.

Product Overview

- Unique Arched Design Adds Flair to Frameless Shower
- Designed for use with 1/4" - 1/2" (6 mm to 12 mm) Tempered Glass
- 2x (1/2" Diameter Holes) required ; 6" or 8" CTC

Finishes




ATLA6X6 **

Tubular Style
Back to Back Pull Handle



ATLA8X8 **

Tubular Style
Back to Back Pull Handle



For glass fabrication details, CAD files, and the latest product information, please visit our website.
 Stock and finish availability may vary by product.

Tartarian Series – Towel Bar


Atlantis Series – Towel Bar

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.




- Sleek, Washer-Free Design for a Clean, Minimalist Look
- Durable 3/4" (19 mm) Diameter Tubular Brass – 1.5 mil Wall Thickness
- Available in Several Popular Finishes – Custom Finishes Upon Request
- Offered in Two Standard Sizes



TART18X18 / TART24X24 *

Tubular Handle Back to Back



ATLA18X18 / ATLA24X24 *

Tubular Handle Back to Back

Single Sided Towel Bars

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



- **Construction:** Made from 3/4" (19 mm) diameter heavy brass tubing with a 1.5 mm thickness for enhanced durability.
- **Glass Compatibility:** Designed to fit glass thicknesses ranging from 1/4" to 1/2" (6 to 12 mm).

- **Hole Diameter Required:** Requires a 1/2" (12 mm) hole for installation.



SLIM24 **

Single-Sided Slim Style Towel Bar



TART24 **

Single-Sided Tartarian Style Towel Bars



ATLA24 **

Single-Sided Atlantis Style Towel Bars



SSLP18 & SSLP24 **

Single-Sided Ladder Pull Style Towel Bars



Stylish Series Handles

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.



- **Materials:** High-quality brass construction for strength and corrosion resistance.
- **Design:** Tubular design with a 1" rounded decorative metal washer for a sleek and modern look.
- **Glass Compatibility:** Designed for 1/4" to 1/2" (6 to 12 mm) glass thickness.
- **Protection:** Includes plastic washers to prevent metal-to-glass contact, enhancing durability.



STY6X6 *
Stylish Series
Back to Back Pull Handles



STY8X8 *
Stylish Series
Back to Back Offset Pull Handles



STYOS6X6 *
Ladder Pull Handle
Back to Back



STYOS8X8 *
Ladder Pull Handle
Back to Back

Slim Series Handles

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.



SLIM6X6 *
SLIM8X8 *
Pull Handle
Back to Back




D-Miter Series Handles

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.



DMIT6X6 *
DMIT8X8 *
Flat Round Mitered Series
Back to Back Pull Handles



Champion Series

Please note that these handles are not currently in stock.

For real-time inventory updates and availability, please refer to our website ggshardware.com.



CHAM6X6 *
Tubular Handle Back to Back



CHAM8X8 *
Tubular Handle Back to Back

Key Features


















- Design Enhances the Elegance of Any Shower
- 1-1/2" Decorative Rosettes Provide Additional Detail
- 6" or 8" CTC Hole Spacing (2) 1/2" Diameter Holes in Glass
- Heavy Duty 3/4" Diameter Tubular Construction
- Popular Finishes Available
- Custom Finishes Also Available

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Shower Door Knobs & Combo & Robe Hooks



- **Material:** Solid Brass for superior strength and corrosion resistance
- **Glass Thickness Range:** Fits 1/4" - 1/2" (6mm - 12mm) glass for versatile applications
- **Height:** 1" overall height for a sleek, minimalist design


<p>BEST SELLER</p>  <p>DK100 100 Style Back to Back Knob</p>	<p>NEW</p>  <p>DK106 106 Style Back to Back Knob</p>	 <p>DK140 140 Style Back to Back Knob</p>	 <p>DKSQ SQ Style Back to Back Knob</p>	 <p>DK160 160 Style Back to Back Knob</p>
 <p>DK180 180 Style Back to Back Knob</p>	 <p>DKSQ2 SQ2 Style Back to Back Knob</p>	 <p>DK118 * Back-to-Back RoundShower Knobs</p>	 <p>DK053 * Back-to-Back Fluted Shower Knobs</p>	 <p>DK046 * Back-to-Back Funnel Shower knobs</p>
 <p>DK109 * Back-to-Back Bongo Shower Knobs</p>	<p>NEW</p>  <p>R18KNOB Door Knob with 18" Towel Bar Combo / Towel Bar Combo Back to Back</p>		 <p>R18DK100 / R24DK100 * Shower Towel Bar With DK100 Knob</p>	
 <p>GRH01 Shower Robe Hooks Round Trunk Style</p>	 <p>RHRD Shower Robe Hooks Round Style</p>	 <p>RH7SQ * Shower Robe Hooks Square Style</p>	 <p>RH6SO * Shower Robe Hooks Sleeve Over Style</p>	

Handle Accessories

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



















Finishes



Key Features

- **Complete Kit:** Includes washer and stud for secure handle mounting
- **Application:** Perfect for replacements or upgrades on frameless shower doors


 <p>RSPACCLR * Spacer For Shower Handles & Towel Bar</p>	 <p>RGAS1CLR Gasket For Shower Handles & Towel Bar</p>	<p>1-1/4" Dia Commercial</p>  <p>LPHS Cap For Single Sided Handles</p>	<p>1-1/4" Ø Shower</p>  <p>RLMHS Cap With Washer For Single Sided Handles</p>
 <p>THM6X1 * 1-9/16" Long Threaded Connecting Rod</p>	<p>1-1/4" Ø Shower</p>  <p>RWRH Round Washer/Stud Kit - 1-1/4" Diameter</p>	<p>1"x1" Commercial</p>  <p>SWSLLP Square Washer/Stud Kit - 1"x1"</p>	<p>1"x1" / Upto 2" Commercial</p>  <p>2SWSLLP Square Washer/Stud Kit - Upto 2" Thick Door</p>
<p>1"x1" Commercial</p>  <p>SLPSLHS Washer Kit - Square Leg</p>	<p>13/16" x 13/16" Shower</p>  <p>SWSH Square Washer/Stud Kit</p>	<p>13/16" x 13/16" Commercial</p>  <p>SHS Washer Kit</p>	<p>1-1/4" Ø Commercial</p>  <p>2RWLLP Round Washer/Stud Kit - Upto 2" Thick Door</p>
<p>1-1/4" Ø Commercial</p>  <p>RWLLP Round Washer/Stud Kit - 1-1/4" Diameter</p>	<p>1-1/4" Ø Commercial</p>  <p>LPHS Washer Kit for Round and Mitered Shower Ladder Pull Series</p>	<p>1-1/4" Ø Shower</p>  <p>RLMHS Washer Kit for Round and Mitered Shower Ladder Pull Series</p>	



01 FRAMELESS SHOWER DOOR

Shower U Channels

Shower U-Channel 55

Shower End Cap & Threshold 55



		U Channel Length	Glass Thickness	SKU
<div><div>6mm to 12mm / 98"</div><p>UC9810 98" Long Shower U Channel For 6 to 12mm Glass</p></div>	98"	6mm	UC986	
		10mm	UC9810	
		12mm	UC9812	
<div><div>6mm to 12mm / 144"</div><p>UC14412 144" Long Shower U Channel For 6 to 12mm Glass</p></div>	144"	6mm	UC1446	
		10mm	UC14410	
		10mm - 1"	UCH14410	
		12mm	UC14412	
		12mm - 1"	UCH14412	

* For the most up-to-date product availability, visit our website.

Shower U-Channel



Finishes



Product Overview

- **Glass Compatibility:** Exclusively designed for 6mm, 10mm or 12mm (1/4", 3/8" or 1/2") glass panels.
- **Depth:** 3/4" to 1" depth enhances glass visibility and creates a clean, low-profile look.
- **Length:** Stocked in convenient 98" or 144" lengths, ideal for a variety of installations.
- **Durability:** Manufactured with corrosion-resistant materials, ensuring longevity and performance.
- **Versatile Installation:** Can be mounted on floors, walls, or ceilings, adapting to your design needs.
- **Ease of Use:** Designed for quick and straightforward installation, making it ideal for residential projects.



Shower End Cap & Threshold




Finishes



Product Overview

- **Glass Compatibility:** Suitable for 3/8" (10mm) & 1/2" (12mm) glass
- **Material:** Constructed from 6063-T5 Aluminum Alloy for strength and longevity
- **Easy Fit:** Simple and efficient to install for a quality finish



01 FRAMELESS SHOWER DOOR

Mirror L & J Channels

Mirror L & J Channels 57

Shower Van Mirror Clips 57



Mirror L & J Channels




Finishes



Product Overview

- Mirror Channels are designed for precision, durability, and a sleek finish.
- Deep Nosed J-Molding is usually used for top mirror installation
- 12FT (144") Length
- 40 Per Case



Shower Van Mirror Clip Sets



LED Mirrors



Overview

Voltage: 120 – 277V AC
Lumens: 3300 LM
Wattage Specs: 29W @ 120V AC
Certifications: UL Listed
Grey Goat Hardware - Outer Etched LED Mirror

Specification


Elevate your interior with Grey Goat's premium Outer Etched LED Mirror—engineered for high performance, ambient lighting, and visual appeal. Designed with outer-etched side lighting, this mirror delivers consistent brightness and reduced shadowing across its crystal-clear rectangular surface. The soft halo illumination creates a relaxing and elegant atmosphere, making it ideal for use in bathrooms, hotel lobbies, salons, residential vanities, and upscale commercial spaces.

Key Features


Outer-edge etched LED light for uniform illumination Sleek, modern frame adds style and depth to any room
Energy-efficient and built for long-term use. Easy installation for both residential and commercial applications




LEDM2BSF- Two Bar With Shelf *




LEDMOER - Outer Etched - Rectangular *



LEDM2B - Two Bar *



LEDMIER - Inner Etched *



LEDMOES - Outer Etched - Square *



LEDMNE - Backlit - No Etch *



01 FRAMELESS SHOWER DOOR

Shower Header Kits

Header Kit 60


Header Accessories 61



Shower Header Kit



Remember To Purchase
GOAT 6" Shank For Easy
Header Installation! Page: 272



Key Features

- **Glass Compatibility:** Suitable for 3/8", and 1/2" (10, and 12 mm) glass.
- **Material:** Constructed from 6063-T5 aluminum alloy for superior strength and durability.
- **Design:** Features a 1-1/4" (32 mm) face for an enhanced, more visible sightline.

Included Components

- 1x66", 98" or 144" Piece of Aluminum Header Extrusion
- 1x36" (914mm) Piece of Aluminum Snap-In Filler for Door Pocket
- 2x Brass Wall Mounting Brackets
- 1x Clear Vinyl Gasket

Header Length	SKU NO.
66"	HK66
98"	HK98
144"	HK144

Finishes

Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

HK66, HK98, HK144

Adjustable Header Kit



Adjustable Pivot
Page No. 26



Key Features

- **Glass Compatibility:** Suitable for 5/16", 3/8", and 1/2" (8, 10, and 12 mm) glass.
- **Material:** Constructed from 6063-T5 aluminum alloy for superior strength and durability.
- **Design:** Features a 1-1/4" (32 mm) face for an enhanced, more visible sightline.

Included Components

- 144" pieces of aluminum header extrusion
- 36" (914 mm) piece of aluminum snap-in filler for door pocket
- One pack of two Brass Wall Mounting Brackets [HWMB]
- Clear vinyl for 5/16" (8 mm) and 3/8" (10 mm) glass

Finishes










Chrome	Satin Brass	Gun Metal	Polished Brass
Brushed Nickel	Polished Nickel	Brushed Bronze	White
Matte Black	Oil Rubbed Bronze	Antique Brass	Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

HK144ADJ

Header Kit Accessories



<p>Regular Duty</p>  <p>HA01 Shower Header Adapter Block</p>	<p>Heavy Duty</p>  <p>HDHA01 Shower Header Adapter Block</p>	<p>48" Piece / 500' Length Roll</p>  <p>HGAS48 / HGAS500 Clear Vinyl Gasket</p>	<p>3FT (36 inches)</p> <p> Available in all finishes</p>  <p>HF09 Shower Header Filler</p>
 <p>HC90 Shower Header Corner - 90° Fixed</p>	 <p>HC135 Shower Header Corner - 135° Fixed</p>	 <p>HCADJ Shower Header Corner - Adjustable</p>	 <p>HWMB Brass Wall Mounting Brackets</p>



01 FRAMELESS SHOWER DOOR

Flat Bar For Grid Showers



Aluminum Flat Bars - Grid Showers 63




Aluminum Flat Bars – Grid Showers



Finishes



FB98
3/4" Flat Bar For Grid Showers - 98" Length
3/4" Wide X 1/16" Thick



FB144
3/4" Flat Bar For Grid Showers - 144" Length
3/4" Wide X 1/16" Thick




Black Foam Tape

Dimension	SKU
1/2" W - 32.8FT L - 1/4" Thick	FT1412BL
3/4" W - 32.8FT L - 1/4" Thick	FT1434BL
1/2" W - 65.6FT L - 1/8" Thick	FT1812BL
1/2" W - 131.2FT L - 1/16" Thick	FT11612BL



3M Clear Adhesive Tape

Dimension	SKU
1/2" W - 108FT L - 0.040" Thick	AHB04012
1/4" W - 108FT L - 0.040" Thick	AHB04014
1/2" W - 32FT L - 0.040" Thick	AHB04012-32
1/4" W - 32 FT L - 0.040" Thick	AHB04014-32
3/4" W - 108FT L - 0.050" Thick	AHB05034



P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

01 Frameless Shower Door



01 FRAMELESS SHOWER DOOR

Shower Support Bar

Shower Support bar - Round & Square 66

Glass Shower Door Stoppers 67



Shower Support Bar – Round – Adjustable



Finishes



Product Overview

- **Adjustable Length:** 30"-42" bar for flexible fit across shower setups
- **Material & Finish:** 3/4" brass tubular bar with solid end caps for strength and polish
- **Installation Type:** For glass-to-glass setups, supporting frameless shower panels
- **Glass Compatibility:** Fits 3/8" (10 mm) tempered glass

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



SUPC
Support Bar Connector 90°



SUPB22 *
Support Bar Bracket 22°

Shower Support Bar – Square – Adjustable



Please note that these handles are not currently in stock.


For real-time inventory updates and availability, please refer to our website ggshardware.com.

Finishes



Product Overview

- **Materials:** High-quality brass construction for strength and corrosion resistance.
- **Design:** Square design with a decorative metal washer for a sleek and modern look.
- **Glass Compatibility:** Designed for 1/4" to 1/2" (6 to 12 mm) glass thickness.
- **Protection:** Includes plastic washers to prevent metal-to-glass contact, enhancing durability.



Glass Shower Door Stoppers



Finishes



Product Overview

- **Glass Compatibility:** Designed for 10 mm tempered glass
- **Product Type:** Shower door stop for secure panel positioning
- **Easy Installation:** No glass fabrication required
- **Design Options:** Available in both square and beveled profiles



SQDS10

Square Glass Mount Swinging Shower Door Stop




BVDS10 *

Beveled Glass Mount Swinging Shower Door Stop

Privacy Glass Door Lock with Indicator



Finishes




Product Overview

- **Glass Compatibility:** Designed for monolithic tempered glass thicknesses of 5/16" to 1/2" (8 to 12 mm).
- **Versatile Applications:** Suitable for glass-to-wall or 180° glass-to-glass installations with an optional matching keeper.
- **Indicator Functionality:** Displays Red when locked and Green when open for easy status identification.
- **Emergency Access:** Includes a low-profile screw on the exterior for added safety upon emergency to open from exterior.
- **Comprehensive Kit:** Comes with screws, anchors, gaskets, and glass mount keeper.



GTDLGM

Privacy Glass Door Lock for Washroom - Thumbturn



P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies


01 Frameless Shower Door



01 FRAMELESS SHOWER DOOR

Sliding Door Kits

TRANQUILITY Series	70	TRANQUILITY Heavy Duty Series	74
CAM Series	71		
HYDRO Series	72		
LUNA Series	73		



Stainless Steel / Single Door Slide Tranquility Series

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



TQ78
Tranquility Series

Kit Includes

- 1 x Header Bar (78")
- 2 x Track Holders
- 2 x Door Stopper
- 1 x L-Seal Jamb
- 4 x Roller
- 1 x Thru-Glass Pull
- 2 x Track Fittings
- 1 x Floor Guide

Key Features

- Materials:** Made from high-quality stainless steel for long-lasting durability.
- Configuration:** One sliding door and one fixed panel, suitable for use with 5/16" to 3/8" (8-10mm) tempered safety glass (glass not included).
- Smooth Door Operation:** Equipped with 4 anti-lift rollers for quiet, smooth sliding, ensuring easy opening and closing.


Specification

SKU NO.	Glass Thickness	MAX. Door Size	MAX. Door Weight
TQ78	5/16" to 1/2"	Up to 30"(762mm)	Up to 88lbs (40kg)
HDTQ78	(8mm to 12mm)	Up to 30"(762mm)	Up to 100lbs (50kg)

Finishes

Polished Stainless	Matte Black	Red Copper	Gun Metal	White
Brushed Nickel	Satin Brass	Oil Rubbed Bronze	Antique Brass	Custom Finishes


Included in Kit



**TQH78
TQH120**
Header Bar (78" & 120" Length)

Included in Kit

*Good for Lever adjustment



TQTH
Track Holder

Included in Kit



TQDS
Door Stopper

Included in Kit

*Pre applied Hi-bond tape



LJAMB
Multi-Purpose L-Jamb

Included in Kit



TQRO
Roller

Included in Kit




GLASSPULL
Thru Glass Pull

Included in Kit



TQTF
Track Fittings

Included in Kit



TQFG
Floor Guide

Sold Separate



TQB092
90° Corner Bracket

Sold Separate



TH98
Threshold (98" Length)

Sold Separate



TQ90R
90° Glass Return

Order Online Sample Kit



TRANQ78-SAMPLE
Tranquility Kit Sample

Brass / Double Door Slide CAMI Series

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



*Premium Double bypass system

CAMI73
CAM Series

Kit Includes

1 x Stainless Steel Header(73")
8 x Stainless Rollers
2 x Door Stoppers
2 x Track Holder Fittings
1 x Bottom Guide
2 x Towel Bar(24" Single-Sided)
2 x Clear L-Jambs
1 x Bottom Sweeps
1 x Tool Kit

Key Features

- **Premium Material:** Crafted from brass for durability and corrosion resistance.
- **Glass Compatibility:** Designed for 5/16" to 3/8" (8 mm to 10 mm) tempered safety glass (glass not included).
- **Elegant Design:** Combines sleek style with functional precision for modern frameless showers.

Specification

SKU NO.	Glass Thickness	MAX. Door Weight	MAX. Door Size
CAMI73	5/16" to 1/2" (8mm to 12mm)	Up to 84lbs (38 kg)	Up to 37" (940 mm)

Finishes



Included in Kit



CAMIH73
Header Bar (73" Length)

Included in Kit



CAMIRO
Rollers

Included in Kit



CAMIDS
Door Stoppers

Included in Kit




CAMITH
Track Holder

Included in Kit



CAMIFG
Bottom Guide

Included in Kit



R24
24" Tubular Single Sided Towel Bar


Included in Kit

*Pre applied HI-bond tape



LJAMB
Multi-Purpose L-Jamb

Included in Kit



CAMIBSWP
Bottom Sweep

Included in Kit



CAMI-TOOL
Tool Kit


Sold Separate



CAMI90R
90° Glass Return



**USE ONLY
MONOLITHIC
TEMPERED
GLASS**



**INSTALLER'S
FAVORITE!**
GOAT Drill & Spade Bits,
Refer Page Number: 272

Single Door Slide HYDRO Series



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



HYDRO84
HYDRO Series

Kit Includes

- 1 x Header Bar (84")
- 1 x Bottom Door Guide
- 1 x Drill Guide
- 2 x Fixed Plate Fittings
- 2 x Hangers Set
- 1 x L-Seal
- 2 x Wall Mount & Stopper

Key Features

- **Material:** Made from high-quality stainless steel for durability and resistance to corrosion.
- **Configuration:** 84" long sliding door kit designed for seamless installations.
- **Smooth and Quiet Operation:** Equipped with 2 rollers for quiet door movement, ensuring effortless opening and closing.

Specification

SKU NO.	Glass Thickness	MAX. Door Weight	MAX. Door Width
HYDRO84	5/16" to 3/8" (8mm to 10mm)	Up to 88lbs (40kg)	Up to 30" (762mm)

Finishes



Included in Kit



HYDROH84 *
Header Bar - 84" Length

Included in Kit



HYDRODG *
Drill Guide

Included in Kit



HYDROFPF *
Fixed Plate Fitting

Included in Kit



HYDROHANGER *
Hanger

Included in Kit



HYDROFG *
Bottom Door Guide


Included in Kit

*Pre applied Hi-bond tape



LJAMB
Multi-Purpose L-Jamb

Included in Kit



HYDRODS *
Wall Mount & Stopper

Sold Separate



TH98
Threshold - 98" Length

Sold Separate



HYDRO05
90° Wall-to-Glass Bracket


Sold Separate



HYDRO90
90° Glass-to-Sliding Track



**USE ONLY
MONOLITHIC
TEMPERED
GLASS**



**INSTALLER'S
FAVORITE!**
GOAT Drill & Spade Bits,
Refer Page Number: 272

Single Door Slide LUNA Series

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



LUNA78
LUNA Series

Kit Includes

- 1x Header Bar
- 4x Stainless Rollers
- 1x Door Stopper
- 2x Wall Mount Fittings
- 2x Track Holder Fitting
- 1x Bottom Floor Guide
- 1x Clear L-Seal Jamb
- 1x Bottom Sweep

Key Features

- **Materials and Dimensions:** Made from high-quality stainless steel for durability and resistance to corrosion.
- **Configuration:** 78" long sliding door kit designed for seamless installations.
- **Smooth and Quiet Operation:** Equipped with 4 rollers for quiet door movement, ensuring effortless opening and closing.

Specification

SKU NO.	Glass Thickness	MAX. Door Weight	Material
LUNA78	3/8" to 1/2" (10mm to 12mm)	Do not exceed 100lbs (45 kg) in weight	Stainless Steel

Finishes

Chrome	Matte Black	Polished Nickel	Gun Metal	Custom Finishes
Brushed Nickel	Satin Brass	Brushed Bronze	Oil Rubbed Bronze	

Included in Kit



LUNAH78
Header Bar - 78" Length

Included in Kit



LUNARO
Roller

Included in Kit



LUNADS
Door Stopper

Included in Kit



LUNAWM
Wall Mount

Included in Kit



LUNATF
Track Holder Fitting

Included in Kit



LAGFG
Floor Guide

Included in Kit

*Pre applied Hi-bond tape



LJAMB
Multi-Purpose L-Jamb

Sold Separate



CAMIBSWP
Bottom Sweep


Sold Separate



LUNA90R
90° Glass Return Kit



**USE ONLY
MONOLITHIC
TEMPERED
GLASS**



**INSTALLER'S
FAVORITE!**
GOAT Drill & Spade Bits,
Refer Page Number: 272

Double Door Slide

Tranquility Series – Heavy Duty



HDTQ78

Heavy Duty Tranquility Series

Kit Includes

1 x Header Bar
2 x Track Holders
2 x Door Stopper
1 x L-Seal Jamb
4 x Roller
1 x Thru-Glass Pull
2 x Track Fittings
1 x Floor Guide

Key Features

- **Materials and Dimensions:** Constructed from high-grade stainless steel for exceptional durability and corrosion resistance.
- **Configuration:** One sliding door and one fixed panel, designed for use with 12mm tempered safety glass (glass not included).
- **Smooth and Quiet Operation:** Includes 4 anti-lift rollers for quiet, easy door movement and effortless operation.

Specification

SKU NO.	Glass Thickness	MAX. Door Size	MAX. Door Weight
HDTQ78	1/2" (12mm)	Up to 30"(762mm)	Up to 100lbs (50kg)

Finishes

Polished Stainless	Matte Black	Polished Nickel	Gun Metal	Polished Brass	Custom Finishes
Brushed Nickel	Satin Brass	Oil Rubbed Bronze	Antique Brass	White	

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Included in Kit

TQH78 TQH120

Header Bar - 78" Length

Included in Kit

*Good for Lever adjustment

TQTH

Track Holder

Included in Kit

TQDS

Door Stopper

Included in Kit

*Pre applied Hi-bond tape

LJAMB

Multi-Purpose L-Jamb

Included in Kit

TQRO

Roller

Included in Kit

GLASSPULL

Thru Glass Pull

Included in Kit

TQTF

Track Fittings

Included in Kit

TQFG

Floor Guide

Sold Separate

TQB092

90° Corner Bracket

Sold Separate

TH98

Threshold (98" Length)

Sold Separate

TQ90R

90° Glass Return

Order online sample kit

TRANQ78-SAMPLE

Tranquility Kit Sample

P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

01 Frameless Shower Door




P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

01 Frameless Shower Door



01 FRAMELESS SHOWER DOOR

Stock Glass Doors

Shower Stock Door - 24" Width 78

Shower Stock Door - Sliding Door 80

Shower Stock Door - 26" Width 79

Shower Shelves & Shelf Clamps 81




Shower Stock Door – 24" Width



Glass Thickness: 3/8" (10mm) Tempered Safety Glass.

Beveled and Polished Edges, Prefabricated for either 6" or 6×18" handle combinations

24inches Width 2H




X Height

SKU

64-2H	SD24X64-2H
66-2H	SD24X66-2H
68-2H	SD24X68-2H
70-2H	SD24X70-2H
72-1H	SD24X72-1H
72-2H	SD24X72-2H
74-2H	SD24X74-2H
76-2H	SD24X76-2H
78-2H	SD24X78-2H
80-2H	SD24X80-2H
82-2H	SD24X82-2H
84-2H	SD24X84-2H

24inches Width 3H



X Height

SKU

64-3H	SD24X64-3H
66-3H	SD24X66-3H
68-3H	SD24X68-3H
70-3H	SD24X70-3H
72-3H	SD24X72-3H
74-3H	SD24X74-3H
76-3H	SD24X76-3H
78-3H	SD24X78-3H
80-3H	SD24X80-3H
82-3H	SD24X82-3H
84-3H	SD24X84-3H


Shower Stock Door – 26" Width



Glass Thickness: 3/8" (10mm) Tempered Safety Glass.

Beveled and Polished Edges, Prefabricated for either 6" or 6x18" handle combinations

26inches Width 2H




X Height

SKU

64-2H	SD26X64-2H
66-2H	SD26X66-2H
68-2H	SD26X68-2H
70-2H	SD26X70-2H
72-2H	SD26X72-2H
74-2H	SD26X74-2H
76-2H	SD26X76-2H
78-2H	SD26X78-2H
80-2H	SD26X80-2H
82-2H	SD26X82-2H
84-2H	SD26X84-2H

26inches Width 3H



X Height



SKU

64-3H	SD26X64-3H
66-3H	SD26X66-3H
68-3H	SD26X68-3H
70-3H	SD26X70-3H
72-3H	SD26X72-3H
74-3H	SD26X74-3H
76-3H	SD26X78-3H
78-3H	SD26X78-3H
80-3H	SD26X80-3H
82-3H	SD26X82-3H
84-3H	SD26X84-3H

Shower Stock Door – For Sliding Door


For Tranquility Stock Doors



30inches Fixed Panel	X Height	SKU	30inches Width 1H Sliding Panel	X Height	SKU
	60-PANEL	SD30X60PANEL		60-1H	SD24X64-2H
	62-PANEL	SD30X62PANEL		62-1H	SD30X62DOOR-1H
	66-PANEL	SD30X66PANEL		66-1H	SD30X66DOOR-1H
	76-PANEL	SD30X76PANEL		76-1H	SD30X76DOOR-1H
				76-2H	SD30X76DOOR-2H



Shower Glass Shelves (3/8")



SGS10X10

Stock Glass Shelves
10" X 10" - Round (Quarter Circle)



SGS9X9


Stock Glass Shelves
9" X 9" - Round (Quarter Circle)

Shower Shelf Clamps




- **Material:** Solid Brass for exceptional strength and resistance to corrosion
- **Glass Thickness Range:** 1/4" to 3/8" (6 to 10 mm) to accommodate a variety of glass shelf thicknesses
- **No Glass Fabrication Required:** Clamps tighten easily using nylon-tipped screws, streamlining installation without the need for custom glass fabrication

Finishes



SCSQ

Shower Shelf Clamp - Square
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



SCRD

Shower Shelf Clamp - Round
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



SCFL *

Shower Shelf Clamp - Falcon
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



Factory Order Program

Secure your supply, scale your savings.

If you have recurring demand or are planning a large project rollout, our Factory Order Program is built to serve your timeline and your bottom line.

Program Highlights:

- Direct-from-factory pricing for large-scale commitments
- Flexible order forecasting and inventory planning
- Custom labeling and product configurations
- Scheduled shipments based on your project phases
- MOQ (Minimum Order Quantity) applies – ask us for details

Contact us to enroll: sales@ggshardware.com

Speak with our program manager: 1-905-264-1600

Ask about our MOQ charts, lead time options, and program perks.

Ideal for:

- OEM partners
- Large-scale distributors
- International buyers
- Developers managing multiple sites

Do you have large projects?

- Condominiums
- Residential Developments
- High-Rise Buildings
- Sub-Divisions

Want to Save Money?

Our program helps you cut costs on large builds without compromising on product quality or logistics.

GGH Extra Value

- Volume Discounts
- Reliable Product Quality
- Consistent Lead Times
- Dedicated Project Support



01 FRAMELESS SHOWER DOOR

Grey Goat Color Sample Kit

Grey Goat Color Samples Kit 84

Get Yours Today!




Grey Goat Color Samples Kit

Explore upcoming color finishes on our website.



Frameless Shower Hardware



This color tower was created for one-time distribution only. For the most up-to-date selection of available finishes, please visit our website at ggshardware.com.


Railing Hardware



Commercial Finishes



Future Colors



*These finishes aren't listed on our website yet — but they're available in our color chain. If you're interested, we'd be happy to provide upon request!

Don't have an account?

Sign up now at GGSHARDWARE.COM and get approved by one of our representatives same day! Check Page #4 for more info!

Need Help ?


Call our office today and speak to one of our friendly specialist



02 RAILING HARDWARE

ARCH-LOC™

ADJUSTABLE BASE SHOE SYSTEM



Arch-Loc® Series	86
Arch-Loc® Series - 69 Series	88
Arch-Loc® Series - 86 Series	89
Accessories & Installation Application	90

2° Tilt Adjustment
Quick & Easy Installation
Save Time and Money

Canadian Patent Number: 2962407
Engineered & Stamped - Canadian National Building Code (Per Province)



Manufactured by




Distributed by






FAST • EASY • ENGINEERED

Revolutionize Your Installations with our ARCH-LOC™ System. Our ARCH-LOC™ Base Rail Systems are **engineered** to deliver unmatched **ease of installation, superior precision, and reliable durability**. With **2° tilt adjustment** in each direction, achieved entirely from the inside of the balcony, this innovative system simplifies alignment and reduces installation time by up to threefold compared to traditional methods.



2° Tilt Adjustment
Quick & Easy Installation
Save Time and Money



Features and Benefits

Engineered: Engineered and Stamped to meet **National Building Code & Miami-Dade County NOA's**.

Glass Thickness: Suitable for glass from 1/2" - 27/32" (12mm-21.4 mm) thickness.

Available Length: 10FT & 20FT.

Premium Quality Materials: Constructed from high-strength, pure aluminum for exceptional durability.

Height From Ground: 1-1/2" above ground level.

Flexible Applications: Top-mounted, side-fixed, or recessed installations to suit diverse needs.

Faster Installations: Patented rotating pressure plate system ensures a smooth and efficient setup.

Canadian Patent: 2962407

P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

02 Railing Hardware

ARCH-LOC™
FULL KIT DETAILS



Residential & Commercial Applications	69 Series - Top Mount 1/2" (12 mm)	69 Series - Side Mount 1/2" (12 mm)	86 Series - Top Mount 19/32" - 11/16" (15mm-17mm) 3/4" - 27/32" (19mm-21mm)
Base Shoe Type <ul style="list-style-type: none"> • Top Mount • Side Mount • Recessed Mount 			
Technical Drawing			

Kit Includes

FAST • EASY • ENGINEERED

Shoe Length	10 FT	20 FT	10 FT	10 FT
Glass Thickness	1/2" (12 mm)			19/32" - 11/16" (15mm-17mm) 3/4" - 27/32" (19mm-21mm)
Height From Ground	1 - 1/2"	1 - 1/2"	1 - 5/8"	1 - 1/2"
No. of Claddings	2 X 10 FT	4 X 10 FT	2 X 10 FT	2 X 10 FT
Glass Kits	10 pcs	20 pcs	10 pcs	10 pcs
Joining Pins	4 pcs	8 pcs	4 pcs	4 pcs
Stabilizing Washers	10 pcs	20 pcs	10 pcs	10 pcs
Gap Rubber	1 X 3.94"	2 X 3.94"	1 X 3.94"	1 X 3.94"
Flat Washers	10 pcs	20 pcs	10 pcs	10 pcs
End Caps	2	2	2	2

69 Series – Components & Accessories

Suitable for glass from 3/8" - 1/2" (10mm-12 mm) thickness



Finishes & Specification



Canadian Patent Number: 2962407
 Engineered and Stamped - National / Ontario Building Code

- Engineered and stamped **National and Ontario Building Codes & Miami-Dade County NOA's**.
- **Material:** High Strength Pure Aluminum Construction
- Suitable for glass from 19/32" - 27/32" (15mm - 21.4 mm) thickness
- Glass height 1-1/2" (For Top Mount) & height 1-5/8" (For Side Mount) above ground level

<div>Mill Extrusion</div> <div></div> <div>ARCH69SMILL ARCH69TMILL</div> <div>Available in 10 ft & 20 ft length</div>	<div></div> <div>ARCH6910TCLD ARCH6920TCLD</div> <div>Top Mount Cladding</div>	<div></div> <div>ARCH6910SCLD</div> <div>Side Mount Cladding (120" Length)</div>	<div>External & Internal Corner</div> <div></div> <div>ARCH6990CNTMIN</div> <div>90° Top Fix Corner</div>
<div></div> <div>ARCHC12</div> <div>Glass Clamping Kit</div>	<div></div> <div>ARCH69RS3 / ARCH69RS7</div> <div>3Inches/7Inches Gap rubber</div>	<div></div> <div>ARCH69SW</div> <div>Stabilizer Washer</div>	<div>External & Internal Corner</div> <div></div> <div>ARCH6990CNTMEX</div> <div>90° Top Fix External Corner</div>
<div></div> <div>ARCHFWRENCH</div> <div>Ratcheting Wrench</div>	<div></div> <div>ARCHJP</div> <div>Joining Pin</div>	<div></div> <div>ARCHCWRENCH</div> <div>Wrench</div>	
<div></div> <div>ARCHEC69</div> <div>End Cap</div>	<div></div> <div>ARCHDBLOCK</div> <div>Drain Block</div>		
<div></div>			

86 Series – Components & Accessories

Suitable for glass from 19/32" - 27/32" (15mm - 21.4 mm) thickness



Finishes & Specification








Canadian Patent Number: 2962407
Engineered and Stamped - National / Ontario Building Code

- Engineered and stamped as per National and Ontario Building Codes & Miami-Dade County NOAs.
- Material: High Strength Pure Aluminum Construction
- Suitable for glass from 19/32" - 27/32" (15mm - 21.4 mm) thickness
- Glass height 1-1/2" (For Top Mount) above ground level & height 1-5/8" (For Side Mount)


<p>10FT / Top Mount Kits</p> <p>ARCH8610T1517 ARCH8610T1921 Available in 10 ft length</p>	<p>10FT / Mill Top Mount Kits</p> <p>ARCH86TMILL10 Mill Top Mount / Available in 10 ft length</p>	<p>ARCHC1517 Glass Clamp Kit For 19/32" - 11/16" (15mm-17mm) thick Glass</p>	<p>ARCHC1921 Glass Clamp Kit For 3/4" - 27/32" (19mm-21mm) thick Glass</p>
<p>ARCH8610CLD ARCH8610CLD</p>	<p>ARCH86SCLD Top Mount Cladding</p>	<p>ARCH86SCLD Cover Kit for ARCH86</p>	<p>External & Internal Corner</p> <p>ARCH8690CNTMEX 90° Top Fix External Corner</p>
<p>ARCHEC86 End Cap</p>	<p>ARCHCWRENCH Wrench</p>	<p>ARCHFWRENCH Ratcheting Wrench</p>	
<p>ARCH69RS3 ARCH69RS7 3 & 7Inches Gap rubber</p>	<p>ARCHJP Joining Pin</p>	<p>ARCH86SW Stabilizer Washer</p>	

Base Shoe Installation Application





Available Mount Types

- **Top Fixed Application:** Ideal for surfaces like floors or beams, ensuring a clean and modern look.
- **Side Fixed Application:** Perfect for maximizing floor space, mounted directly to the side of the structure.
- **Recessed Application:** Provides a sleek, minimalistic finish by concealing the base shoe within the surface.



Joining Pins

Ensure seamless alignment and structural integrity with Joining Pins from the Arch-Loc Base Shoe System. These precision-engineered components securely connect base shoe segments, providing enhanced stability and a clean, continuous appearance. Built for durability and ease of installation, they are an essential part of achieving a flawless glass railing system.



Clamp Adjustments - Rubber


Rubber in the Arch-Loc Base Shoe System provide protection from duct and debris and vibration damping. These durable rubber inserts ensure a secure fit while protecting the glass from damage, making installation easier and maintaining long-term stability in your glass railing system.

P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

02 Railing Hardware



02 RAILING HARDWARE

Titan Spigots

SQ/RD Top Mount Spigots	94	Side Mount Spigots	97	Connectors & Accessories	100
Arch Loc Series - Spigots	95	Edge Mount Spigots	98		
Stair Mount Spigots	96	Core Mount Spigots	99		

Engineered and Stamped - National / Ontario Building Code



Titan Series – SQ/RD Top Mount Spigots

Adjustable Railing Spigots



↑ Adjustable Glass Height
↙ Adjustable Glass Angle

Set Screw
to Adjust Height





TI6SQADJ
TI8SQADJ

6" or 8" Height Adjustable Spigot - Square



TI6RD

6" Top Mount Spigot - Round



ISOMETRIC VIEW
SCALE: NTS

Key Features

The clean architectural lines create a unique facade providing a very cost efficient modern solution for structural glass railings.

- **Height Adjustable:** Extra 1/2" adjustment for perfect glass alignment.
- **Tilt Adjustment:** $\pm 3^\circ$ flexibility for angled or horizontal installations.
- **Premium Material:** Duplex 2205 stainless steel with SS316 cover for top strength and corrosion resistance.
- **Glass Compatibility:** Fits 12mm glass.
- Engineered and Stamped to meet **National Building Codes**.



ARCH-LOC™ Spigots



Manufactured by
H&G
Systems





For 12-17.52mm
Tempered Glass



ARCH6SQADJ
Arch-Loc Spigot

Glass Size	Gasket Sticker Colors
12mm	Yellow Gasket - L + Red Gasket - I
12.76mm	Yellow Gasket - L + White Gasket - I
13.52mm to 14.28mm	Green Gasket - L + Red Gasket - I
15mm	Green Gasket - L + White Gasket - I
16.76mm to 17.52mm	Purple Gasket - L + White Gasket - I




INSTALLATION METHODS

The clean architectural lines create a unique facade providing a very cost efficient modern solution for structural glass railings.

- **Canadian Patent No.:** 2,962,407
- **Height Adjustable:** Extra 1/2" adjustment for perfect glass alignment.
- **Tilt Adjustment:** ±30mm flexibility for angled or horizontal installations.
- **Premium Material:** Duplex 2205 stainless steel with SS316 cover for top strength and corrosion resistance.
- **Glass Compatibility:** Fits 12mm glass.
- **Engineered and Stamped** to meet **National Building Codes.**




Manufactured by
H&G
Systems



Titan Series – Stair Mount Spigots

Adjustable Railing Spigots



Key Features

The clean architectural lines create a unique facade providing a very cost efficient modern solution for structural glass railings.

- **Height Adjustable:** Extra 1/2" adjustment for perfect glass alignment.
- **Tilt Adjustment:** $\pm 3^\circ$ flexibility for angled or horizontal installations.
- **Premium Material:** Duplex 2205 stainless steel with SS316 cover for top strength and corrosion resistance.
- **Glass Compatibility:** Fits 12mm glass.




Titan Series – Core Mount Spigots

Adjustable Railing Spigots



TICORE
Core Mount Spigot



Key Features

The clean architectural lines create a unique facade providing a very cost efficient modern solution for structural glass railings.

- **Height Adjustable:** Extra 1/2" adjustment for perfect glass alignment.
- **Tilt Adjustment:** $\pm 3^\circ$ flexibility for angled or horizontal installations.
- **Premium Material:** Duplex 2205 stainless steel with SS316 cover for top strength and corrosion resistance.
- **Glass Compatibility:** Fits 12mm glass.




Titan Series Spigot Height Guide

Adjustable Railing Spigots



X = Glass Height from Floor

Type of Spigot	Dimension (X)
6" Spigot	2-1/2" (63.5mm)
8" Spigot	3-3/8" (84.35 mm)
Core Mount Spigot	4" (100.74mm)
Edge Mount Spigot	2-1/4" (58mm)
Side Mount Spigot	1-1/2" (37mm)



Titan Series – Connectors & Accessories

<p>Slim</p> <p>CON180S 180° Glass-to-Glass</p>	<p>Slim</p> <p>CON092S 90° Glass-to-Glass</p>	<p>Slim</p> <p>CON90S 90° Wall-to-Glass</p>	<p>Slim</p> <p>CON345S Adjustable Glass-to-Glass</p>	<p>Slim</p> <p>CON3WAY Railing Connectors 3-Way Glass-to-Glass</p>	
<p>3" Length</p> <p>WEDGEANCHOR -3/8X3 Wedge Anchor 3/8" Diameter</p>	<p>5" Length</p> <p>WEDGEANCHOR -3/8X5 Wedge Anchor 3/8" Diameter</p>	<p>5" Length</p> <p>LAGBOLT-3/8X5 Hex Lag Bolt</p>	<p>3-3/4" Length</p> <p>HB12X3.75SS Hanger Bolt for Side Mount Spigots - M12 X 3-3/4" SS316</p>	<p>6" Length</p> <p>HB12X6SS Hanger Bolt for Side Mount Spigots - M12 X 6" SS316</p>	<p>Installation Socket Side Mount Spigot</p> <p>TISM-TOOL Socket Tool</p> <p>Thread Size: 3/8"-16 for a precise and secure fit</p> <p>TISCREW Set Screw</p>



GGH LED Systems



PRODUCT INFO


- Designed to fit into LED Pro-fit Spigot TI6SQADJ models
- Core in the base of spigot for simple light installation & replacement
- Integrated 1.5W RGB LED deck light set
- RGB, 16 light colors to choose from (speed & brightness adjustable)
- Sleek & modern design
- Life: 20,000 hours
- Waterproof rate of IP67
- 2205 Ultra Marine Grade Stainless Steel
- LED lighting can be changed without removing the spigot with a remote
- 4 mode settings - Flash, strobe, fade & smooth



MOODLEDKIT

LED Kit for Titan Series Spigot

KIT INSTALLATION METHOD



P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

02 Railing Hardware



02 RAILING HARDWARE

Standoffs

Arc Series - Standoffs	104	Gaskets & Accessories	110
Solid Standoffs - RD & SQ	106	Solid Standoff With Mounting Plate	111
Solid Standoffs - Base	108		
Hanger Bolts & Threaded Rod	109		




Arc Series – 4D Adjustable

Standoffs

Brushed Stainless Matte Black Satin Brass More Finishes Online




FAST • EASY • ENGINEERED



4D Base Adjustable

Oval shaped countersunk hole allow us to adjust Standoff base in four directions.



Height Adjustable

Standoff height can be adjusted for your panel projection needs.



Tilt Adjustable

Simple locking Angle with a standard Allen key - No special tools required.



Strong & Stable

Micro-adjustable for perfect glass alignment - Even after mounting.


Ultimate 4D Adjustable Standoffs



USE ONLY MONOLITHIC TEMPERED GLASS

Check out our video

Our video for easy installation tips and detailed product insights.



Get a closer look at our hardware in action.

At Grey Goat Hardware, we don't just sell products — we show you how they work, install, and perform. Our YouTube channel features hands-on demonstrations, product highlights, installation tips, and project showcases — all designed to help you work smarter and spec with confidence.

Scan the QR Code to Watch

Or visit: www.youtube.com/@greygoathardware

Subscribe and stay updated on the latest innovations.

Arc Series – 4D Adjustable

Standoffs


Brushed Stainless
 Matte Black
 Satin Brass
 More Finishes Online



Grey Goat Hardware Standoffs offer a sleek, durable solution for mounting glass, acrylic, or signage panels — ideal for both architectural and decorative applications.

- **Design Compliance:** Engineered to meet National Building Code
- **Patents Canada:** Patent No. 3113019 USA: Patent pending

- **Material:** High-grade Stainless Steel (AISI 316)
- **Glass Thickness Compatibility:** Suitable for 3/8" to 7/8" (10mm to 21.52mm) monolithic tempered glass
- **Glass Fabrication Requirement:** Ø7/8" (22.25mm)




Arc Series Standoff Round

Diameter	Height	SKU
1-1/2" Ø	1-1/4"	RDARC1.5X1.25
1-1/2" Ø	1-1/2"	RDARC1.5X1.5
2" Ø	1-1/4"	RDARC2X1.25
2" Ø	1-1/2"	RDARC2X1.5
2" Ø	2"	RDARC2X2

Arc Series & Accessories

- **Material:** High-grade Stainless Steel (AISI 316)
- **Glass Thickness Compatibility:** Suitable for 3/8" to 7/8" (10mm to 21.52mm) monolithic tempered glass
- **Glass Fabrication Requirement:** Ø7/8" (22.25mm)



Arc Series Standoff Square

X	Y	SKU
1-1/2"	1-1/2"	SQARC1.5X1.5
2"	2"	SQARC2X2



ARC-TOOL
T Wrench



BOLT-M10X84
Countersunk Anchor Bolts



SCREW-ST10X100
Countersunk Wood Screw




Solid Standoffs

Standoffs

- **Material:** High-grade Stainless Steel (AISI 316)
- **Glass Thickness Compatibility:** Suitable for 3/8" to 7/8" (10mm to 21.52mm) monolithic tempered glass
- **Glass Fabrication Requirement:** Ø7/8" (22.25mm)




Finishes



* : below mention, cap does not come with 1 inch Allen Screw.


Solid Round 1-1/2" Ø Standoffs



Glass Fabrication: 3/4" (19mm) Ø (Suggested)*

Diameter	Height	SKU
1-1/2" Ø **	1/4"	SSO1.5X0.25
1-1/2" Ø **	1/2"	SSO1.5X0.5
1-1/2" Ø **	3/4"	SSO1.5X0.75
1-1/2" Ø	1"	SSO1.5X1
1-1/2" Ø	1-1/4"	SSO1.5X1.25
1-1/2" Ø	1/2"	SSO1.5X1.5
1-1/2" Ø	2"	SSO1.5X2

Solid Round 2" Ø Standoffs



Glass Fabrication: 3/4" (19mm) Ø (Suggested)*

Diameter	Height	SKU
2" Ø **	1/4"	SSO2X0.25
2" Ø **	1/2"	SSO2X0.5
2" Ø **	3/4"	SSO2X0.75
2" Ø	1"	SSO2X1
2" Ø	1-1/4"	SSO2X1.25
2" Ø	1-1/2"	SSO2X1.5
2" Ø	1-3/4"	SSO2X1.75
2" Ø	2"	SSO2X2
2" Ø	1/2" - 13 Thread	SSOH2X2
2" Ø	2-1/4"	SSO2X2.25
2" Ø	2-1/2"	SSO2X2.5
2" Ø	3"	SSO2X3
2" Ø	3-1/2"	SSO2X3.5

Solid Standoffs

Standoffs

- **Material:** High-grade Stainless Steel (AISI 316)
- **Glass Thickness Compatibility:** Suitable for 3/8" to 7/8" (10mm to 21.52mm) monolithic tempered glass
- **Glass Fabrication Requirement:** Ø7/8" (22.25mm)



Finishes

- Brushed Stainless
- Matte Black
- Satin Brass
- White
- Custom Finish Available

Solid Square

2" x 2" Standoffs



Glass Fabrication: 3/4" (19mm) Dia (Suggested)*

Dimension	SKU
2" X 2"	SQSO2X2
2" X 1-1/2"	SQSO2X1.5

Solid Round

Standoff Cap



Dimension	SKU
1-1/2"	SSOC1.5
2"	SSOC2

Clear Black



SOGAS1.5-1

Gasket For Standoffs - 1.5" Ø- X 1 & 2 mm Thick

Clear Black



SOGAS2-1

Gasket For Standoffs - 2" Ø- X 1 & 2 mm Thick



* For the most up-to-date product availability, visit our website.

107


www.ggshardware.com

Solid Standoff Base

Standoffs



2" (50mm) Ø



Solid Standoff Base - SS316 - Round

Diameter	Height	SKU
2" Ø	2"	SSOB2X2
2" Ø	1-1/2"	SSOB2X1.5
2" Ø	1-1/4"	SSOB2X1.25
2" Ø	1"	SSOB2X1
2" Ø	3/4"	SSOB2X0.75
2" Ø	1/2"	SSOB2X0.5
2" Ø	1/4"	SSOB2X0.25

1-1/2" (38mm) Ø




Solid Standoff Base - SS316 - Round

Diameter	Height	SKU
1-1/2" Ø	2"	SSOB1.5X2
1-1/2" Ø	1-1/2"	SSOB1.5X1.5
1-1/2" Ø	1-1/4"	SSOB1.5X1.25
1-1/2" Ø	1"	SSOB1.5X1
1-1/2" Ø	3/4"	SSOB1.5X0.75
1-1/2" Ø	1/2"	SSOB1.5X0.5
1-1/2" Ø	1/4"	SSOB1.5X0.25



Solid Round Standoff Cap

Diameter	SKU
1-1/2" Ø	SSOC1.5
2" Ø	SSOC2



Hanger Bolts & Threaded Rod Standoffs



Stainless Steel / Zinc

We provides 1" to 2" (X) threading for Hanger Bolt.



Size

Material

SKU

2-1/2"

ZINC

HB38X2.5Z

3.5"

ZINC

HB38X3.5Z

4.5"

ZINC

HB38X4.5Z

2-1/2"

SS316

HB38X2.5SS

3"

SS316

HB38X3SS

3.5"

SS316

HB38X3.5SS

3-3/4"

SS316

HB12X3.75SS

4"

SS316

HB38X4SS

4.5"

SS316

HB38X4.5SS

5"

SS316

HB38X5SS

6"

SS316

HB12X6SS

6.5"

SS316

HB38X6.5SS

Hanger Bolt

Stainless Steel



Size

Material

SKU

3/8" X 6"

SS316

TR38X6-SS316

1/2" X 6-1/4"

SS316

TR12X6.25SS

Threaded Rod



Gaskets & Accessories

Standoffs



DRIVER-HANGERBOLT

Driver



SOWRENCH


Wrench

Super Duty Standoff Tightening Kit
For Easy & Safe Installation



SSOKIT

Standoffs Tightening Kit



BEST FOR ARC STANDOFFS



ARC-TOOL

T Wrench 10mm



BOLT-M10X84

SCREW-ST10X100

Countersunk Anchor Bolts & Wood Screw

Available In Clear & Black



SOGAS1.5-1

SOGAS2-1




SOGAS1.5-2

SOGAS2-2

Gasket For Standoffs - 1.5"Ø or 2"Ø (1 & 2 mm Thick)

Single Sheet & Pack of 10 Available



**FAST GLASS
TEMPLATING**

TEMPSHEET

Templating Sheet - Polypropylene Corrugated Plastic - (96" X 48" X 5/32")



Standoffs With Mounting Plate

Standoffs




Finishes




Product Overview

- **Features:** 2"Ø Standoff available in Side Mount.
- **Recommended Glass Thickness:** 1/2" (12mm).
- **Dimension:** 4" X 8" Back Plate.



SSOPATE2


2"Ø Standoffs with Mounting Plate



Display Standoffs



Finishes



Key Features

- **Material:** High-grade Stainless Steel (AISI 316)
- **Glass Thickness Compatibility:** Suitable for 3/8" to 7/8" (10mm to 21.52mm) monolithic tempered glass
- **Glass Fabrication Requirement:** Ø1/2" (12mm)



	Diameter	Base Height	SKU	<div>Cap Only</div> <div>DCAP34 Standoff Cap In 3/4\" Dia</div>		<div>Cap Only</div> <div>DCAP114 Standoff Cap In 1-1/4\" Dia</div>
	3/4"	1/2"	DSO3412			
	3/4"	3/4"	DSO3434			
	3/4"	1"	DSO341			
	3/4"	1-1/2"	DSO34112			
	3/4"	2"	DSO342			
	Diameter	Base Height	SKU	 		
	1-1/4"	1/2"	DSO11412			
	1-1/4"	3/4"	DSO11434			
	1-1/4"	1"	DSO1141			
	1-1/4"	1-1/2"	DSO114112			
	1-1/4"	2"	DSO1142			
	1-1/4"	4"	DSO1144			

02 RAILING HARDWARE

Railing Glass Panels (1/2")

34" - 46" Railing Glass Panel 114

46" Glass Panel With Hinge Cutout 115

Glass Panel With Hinge & Latch Cutout 116



1/2" (12mm) Railing Glass Panel


Railing Glass Panels (1/2") Thickness

- CAN/CGSB 12.1-2017
- ANSI Z97.1-2015
- Certified by SGCC®



(Certification documents available upon request)

34" Height




Perfect for Solid Round 1-1/2" Ø Standoffs

Dimension

SKU

18X34	RG18X34
22X34	RG22X34
26X34	RG26X34
30X34	RG30X34
34X34	RG34X34
36X34	RG36X34
42X34	RG42X34
44X34	RG44X34
48X34	RG48X34
50X34	RG50X34
54X34	RG54X34
56X34	RG56X34
60X34	RG60X34
66X34	RG66X34
72X34	RG72X34

41" Height



Perfect for Solid Round 2" Ø Standoffs

Dimension

SKU

Dimension

SKU

12X41	RG12X41	44X41	RG44X41
14X41	RG14X41	46X41	RG46X41
16X41	RG16X41	48X41	RG48X41
18X41	RG18X41	50X41	RG50X41
20X41	RG20X41	52X41	RG52X41
22X41	RG22X41	54X41	RG54X41
24X41	RG24X41	56X41	RG56X41
26X41	RG26X41	58X41	RG58X41
28X41	RG28X41	60X41	RG60X41
30X41	RG30X41	62X41	RG62X41
32X41	RG32X41	64X41	RG64X41
34X41	RG34X41	66X41	RG66X41
36X41	RG36X41	68X41	RG68X41
38X41	RG38X41	70X41	RG70X41
40X41	RG40X41	72X41	RG72X41
42X41	RG42X41		

1/2" (12mm) Railing Glass Panel


Railing Glass Panels (1/2") Thickness

- CAN/CGSB 12.1-2017
- ANSI Z97.1-2015
- Certified by SGCC®



(Certification documents available upon request)

46" Height



Dimension

SKU

32X46

RG32X46

48X46

RG48X46

54X46

RG54X46

60X46

RG60X46

70X46


RG70X46

72X46

RG72X46

1/2" (12mm) Railing Glass Panel With Hinge Cutout only

46" Height With Hinge Cutout



Dimension

SKU

32X46

RG32X46-2H

48X46

RG48X46-2H

54X46


RG54X46-2H

60X46

RG60X46-2H


1/2" (12mm) Railing Glass Panel With Hinge & Latch Cutout

Railing Glass Panels (1/2") Thickness



RG32X46-2HL

1/2" Railing Glass Panel (Size: 32" x 46") With Hinge & Latch Cutout



Refer to local building codes for product compliance and installation requirements.

Factory Order Program

Factory Direct Savings on Volume Orders

Take advantage of our Factory Direct Program and save big on large-scale shower door orders. Whether you're working on condos, high-rises, or residential developments, we make the process easy, fast, and cost-effective

What You Get

01 Full Crates of Glass Shipped Directly to You

- Delivered fast and hassle-free - right to your shop or job-site.

02 Order Today – Just Give Us a Call

- Our team is ready to assist with quotes, coordination, and delivery planning.

Contact us to enroll: sales@ggshardware.com

Speak with our program manager: 1-905-264-1600


Ask about our MOQ charts, lead time options, and program perks.



02 RAILING HARDWARE

Pro Series – Engineered

Railing Post - Blank	118	Railing Post - Stairs Mount	122	Railing Mini Post	126
Railing Posts - Square (32"-42")	119	Railing Post - Accessories	123		
Railing Posts - Round (32"-42")	120	Railing Post - Double Arm	124		
Railing Posts - Side Mount	121	Double Arm Connector	125		



Architectural Railing Post – Blank

Pro Series - Engineered



Finishes




***All Post Endcaps and Saddle Support Sold Separately**

Square

1-9/16" X 1-9/16"

44"
(1117mm)



POST DETAILS-TOP VIEW

Sold Separately



← Base Plate With Cap Included

SPRO44B

Square Pro Series Railing Post - 44" Height


Specification

- **Material:** Constructed from high-quality Stainless Steel 316, offering superior durability and resistance to corrosion.
- **Customizable Design:** Blank posts with no pre-drilled holes, allowing for fabrication based on project-specific needs.
- **Applications:** Ideal for both residential and commercial installations, suitable for interior and exterior use.
- **Warranty:** Backed by a full 5-year warranty for peace of mind.
- **Compliance:** Engineered to meet Ontario and National Building Code requirements.

Square

2" X 2"

50"
(1270mm)



POST DETAILS-TOP VIEW

*2"X2" post allows for gate post with small picture of Hulk Hinge



page number: ____

← Base Plate With Cap Included


SPRO50B

Square Pro Series Railing Post - 50" Height - Blank

Round

1-11/16" Ø

44"
(1117mm)



Sold Separately



← Base Plate With Cap Included

RPRO44B

Round Pro Railing Post - 44" Base Height - Blank

Architectural Railing Posts – Square (32"-42")

Pro Series - Engineered

Finishes

Brushed Stainless
 Matte Black
 More Finishes Online

***All Post Endcaps and Saddle Support Sold Separately**



End Post 		Inline Post 		Corner Post 	
Available Height	SKU	Available Height	SKU	Available Height	SKU
32" (812.8mm)	SPRO32E	32" (812.8mm)	SPRO32I	32" (812.8mm)	SPRO32C
36" (914.4mm)	SPRO36E	36" (914.4mm)	SPRO36I	36" (914.4mm)	SPRO36C
38" (978mm)	SPRO38E	38" (978mm)	SPRO38I	38" (978mm)	SPRO38C
42" (1067mm)	SPRO42E	42" (1067mm)	SPRO42I	42" (1067mm)	SPRO42C

Architectural Railing Posts – Round (32"-42")


Pro Series - Engineered




Finishes



***All Post Endcaps and Saddle Support Sold Separately**



Available Height		SKU	Available Height		SKU	Available Height		SKU
32" (812.8mm)		RPRO32E	32" (812.8mm)		RPRO32I	32" (812.8mm)		RPRO32C
36" (914.4mm)		RPRO36E	36" (914.4mm)		RPRO36I	36" (914.4mm)		RPRO36C
38" (978mm)		RPRO38E	38" (978mm)		RPRO38I	38" (978mm)		RPRO38C
42" (1067mm)		RPRO42E	42" (1067mm)		RPRO42I	42" (1067mm)		RPRO42C



Architectural Railing Posts – Side Mount

Pro Series - (Order On Request)




Finishes



Custom Fabrication
Available

End Post



SPROSIDEE

Side Mount Square Pro Railing Post
CUSTOM - End Post

Inline Post



SPROSIDEI

Side Mount Square Pro Railing Post
CUSTOM - Inline Post

Corner External Post



SPROSIDEEXT

Side Mount Square Pro Railing Post
CUSTOM - External Post

Corner Internal Post





SPROSIDEINT

Side Mount Square Pro Railing Post
CUSTOM - Internal Post

Custom Side Mount Post Requirements:

A: Distance from top of the post to 1st clamp.
B: Distance between clamp to clamp.
C: Distance from 2nd clamp to bottom of the post.
H: Total height of the post.

X: Width of the Mounting Plate.
Y: Height of the Mounting Plate.
T: Thickness of the Mounting Plate.
G: Hole distance from edge of the plate.



Architectural Railing Post – For Stairs

Pro Series




Finishes



Specification

Made from heavy-gauge 316 stainless steel for superior corrosion resistance, this 40×40mm (1.57"×1.57") post stands 32" tall, with 36", 38", and 42" options available. Includes gaskets for 10mm (3/8") and 12mm (1/2") toughened glass.

Inline Stair



SPRO32STAIR


32" Base Height - Inline

Specification


- **Material:** Constructed from high-quality Stainless Steel 316, offering superior durability and resistance to corrosion.
- **Various Configuration:** Available with per-fabricated clamps for Inline, Corner and end post.
- **Applications:** Ideal for both residential and commercial stair glass panels installations, suitable for interior and exterior use.
- **Warranty:** Backed by a full 5-year warranty for peace of mind.
- **Compliance:** Engineered to meet Ontario and National Building Code requirements.

Custom Fabrication Available based on your requirement, send us quote on products@ggshardware.com



Inline Ground



Inline Stair



End Post



Architectural Railing Post – Accessories


Pro Series - Engineered



Finishes



SPROBASE
Base Plate for Square Posts



CP40SQ
Coverplate for Square Post



RPROSUP
Handrail Support - Round



RPROSUPADJ
Handrail Support - Round - Adjustable



SPROSUP
Handrail Support - Square



SPROSUPADJ
Handrail Support - Square - Adjustable



FLATSAD135
Flat Saddle - 135°



FLATSAD180
Flat Saddle - 180°



FLATSAD90
Flat Saddle - 90°

3" Length




WEDGEANCHOR-3/8X3
Wedge Anchor 3/8" Diameter

3/8"



LAGBOLT-3/8X3
Hex Lag Bolt - 3/8" X 3-1/2"



USE ONLY
MONOLITHIC
TEMPERED GLASS

Architectural Railing Posts – Double Arm Posts


Double Arm Posts



Finishes




ADJ-RD



RPROARM-44ADJ

Adjustable Round Post - 44" Height


ADJ-SQ



SPROARM-44ADJ

Adjustable Square Post - 44" Height


Round



RPROARM-44

Fixed Round Post - 44" Height


Square



SPROARM-44

Fixed Square Post - 44" Height


ADJ-SQ



SPROARM-50ADJ

Adjustable Square Post - 50" Height

Square



SPROARM-50

Fixed Square Post - 50" Height

Double Arm Connector



Finishes



- **Premium Material:** Made from high-quality stainless steel for strength and long-lasting performance.
- **Glass Compatibility:** Suitable for 1/2" to 13/16" (12mm to 20mm) thick glass.

Adjustable



PROARMADJ

Pro Series Double Arm Glass Connector - Adjustable

Fixed



PROARM

Pro Series Double Arm Glass Connector - Fixed

Canopy Bracket



Finishes



*Custom configuration and size available based upon request products@ggshardware.com



Custom Fabrication Available

24"



GC2401

Glass Canopy Bracket (24" Height)

36"



GC3601

Glass Canopy Bracket (36" Height)



Ask us about
FACTORY DIRECT PROGRAM



Railing Mini Post

*Engineered for national and building code




Finishes



- **Compact Design:** Mini posts measure 3/4" x 2" with a total height of 12" (including surface mount plate).
- **Strong Surface Mount Plate:** 5-1/2" x 3" x 3/4" base for secure installation.
- **Glass Compatibility:** Recommended for 1/2" (12mm) glass panels.

SS316

12" (304.8mm)




MINIPRO

Railing Mini Post - Surface Mount

Glass fabrication required, visit ggshardware.com for reference

SS316

21" (533.4mm)



MINIPROSM

Railing Mini Post - Side Mount

Glass fabrication required, visit ggshardware.com for reference

Divider Series – Partition Post




Finishes



Specification:

- **Versatile Use:** Ideal for creating sleek, modern glass partition systems in office desk, commercial, or residential spaces.
- **Profile Options:** Available in both End-to-End Glass and Air Space Glass profile configurations to suit your design and privacy requirements.



PPOST1
Partition Post - 1 Way



PPOST2C
Partition Post - 2 Way Corner




PPOST3
Partition Post - 3 Way



PPOST2I
Partition Post - 2 Way Inline



PPOST4
Partition Post - 4 Way



PPOSTH1
Air Gap Partition Post
1 Way



PPOSTH2C
Air Gap Partition Post -
2 Way Corner



PPOSTH3
Air Gap Partition Post
3 Way



PPOSTH2I
Air Gap Partition Post -
2 Way Inline



PPOSTH4
Air Gap Partition Post
4 Way



G-AWS Aluminum Windscreen System



Overview

The Windscreen Awning System is a modern, durable solution for creating glass wind barriers in residential and commercial outdoor spaces.

**Ask us about
FACTORY DIRECT PROGRAM**

Key Features

- Clean, contemporary design with minimal hardware for unobstructed views
- Low-maintenance aluminum construction with corrosion-resistant finish
- Supports both dry and wet glazing methods, depending on glass thickness
- Suitable for installation on concrete slabs, block walls, or individual footings
- Adaptable to flat, sloped, or stepped surfaces
- Ideal for decks, patios, balconies, and poolside enclosures
- Standard color options available, with custom finishes upon request
- Compatible with phased construction timelines for added flexibility



02 RAILING HARDWARE

Railing Clamps

Square Railing Clamps 130

Railing Clamps Accessories 131

Pool Fencing - Brackets 132




Square Railing Clamps

CLAM Series - SS316 & ZINC

Finishes



SS316



SCLAM

Square Clamp - 55x55mm - Flat Back


SS316



SCLAMRB

Square Clamp - 61x55mm - Round Back


SS316



SCLAM54

Square Clamp - 54x54mm - Flat Back

ZINC



SCLAMZ

Square Clamp - 55x55mm - Flat Back

High-Quality Stainless Steel Clamps for Secure Glass Installation

- **Material:** Constructed with high-grade SS316 stainless steel, offering exceptional corrosion resistance for both indoor and outdoor use.
- **Glass Compatibility:** Designed to securely hold 10mm (3/8 inch) and 12mm (1/2 inch) thick monolithic tempered glass.

Round Railing Clamps

CLAM Series - SS316 & ZINC

INSTALLER'S FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272



SS316



RCLAMFB


Round Clamp - 63x45mm - Flat Back

SS316



RCLAM

Round Clamp - 67x45mm - Round Back



Railing Clamps Accessories

CLAM Series - SS316

INSTALLER'S FAVORITE!
 GOAT Drill & Spade Bits,
 Refer Page Number: 272



Finishes

Brushed Stainless
 Polished Stainless
 Matte Black



SCLAMCONSQ

Adjustable 180° Connector For Square Post



SCLAMCONRD

Adjustable 180° Connector For Round Post



CLAMSAFETYPIN

Extra Pair of Safety Pin



SCREW-M8X20

Replacement Allen Screws



SCLAMRUB

Rubber Inserts

Dimension	SKU(PAIR)
12mm Glass	SCLAMRUB12
10mm Glass	SCLAMRUB10
8mm Glass	SCLAMRUB8
6mm Glass	SCLAMRUB6



RCLAMRUB

Rubber Inserts

Dimension	SKU(PAIR)
12mm Glass	RCLAMRUB12
10mm Glass	RCLAMRUB10
8mm Glass	RCLAMRUB8
6mm Glass	RCLAMRUB6




Pool Fencing – Brackets

Railing Clamps



Finishes



Key Features

- **Materials:** Crafted from premium Stainless Steel 316 for superior strength and corrosion resistance
- **Applications:** Ideal for pool fencing, offering a modern and secure enclosure for both residential and non-residential properties
- **Glass Compatibility:** Suitable for 5/16" to 1/2" (8mm, 10mm, and 12mm) monolithic tempered glass



BDIVESQ90

Pool Fencing Bracket 90° Glass to Glass - Square



BDIVE90

Pool Fencing Bracket 90° Glass to Glass - Round



CLAMSAFETYPIN
Extra Pair of Safety Pin



CLAMSAFETYPIN
Extra Pair of Safety Pin



BDIVE180SQ

Pool Fencing Bracket 180° Glass to Glass - Square



BDIVE180RD

Pool Fencing Bracket 180° Glass to Glass - Round

02 RAILING HARDWARE

Railing Handrails & Caprails

Handrail - RD - 42.4mm Ø	134	Caprail - RD - 42.4mm Ø	139	Aluminum Caprail - RD - 42.4mm Ø	143
Handrail - RD - 38.1mm Ø	136	Caprail - SQ - 40mm	140	Aluminum Caprail - SQ	144
Handrail - SQ - 40X40mm	137	Caprail - REC - 60×40mm	141	Aluminum Caprail - REC	145
Handrail - REC - 50mm X 25mm	138	Caprail - SQ - 1"X1"	142		




Handrail – Round – 1-5/8" (42.4mm) Ø

Handrails & Caprails (19FT)














Finishes



- **Premium Material:** Constructed from SS316 stainless steel for durability and long-term performance.
- **Standard Sizing:** 42.4mm (1-5/8") outer diameter with a 1.85mm wall thickness, available in a 19FT length.



Custom Fabrication Available

<p>1-5/8" Ø</p>  <p>HR42.4 42.4mm Ø Round Handrail - 19' Length</p>	 <p>END42.4 Endcap for Handrail</p>	 <p>END42.4B Ball Endcap for Handrail</p>	 <p>E42.4F180 Handrail Elbow - 180° Fixed</p>
 <p>CP42.4 Cover Plate Handrail</p>	 <p>E42.4WELD90 Handrail Elbow 90° Welded</p>	 <p>E42.4F90 Handrail Elbow 90° Fixed</p>	
 <p>E42.4MT90 Handrail Elbow 90° Mitered</p>	 <p>E42.4ADJ90 Handrail Elbow 90° Adjustable</p>	 <p>END42.4C Handrail Elbow Curved</p>	

Handrail – Round – 1-5/8" (42.4mm) Ø

Handrails & Caprails (19FT)














Finishes



- **Premium Material:** Constructed from SS316 stainless steel for durability and long-term performance.
- **Standard Sizing:** 42.4mm (1-1/2") outer diameter with a 1.85mm wall thickness, available in a 19FT length.



Custom Fabrication Available


				
E42.4T180 42.4mm Handrail Elbow T-Shape 180°	E42.4T90 42.4mm Handrail Elbow T-Shape 90°	E42.4F135 42.4mm Handrail Elbow Fixed 135°	E42.4ADJR 42.4mm Handrail Elbow Adjustable Right	E42.4ADJL 42.4mm Handrail Elbow Adjustable Left
				
E42.4R360 42.4mm Handrail Elbow Rotating 360°	RPROSUP Handrail Support - Round	RPROSUPADJ Handrail Support Round - Adjustable		
				
WF42.4ADJ Wall Mount Flange 42.4mm Handrail -Adjustable	WF42.4HD Wall Mount Flange - 42.4mm Handrail - Heavy Duty			

Handrail – Round – 1-1/2" (38.1mm) Ø

Handrails & Caprails (19FT)













Finishes



- **Premium Material:** Constructed from SS316 stainless steel for durability and long-term performance.
- **Standard Sizing:** 1-1/2" (38.1mm) outer diameter with a 1.85mm wall thickness, available in a 19FT length.



Custom Fabrication Available


<p>1-1/2" Ø</p>  <p>HR38.1 38.1mm Ø Round Handrail - 19' Length</p>	 <p>END38.1 Endcap for Handrail</p>	 <p>E38.1F90 Handrail Elbow - 90° Fixed</p>	 <p>E38.1MT90 Handrail Elbow - 90° Mitered</p>
 <p>E38.1ADJ90 Handrail Elbow 90° Adjustable</p>	 <p>E38.1F180 Handrail Elbow 180° Fixed</p>	 <p>E38.1F135 Handrail Elbow 135° Fixed</p>	 <div data-bbox="1042 1936 1360 2054"> <p>INSTALLER'S FAVORITE! GOAT Drill & Spade Bits, Refer Page Number: 272</p> </div>
 <p>RPROSUP Handrail Support - Round</p>	 <p>RPROSUPADJ Handrail Support - Round - Adjustable</p>		

Handrail – Square – 1-9/16" (40mm)

Handrails & Caprails (19FT)














Finishes



- **Premium Material:** Manufactured from high-gauge SS316 stainless steel for superior strength and corrosion resistance.
- **Standard Sizing:** 40mm x 40mm (1-5/8") square profile, available in a 19FT length.



Custom Fabrication Available

<p>1-5/8"</p>  <p>HR40SQ 40mm Square Handrail - 19' Length</p>	 <p>END40SQ Endcap for 40mm Handrail</p>	 <p>E40F90 40mm Square Handrail Elbow Fixed 90°</p>	 <p>E40ADJ90 40mm Square Handrail Elbow Adjustable 90°</p>
 <p>E40F180 40mm Square Handrail Elbow Fixed 180°</p>	 <p>CP40SQ 40mm Square Handrail Cover Plate</p>	 <p>WF40SQHD Wall Mount Flange 40mm Square - Handrail - HD</p>	
 <p>WF40ADJ Wall Mount Flange 40mm Handrail - Adjustable</p>	 <p>SPROSUP Handrail Support - Square</p>	 <p>SPROSUPADJ Handrail Support - Square - Adjustable</p>	

Handrail – Rectangle – 2" X 1" (50x25mm)

Handrails & Caprails (19FT)












Finishes



- **Premium Material:** Constructed from SS316 stainless steel for enhanced strength and longevity.
- **Standard Sizing:** 2" x 1", available in a 19FT length.



Custom Fabrication Available

<p>2" X 1"</p>  <p>HR2X1 2 X 1" Rectangle Handrail - 19' Length</p>	 <p>END2X1 Endcap for 2X1" Square Handrail</p>	 <p>E2X1F90H Elbow - 2X1" SQ Handrail Fixed 90° Horizontal</p>	 <p>E2X1F90V Elbow For 2X1" SQ Handrail Fixed 90° Vertical</p>
 <p>E2X1F180 Elbow For 2X1" SQ Handrail Fixed 180°</p>	 <p>E2X1ADJV Elbow For 2X1" SQ Handrail Adjustable Vertical 90°</p>	 <p>E2X1ADJH Elbow For 2X1" SQ Handrail Adjustable Horizontal 90°</p>	
 <p>SPROSUP Handrail Support - Square</p>	 <p>SPROSUPADJ Handrail Support - Square - Adjustable</p>		

Caprail – Round – 1-5/8" (42.4mm) Ø

Handrails & Caprails (19FT)



Custom Fabrication Available


Finishes

■ Brushed Stainless Steel
 ■ Matte Black Anodized Aluminum
 ■ More Finishes Online

- **Premium Material:** Constructed from SS316 stainless steel for enhanced strength and longevity.
- **Standard Sizing:** 1-5/8" outside diameter, available in a 19FT length.


1-5/8"Ø

*Refer to our website for LED options




CR42.4

42.4 Ø Round Caprail - 19' Length




CEND42.4

Endcap for Caprail




WFC42.4

Wall Mount Flange for Caprail




CE42.4F180

Elbow For Caprail - 180° Fixed




CE42.4F90H

Elbow For Caprail - 90° Fixed Horizontal



CE42.4F90V


Elbow For Caprail - 90° Fixed Vertical



CE42.4ADJDN

Elbow For Caprail - Adjustable Downward


10 mm to 21 mm



CRUB


Rubber - 19' Length

Dimension	SKU
10mm (19')	CRUB10
12mm (19')	CRUB12
15mm (19')	CRUB15
17mm (19')	CRUB17
19mm (19')	CRUB19
21mm (19')	CRUB21



CE42.4ADJUP

Elbow For Caprail - Adjustable Upward



Caprail – Square – 1-5/8" – (40x40mm)

Handrails & Caprails (19FT)










Finishes



- Premium Material:** Manufactured from high-gauge Stainless Steel 316 for superior corrosion resistance.
- Modern Square Profile:** 40mm x 40mm (1-5/8") dimensions offer a sleek, contemporary look in 19'



Custom Fabrication Available


<div>40mm Sqaure</div> <div><p>*Refer to our website for LED options</p></div> <div><p>CR40SQ 40mm Square Caprail 19' Length</p></div>	<div></div> <div><p>CEND40SQ Endcap For Caprail</p></div>	<div></div> <div><p>WFC40SQ Wall Mount Flange For Caprail</p></div>	<div><div>10 mm to 21 mm</div></div> <div><p>CRUB Rubber - 19' Length</p></div>	<table><tr><th>Dimension</th><th>SKU</th></tr><tr><td>10mm (19')</td><td>CRUB10</td></tr><tr><td>12mm (19')</td><td>CRUB12</td></tr><tr><td>15mm (19')</td><td>CRUB15</td></tr><tr><td>17mm (19')</td><td>CRUB17</td></tr><tr><td>19mm (19')</td><td>CRUB19</td></tr><tr><td>21mm (19')</td><td>CRUB21</td></tr></table>	Dimension	SKU	10mm (19')	CRUB10	12mm (19')	CRUB12	15mm (19')	CRUB15	17mm (19')	CRUB17	19mm (19')	CRUB19	21mm (19')	CRUB21
Dimension	SKU																	
10mm (19')	CRUB10																	
12mm (19')	CRUB12																	
15mm (19')	CRUB15																	
17mm (19')	CRUB17																	
19mm (19')	CRUB19																	
21mm (19')	CRUB21																	
<div></div> <div><p>CE40F180 Elbow - 180° Fixed</p></div>	<div></div> <div><p>CE40F90H Elbow - 90° Fixed Horizontal</p></div>	<div></div> <div><p>CE40F90V Elbow - 90° Fixed Vertical</p></div>																
<div></div> <div><p>CE40ADJDN Elbow - Adjustable Downward</p></div>	<div></div> <div><p>CE40ADJUP Elbow - Adjustable Upward</p></div>	<div></div> <div><p>CP40SQ Cover Plate - 40mm Square Caprail</p></div>																

Caprail – Rectangle – 2-3/8"x1-9/16" (60X40mm)

Handrails & Caprails (19FT)



Finishes



- **Premium Construction:** Made from 316 stainless steel for long-lasting durability and resistance to corrosion.
- **Modern Rectangular Design:** 60x40mm profile enhances architectural aesthetics.

2-3/8"x1-9/16"

*Refer to our website for LED options



CR60X40
60X40mm Rectangle Caprail
19' Length



CEND60X40
Endcap For Caprail



LED Options Available



Custom Fabrication
Available



Caprail – Square – 1"x1" (25x21mm)

Handrails & Caprails (19FT)



Custom Fabrication
Available



Finishes

Brushed
Stainless Steel

Matte Black
Anodized Aluminum

More
Finishes Online

- **High-Quality Material:** Made from 316 stainless steel for superior corrosion resistance and durability.
- **Versatile Design:** Suitable for a variety of railing applications, including both commercial and residential spaces.
- **Customizable Length:** Available in a 19FT length, with options for custom cutting and fabrication.

1"x1"

*Refer to our website for
LED options



CR1X1SQ

1 X 1" Square Caprail - 19' Length



CRUB12S

Small Rubber For Caprail



CEND1X1SQ

Endcap For Caprail



CE1X1F180

Elbow For Caprail
180° Fixed



WF1X1A

Wall Mount Flange
For 1 X 1" Caprail - Type A



CE1X1F90H

Elbow For Caprail
Fixed 90° Horizontal



CE1X1ADJ135H

Elbow For Caprail
Adjustable 135° Horizontal



CE1X1ADJ90V

Elbow For Caprail
Adjustable 90° Vertical



WF1X1B

Wall Mount Flange for 1 X 1" Caprail - Type B



Aluminum Caprail – Round 1-5/8" (42.4mm) Ø

Handrails & Caprails (19FT)




Custom Fabrication
Available




Finishes



Brushed
Stainless Steel



Matte Black
Anodized Aluminum



More
Finishes Online

- **Material:** Corrosion-resistant 6063-T5 aluminum for long-lasting durability.
- **Glass Compatibility:** Suitable for glass thicknesses of 10-21.52mm.
- **Available Finishes:** Satin Anodized and Matte Black.
- **Lighter and Easier to Fabricate**




<p>1-5/8" Ø</p> <p>*Refer to our website for LED options</p>  <p>ALCRRD 42.4mm Ø Round Caprail - 19' Length</p>	 <p>ALWFRD Aluminum Caprail - Round Wall Flange</p>	 <p>ALCENDRD Aluminum Caprail - Round End Cap</p>	<p>Fixed</p>  <p>ALCR90 Aluminum Caprail - 90° Connector</p>												
<p>Fixed</p>  <p>ALCR180 Aluminum Caprail - 180° Connector</p>	<p>Adjustable</p>  <p>ALCRADJH Aluminum Caprail - Horizontal Connector</p>	<p>Adjustable</p>  <p>ALCRADJV Aluminum Caprail - Vertical Connector</p>													
<p>10 mm to 21 mm</p>  <p>CRUB Rubber Gasket - 19' Length</p>	<table border="1"> <thead> <tr> <th>Dimension</th> <th>SKU</th> </tr> </thead> <tbody> <tr> <td>10mm (19')</td> <td>CRUB10</td> </tr> <tr> <td>12mm (19')</td> <td>CRUB12</td> </tr> <tr> <td>15mm (19')</td> <td>CRUB15</td> </tr> <tr> <td>17mm (19')</td> <td>CRUB17</td> </tr> <tr> <td>19mm (19')</td> <td>CRUB19</td> </tr> <tr> <td>21mm (19')</td> <td>CRUB21</td> </tr> </tbody> </table>	Dimension	SKU	10mm (19')	CRUB10	12mm (19')	CRUB12	15mm (19')	CRUB15	17mm (19')	CRUB17	19mm (19')	CRUB19	21mm (19')	CRUB21
Dimension	SKU														
10mm (19')	CRUB10														
12mm (19')	CRUB12														
15mm (19')	CRUB15														
17mm (19')	CRUB17														
19mm (19')	CRUB19														
21mm (19')	CRUB21														

Aluminum Caprail – Square – 1-9/16" (40mm)

Handrails & Caprails (19FT)






Finishes



- **Material:** Corrosion-resistant 6063-T5 aluminum for long-lasting durability.
- **Glass Compatibility:** Suitable for glass thicknesses of 10-21.52mm.
- **Available Finishes:** Satin Anodized and Matte Black.
- **Lighter and Easier to Fabricate**



<p>1-9/16"</p> <p>*Refer to our website for LED options</p>  <p>ALCRSQ Square Aluminum Caprail - 19' Length</p>	 <p>ALWFSQ Aluminum Caprail Square Wall Flange</p>	 <p>ALCENDSQ Aluminum Caprail - Square End Cap</p>	<p>Fixed</p>  <p>ALCR90 Aluminum Caprail - 90° Connector</p>													
<p>Fixed</p>  <p>ALCR180 Aluminum Caprail 180° Connector</p>	<p>Adjustable</p>  <p>ALCRADJH Aluminum Caprail - Horizontal Adjustable Connector</p>	<p>Adjustable</p>  <p>ALCRADJV Aluminum Caprail - Vertical Adjustable Connector</p>	 <p>Custom Fabrication Available</p> 													
<p>10 mm to 21 mm</p>  <p>CRUB Rubber Gasket - 19' Length</p>	<table border="1"> <thead> <tr> <th>Dimension</th> <th>SKU</th> </tr> </thead> <tbody> <tr> <td>10mm (19')</td> <td>CRUB10</td> </tr> <tr> <td>12mm (19')</td> <td>CRUB12</td> </tr> <tr> <td>15mm (19')</td> <td>CRUB15</td> </tr> <tr> <td>17mm (19')</td> <td>CRUB17</td> </tr> <tr> <td>19mm (19')</td> <td>CRUB19</td> </tr> <tr> <td>21mm (19')</td> <td>CRUB21</td> </tr> </tbody> </table>		Dimension	SKU	10mm (19')	CRUB10	12mm (19')	CRUB12	15mm (19')	CRUB15	17mm (19')	CRUB17	19mm (19')	CRUB19	21mm (19')	CRUB21
Dimension	SKU															
10mm (19')	CRUB10															
12mm (19')	CRUB12															
15mm (19')	CRUB15															
17mm (19')	CRUB17															
19mm (19')	CRUB19															
21mm (19')	CRUB21															

Aluminum Caprail – Rectangle

Handrails & Caprails (19FT)



Finishes

- Brushed Stainless Steel

Matte Black Anodized Aluminum

More Finishes Online

- **Material:** Corrosion-resistant 6063-T5 aluminum for long-lasting durability.
- **Glass Compatibility:** Suitable for glass thicknesses of 10-21.52mm.
- **Available Finishes:** Satin Anodized and Matte Black.
- **Lighter and Easier to Fabricate**



Square

*Refer to our website for LED options

ALCRREC

Rectangular Aluminum Caprail - 19' Length

ALWFREC

Aluminum Caprail - Rectangular Wall Flange

ALCENDREC

Aluminum Caprail - Rectangular End Cap

Fixed

ALCR90

Aluminum Caprail - 90° Connector

Fixed

ALCR180

Aluminum Caprail 180° Connector

Adjustable

ALCRADJH

Aluminum Caprail - Horizontal Adjustable Connector

Adjustable

ALCRADJV

Aluminum Caprail - Vertical Adjustable Connector

10 mm to 21 mm

CRUB

Rubber Gasket - 19' Length

Dimension	SKU
10mm (19')	CRUB10
12mm (19')	CRUB12
15mm (19')	CRUB15
17mm (19')	CRUB17
19mm (19')	CRUB19
21mm (19')	CRUB21

Custom Fabrication Available

Romeo Juliet Balcony System



Key Features

- Full range of Romeo Juliet Balcony System
- Match with H6030 slotted handrail system
- Suitable for 10-21.52mm glass with optional rubbers
- The centre of glass is 86mm distance off wall
- The glass does NOT require holes
- FAST FIT Mini Rails are supplied in any length
- Reduced MINIMUM visual impact
- No welding installation

Contact Us On

products@ggshardware.com
For More Information!



02 RAILING HARDWARE

Handrail Brackets

Handrail Brackets - Wall Mount 148

Handrail Brackets - Glass Mount 149



Handrail Brackets – Wall Mount



Finishes

Brushed Stainless Steel

Matte Black Anodized Aluminum

More Finishes Online













Acronyms:

WM: Wall Mount
GM: Glass Mount

RD: Round
SQ: Square

Material:
SS316



 <p>HRB3X3WM - Fixed 3X3" with Round Saddle</p>	 <p>HRB3X2WM - Fixed 3X2" with Round Saddle</p>	 <p>HRB3X3WM - Fixed 3X3" with Flat Saddle</p>	 <p>HRB3X2WM - Fixed 3X2" with Flat Saddle</p>
 <p>SHRBADJWM Adjustable Wall Mount - Flat Saddle</p>	 <p>SHRBADJWM Adjustable Wall Mount - Round Saddle</p>	 <p>HRBADJWM Adjustable Wall Mount - Round Saddle</p>	 <p>HRBADJWM Adjustable Wall Mount - Flat Saddle</p>
<p>Flat 4.5"</p>  <p>EXTHRB4.5WM 4-1/2" Length with Flat Saddle</p>	<p>Flat 6"</p>  <p>EXTHRB6WM 6" Length with Flat Saddle</p>	<p>Round 4.5"</p>  <p>EXTHRB4.5WM 4-1/2" Length with Round Saddle</p>	<p>Round 6"</p>  <p>EXTHRB6WM 6" Length with Round Saddle</p>

Handrail Brackets - Glass Mount



Finishes		Acronyms:		Material: SS316	<div> <div>Designers Selected</div> </div>
Brushed Stainless Steel	Matte Black Anodized Aluminum	Custom Finishes	WM: Wall Mount GM: Glass Mount RD: Round SQ: Square		
<p>HRB3X2GM - Fixed 3X2" with Round Saddle</p>	<p>HRB3X3GM - Fixed 3X3" with Round Saddle</p>	<p>HRB3X2GM - Fixed 3X2" with Flat Saddle</p>	<p>HRB3X3GM - Fixed 3X3" with Flat Saddle</p>		
<p>SHRBADJGM Adjustable Glass Mount - Flat Saddle</p>	<p>SHRBADJGM Adjustable Glass Mount - Round Saddle</p>	<p>HRBADJGM Adjustable Glass Mount - Round Saddle</p>	<p>HRBADJGM Adjustable Glass Mount - Flat Saddle</p>		
<div>Flat 4.5"</div> <p>EXTHRB4.5GM 4-1/2" Length with Flat Saddle</p>	<div>Flat 6"</div> <p>EXTHRB6GM 6" Length with Flat Saddle</p>	<div>Round 4.5"</div> <p>EXTHRB4.5GM 4-1/2" Length with Round Saddle</p>	<div>Round 6"</div> <p>EXTHRB6GM 6" Length with Round Saddle</p>		

Handrail Brackets




Finishes



Acronyms:

WM: Wall Mount RD: Round Material: SS316
 SQ: Square


WM 2" X 2-1/2"



SHRB2X2.5WM

2" X 2-1/2" - Wall Mount

WM 2" X 3-1/2"





SHRB2X3.5WM

2" X 3-1/2" - Wall Mount



Note: Visit ggshardware.com For Glass Fabrication & Product Information.



02 RAILING HARDWARE



Aluminum Posts

Modern Elegance Series - Kits	152
Modern Elegance Series - Accessories	153
GOAT Cable Railing System	154
Hulk Series - Hinges	156



Modern Elegance Series- Kit

Aluminum Posts




Finishes



*Refer to website for kit components

42" & 50"*

Modern Elegance - 42" Post - All In One



ALPOST-42
ALPOST-50

42" & 50" Base Height - ALL IN ONE - Inline / Corner / End- Square

42" & 50"*




One Side Adjustable



Rubber Infills
3/8" or 1/2" Glass

Both Side Adjustable



Rubber Infills
3/8" or 1/2" Glass

ALPOST-42ADJ

42" Base Height - Adjustable - Square



Modern Elegance Series Accessories

Aluminum Posts



Finishes



42"



ALPOST-INFILL

Aluminum Post Component - 42" Length Infills



ALPOST-RUBBER

Rubber Block



AL-HRAIL-ECAPMBL

End Cap For 2-1/2" X 1" Aluminum Handrail

1/2" (12mm)



ALPOST-RUBBER12

Rubber Gasket
For 12mm Glass (42" Length)

3/8" (10mm)



ALPOST-RUBBER10

Rubber Gasket
For 10mm Glass (42" Length)

Square



ALHRAIL-TOOL

Fix Tool For Aluminum Handrail

19' Length




ALHRAIL-2.5X1

Aluminum Handrail
2-1/2" X 1" - 19' Length



02 RAILING HARDWARE

GOAT Cable Rail System



Goat Cable Rail System



Finishes

Brushed Anodized Aluminum
 Matte Black Anodized Aluminum
 Brushed Stainless Steel
 Polished Stainless Steel
 More Finishes Online



GCSCABLE100

100ft length Cable - 1/8" thickness - SS316



GCSTENSIONER

Torq Tool Tensioner - Fencing Tool



GCSCUT

Goat Cable Rail System - Cable Cutter




GCSSTUD

Goat Cable Rail System - Stud



GCSKEY

Goat Cable Rail System - Release Key



GCSRWASHER

Goat Cable Rail System - Curved Washer Gasket

2" Post



GCSEND50SS

Fixed Cable End for 2" Post

1-5/8" Post




GCSEND40SS

Fixed Cable End for 1-5/8" Post



GCSENDW

Fixed Cable End for Wood Post




GCSADJEND40SS

Adjustable Cable End for 40mm Post

02 RAILING HARDWARE

Hulk Series



Hydraulic Hinges – Hulk Series

Hulk Series



Finishes

- Brushed Stainless
- Matte Black Anodized Aluminum
- Polished Stainless
- More Finishes Online

Wall To Glass

Glass To Glass


Hold Type	Material	SKU	Hold Type	Material	SKU
Non Holds Open	SS304	HULK90NHO	Non Holds Open	SS304	HULK180NHO
Holds Open	SS304	HULK90HO	Holds Open	SS304	HULK180HO
Non Holds Open	SS316	HULK90NHO	Non Holds Open	SS316	HULK180NHO
Holds Open	SS316	HULK90HO	Holds Open	SS316	HULK180HO

Grey Goat Color Samples Kit

Explore upcoming color finishes on our website.



Frameless Shower Hardware



This color tower was created for one-time distribution only. For the most up-to-date selection of available finishes, please visit our website at ggshardware.com.


Railing Hardware



Commercial Finishes



Future Colors



*These finishes aren't listed on our website yet — but they're available in our color chain. If you're interested, we'd be happy to provide upon request!

Don't have an account?

Sign up now at GGSHARDWARE.COM and get approved by one of our representatives same day! Check Page #4 for more info!

Need Help ?

Call our office today and speak to one of our friendly specialist



02 RAILING HARDWARE

Pool Fencing Hardware

Latches with Lock & Floor Lock **160**

Latches with Lock & Brackets **161**

Latches Hinges **162**



Latches with Lock

Pool Fencing Hardware



Finishes



Specification


- **Material:** High-grade SS316 stainless steel.
- **Glass Compatibility:** Fits 8mm, 10mm, and 12mm glass.
- **Application:** Ideal for indoor/outdoor pool fencing.
- **Latch Type:** Various configuration with secure locking.



LDIVE180
180° Glass to Glass





LDIVE90R
90° Round Post to Glass



LDIVE90
90° Wall/Post to Glass

⚠ Visit ggshardware.com
For Glass Fabrication &
Product Information.



LDIVE092IN
90° Glass to Glass - Inswing



LDIVE092OUT
90° Glass to Glass - Outswing



DSDIVE
DIVE Series Pool Fencing Door Stop



BKDIVE
Bottom Keeper



Latches Without Lock

Pool Fencing Hardware



Finishes



Specification


- **Magnetic Latch Mechanism:** Ensures a secure and self-latching system for enhanced safety
- **Premium Material:** SS316 stainless steel for long-lasting durability in harsh environments
- **Glass Compatibility:** Suitable for 8mm, 10mm, and 12mm glass thicknesses
- **Maximum Weight Capacity:** 45kg (100 lbs)
- **Maximum Glass Width:** 40 inches

 <p>NLDIVE90W Glass to Square Post/Wall</p>	 <p>NLDIVE180 180° Glass to Glass</p>	 <p>NLDIVE90RD 90° Glass to Round Post</p>	 <p>NLDIVE90G Glass to Glass 90° - Inswing</p>
---	---	---	--

Brackets



 <p>BDIVE180RD 180° Glass to Glass - Round</p>	 <p>BDIVE180SQ 180° Glass to Glass - Square</p>	 <p>BDIVE90 90° Glass to Glass - Round</p>	 <p>BDIVESQ90 90° Glass to Glass - Square</p>
--	---	---	---



Latches Hinges

Pool Fencing Hardware



Finishes



Specification

- **Material:** High-grade SS316 stainless steel for superior corrosion resistance
- **Glass Compatibility:** Supports 8mm, 10mm, and 12mm tempered glass
- **Heavy-Duty Construction:** Enhanced durability for robust glass-to-glass connections
- **Maximum Weight Capacity:** 45kg (100 lbs)
- **Maximum Glass Width:** 40 inches
- **Regulation Compliant:** Meets pool safety standards for residential and non-residential properties

<div>Heavy Duty</div> <div></div> <div>HDIVE180HD Glass To Glass</div>	<div>Heavy Duty</div> <div></div> <div>HDIVE90HD Glass To Wall / Square Post</div>	<div>Heavy Duty</div> <div></div> <div>HDIVE90RHD Glass To Round Post</div>	<div></div> <div>HDIVE90 Glass to Wall / Square Post</div>
<div></div> <div>HDIVE180 Glass to Glass</div>	<div></div> <div>HDIVE90R Glass to Round Post</div>	<div></div>	

03 STOREFRONT & ENTRANCES HARDWARE

ASSA ABLOY Certified Distributor

Opening Solutions


Panic Device	164	Security Latch Adapter	166	Floating Header	168
Manual & Electric Strike	165	Dummy Device	167	Concealed Door Closer	169



Assa Abloy – Panic Devices (PDU8000)



Finishes



Panic Devices - PDU8000 Series

Combining safety and style, the PDU8000 features an engraved push area with boundary grooves for clear visibility. Available with keyed or non-keyed options, six exterior pulls, and multiple finishes — offering both function and design flexibility.

Specifications

Glass Thickness	3/8" to 13/16"	Handing	<ul style="list-style-type: none"> • Right-hand reverse (swing 3) • Left-hand reverse (swing 4) • Right hand (swing 5) • Left hand (swing 6)
Dimensions	<ul style="list-style-type: none"> • Grip diameter: 11/4" • Projection: 3" 	Options	Custom engraving options available including push area with boundary grooves.
Materials	Stainless steel		
Applications Types	<ul style="list-style-type: none"> • Glass mounted • Rail mounted 		



PDU8000
Standard ROCKWOOD Panic Device
1-3/4" x 4"



PDU8000-1
Panic Device with Full Height L-Shaped Mating Pull



PDU8000-2
Panic Device Half Height L-Shaped Mating Pull



PDU8000-3
Panic Device with Full Height Straight Mating Pull



PDU8000-4
Panic Device with Half Height Straight Mating Pull



PDU8000-5
Panic Device with Short Centered Straight Pull



PDU8000-6
Panic Device with Horizontal Straight Pull

Assa Abloy – Electric & Manual Strike



Finishes



Folger Adam Electric Strikes

The Folger Adam 310-1 (3/4) is an industrial grade electric strike designed specifically for use in glass door applications with addition of a strike plate. The stainless steel construction makes it ideal for strength and corrosion resistance.

Product Features

- Tamper-resistant, heavy duty stainless steel construction
- 3/4" keeper depth
- Plug-in connector
- Fail Safe/Fail Secure
- Non-handed
- Five-year limited warranty



MSK-SGL

Manual Strike - Single Door



MSK-DBL

Manual Strike - Double Door



ESK-SGL

Electric Strike - Single Door



ESK-DBL

Electric Strike - Manual Door

HES 1600 Heavy-Duty Optional Electric Strike

HES Strikes are the most advanced electric strikes available on the market for latchbolt locks. These series set a new standard in the industry by offering dynamic integrated adjustability and field configurable options.

Product Features

- Tamper resistant
- Stainless steel construction
- ESK-9200 and ESK-1600 models are non-handed, ESK-9100 handing required
- Field selectable fail safe/fail secure
- ESK-9100 and ESK-9200 are surface mounted

Static Strength: • 1,500 lbs

Dynamic Strength: • 70 ft-lbs

Endurance Rating: • 1,000,000 cycles

Electrical: ESK-1600

- Dual voltage 12/24 VDC/VAC; 240 mA at 12 VDC/120 mA at 24 VDC ESK-9100
- Adaptable voltage sensing 12/24 VDC/VAC; 240 mA at 12 VDC, 120 mA at 24 VDC ESK-9200
- Adaptable voltage sensing 12/24 VDC/VAC; 240 mA at 12 VDC, 120 mA at 24 VDC

Options: LM for door monitoring (ESK-1600 models only)



ESK-1600-SGL

Electric Strike - Single Door



ESK-1600-DBL

Electric Strike - Double Door

Surface Mount



ESK-9100

Electric Strike - Single Door

Surface Mount



ESK-9200

Electric Strike - Double Door

Assa Abloy – Dummy Devices (DDU8000)



Finishes



Dummy Panic Devices - DDU8000 Series

The DDU8000 Dummy Panic Device suites with the PDU8000 panic device and Rockwood LP3301 locking door pull and maintains design consistency in a space.

Specifications

Glass Thickness	3/8" to 13/16"	Handing	<ul style="list-style-type: none"> • Right-hand reverse (swing 3) • Left-hand reverse (swing 4) • Right hand (swing 5) • Left hand (swing 6)
Dimensions	<ul style="list-style-type: none"> • Grip diameter: 11/4" • Projection: 3" 		
Materials	Stainless steel		
Applications Types	<ul style="list-style-type: none"> • Glass mounted • Rail mounted 	Options	Custom engraving options available including push area with boundary grooves.



DDU8000
Standard ROCKWOOD Dummy Panic Device
1-3/4" x 4"



DDU8000-1
Dummy Panic Device with Full Height
L-Shaped Mating Pull



DDU8000-2
Dummy Panic Device Half Height
L-Shaped Mating Pull



DDU8000-3
Dummy Panic Device with Full
Height Straight Mating Pull



DDU8000-4
Dummy Panic Device with Half
Height Straight Mating Pull



DDU8000-5
Dummy Panic Device with
Short Centered Straight Pull



DDU8000-6
Dummy Panic Device with
Horizontal Straight Pull

Floating Headers



Overview

When opening heights exceed door height recommendations and glass transoms are necessary, floating headers are the perfect solution. They allow for top locking mechanisms, as well as overhead closers, when floor closers are undesirable.

Finishes



HDF-1750x4000
ROCKWOOD 1-3/4" x 4" Floating Header



HDF-1750x4500
ROCKWOOD 1-3/4" x 4-1/2" Floating Header



HDF-2000x6000
ROCKWOOD 2" x 6" Floating Header

Assa Abloy



DLUX4HDC90NHOEXTHD
ROCKWOOD 304 Heavy-Duty Overhead Concealed Door Closer

Product type	SKU
90° Back stop Non-hold open	DLUX4HDC90NHOEXTHD
90° Back stop Hold open	DLUX4HDC90HOEXTHD
105° Back stop Non-hold open	DLUX4HDC105NHOEXTHD
105° Back stop Hold open	DLUX4HDC105HOEXTHD

- **Heavy-Duty Performance:** Supports up to 300 lbs. for interior doors and 250 lbs. for exterior doors.
- **Concealed Installation:** Ensures a sleek, unobtrusive appearance.
- **Durable Cast Iron Body:** Built for long-lasting strength and reliability.
- **Versatile Compatibility:** Suitable for doors up to 48" wide (interior) and 42" wide (exterior).



DLUXPIVHD
DLUX End Load Bottom Pivot - Heavy-Duty (300 lb.)

Key Features

- **Heavy-Duty Capacity:** Supports doors up to 300 lbs. for high-traffic applications.
- **Precise Clearance Adjustments:** Includes shims for bottom clearances ranging from 5/16" to 3/4".
- **Center-Hung Design:** Ensures balanced and smooth door operation.
- **Durable Construction:** Made from high-quality aluminum and stainless steel for long-lasting performance.
- **Easy Installation:** Simple end-load installation into the door rail for convenience.

Rockwood Handles



Finishes



11147

The 11147 Series with Straight 47 Single Bar Set

Product Features

- Heavy-duty straight bar design for commercial and architectural doors
- Compatible with wood, metal, and glass doors
- Constructed from high-quality aluminum, brass, bronze, or stainless steel
- Available in a range of sizes, lengths, and bar diameters
- Offered in multiple mounting styles including back-to-back and single side
- Optional "PUSH" or "PULL" engraving for clear user direction
- Wide selection of architectural finishes to suit any design
- ANSI 156.6 compliant for durability and performance



11147OS

The 11147 Series with Offset 47 Single Bar Set

Product Features

- Sleek offset handle design for a modern and ergonomic look
- Engineered for use on glass, wood, or metal doors
- Built with durable materials: aluminum, brass, bronze, or stainless steel
- Available in various projections, sizes, and bar thicknesses
- Multiple mounting options including concealed and exposed fasteners
- Customizable with "PUSH" or "PULL" engraving for clear function labeling
- Offered in a range of premium finishes for design flexibility
- Meets ANSI 156.6 standards for reliable commercial-grade use

Floating Headers



03 STOREFRONT & ENTRANCES HARDWARE

Solidity Hydraulic Bottom Patch




Solidity Hydraulic Bottom Patch

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



Finishes




100Kg

- **Maximum Weight:** 100KG (220.46LBS)
- **Maximum Door Width:** 39" (1000mm)
- Two Adjustable Speed Settings
- Hold Open at 90°
- Cycle Tested for 500,000 Operations

150Kg

- **Maximum Weight:** 150 Kg (330.70 lb)
- **Maximum Door Width:** 48" (1220mm)
- Two Adjustable Speed Settings
- Hold Open at 90°
- Cycle Tested for 500,000 Operations

Full Kit - Includes Body & Covers Plates



SOL100HO
100kg Hold Open

Hold Type

Maximum Door Weight

SKU

Hold Open

100kg

SOL100HO

Hold Open

150kg

SOL150HO

Non-Hold Open

100kg


SOL100NHO

Non-Hold Open

150kg

SOL150NHO

Body Only



SOL150HONCP
Blank Body - Without Cover Plates

Hold Type

Maximum Door Weight

SKU

Hold Open

100kg

SOL100HONCP

Hold Open

150kg

SOL150HONCP

Non-Hold Open

100kg

SOL100NHONCP

Non-Hold Open

150kg

SOL150NHONCP

Cover Plates Only




SOLCP
Solidity Series Cover Plates

Bottom Base Only



SOLBP
Solidity Series Bottom Base



03 STOREFRONT & ENTRANCES HARDWARE

Patch Fittings & Transom

Patch Fittings Configurations 174

Patch Fittings & Transom 176



Patch Fittings Configurations



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

		Patch Fitting (PFIT Series) Top Patch with Pivot Insert PFIT20A
		Patch Fitting (PFIT Series) Bottom Patch with Pivot Insert PFIT10
 100KG		Solidity Series Hydraulic Bottom Patch 100kg Hold Open SOL100HO
 150KG		Solidity Series Hydraulic Bottom Patch 100kg Hold Open SOL150HO
		Patch Fitting (PFIT Series) Transom - Wall Mount PFIT34
		Patch Fitting (PFIT Series) Transom - Glass Mount With Pivot Pin PFIT40
		Patch Fitting (PFIT Series) L-Shape Connector - No Door Stop PFIT61
		Patch Fitting (PFIT Series) L-Shape Connector With Door Stopper PFIT60
		Patch Fitting (PFIT Series) L-Shape Connector With Heavy Duty Door Stop PFIT60HD




Patch Fittings Configurations




For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Configuration - 1




1	PFIT20A	Patch Fitting (PFIT Series) – Top Patch with Pivot Insert
2A	PFIT10	Patch Fitting (PFIT Series) – Bottom Patch with Pivot Insert
2B	SOL100HO	Solidity Series Hydraulic Bottom Patch – 100kg Hold Open
2C	SOL150HO	Solidity Series Hydraulic Bottom Patch – 150kg Hold Open

Configuration - 2




1	PFIT20A	Patch Fitting (PFIT Series) – Top Patch with Pivot Insert
2A	PFIT10	Patch Fitting (PFIT Series) – Bottom Patch with Pivot Insert
2B	SOL100HO	Solidity Series Hydraulic Bottom Patch – 100kg Hold Open
2C	SOL150HO	Solidity Series Hydraulic Bottom Patch – 150kg Hold Open
3	PFIT34	Patch Fitting (PFIT Series) – Transom – Wall Mount

Configuration - 3




1	PFIT20A	Patch Fitting (PFIT Series) – Top Patch with Pivot Insert
2A	PFIT10	Patch Fitting (PFIT Series) – Bottom Patch with Pivot Insert
2B	SOL100HO	Solidity Series Hydraulic Bottom Patch – 100kg Hold Open
2C	SOL150HO	Solidity Series Hydraulic Bottom Patch – 150kg Hold Open
3	PFIT34	Patch Fitting (PFIT Series) – Transom – Wall Mount
4A	PFIT61	Patch Fitting (PFIT Series) – L-Shape Connector – No Door Stop
4B	PFIT60	Patch Fitting (PFIT Series) – Panel Glass to Glass – L-Shape Connector With Door Stopper
4C	PFIT60HD	Patch Fitting (PFIT Series) – L-Shape Connector – with Heavy Duty Door Stop

Configuration - 4



1	PFIT20A	Patch Fitting (PFIT Series) – Top Patch with Pivot Insert
2A	PFIT10	Patch Fitting (PFIT Series) – Bottom Patch with Pivot Insert
2B	SOL100HO	Solidity Series Hydraulic Bottom Patch – 100kg Hold Open
2C	SOL150HO	Solidity Series Hydraulic Bottom Patch – 150kg Hold Open
3	PFIT34	Patch Fitting (PFIT Series) – Transom – Wall Mount
5	PFIT40	Patch Fitting (PFIT Series) – Transom – Glass Mount

Configuration - 5



1	PFIT20A	Patch Fitting (PFIT Series) – Top Patch with Pivot Insert
2A	PFIT10	Patch Fitting (PFIT Series) – Bottom Patch with Pivot Insert
2B	SOL100HO	Solidity Series Hydraulic Bottom Patch – 100kg Hold Open
2C	SOL150HO	Solidity Series Hydraulic Bottom Patch – 150kg Hold Open
4A	PFIT61	Patch Fitting (PFIT Series) – L-Shape Connector – No Door Stop
4B	PFIT60	Patch Fitting (PFIT Series) – Panel Glass to Glass – L-Shape Connector With Door Stopper
4C	PFIT60HD	Patch Fitting (PFIT Series) – L-Shape Connector – with Heavy Duty Door Stop
5	PFIT40	Patch Fitting (PFIT Series) – Transom – Glass Mount

Patch Fittings & Transom



Finishes

Brushed Stainless
 Matte Black
 Satin Brass
 Polished Stainless
 Satin Anodized



PFIT20A
Top Patch
with Pivot Insert



PFIT10
Bottom Patch
with Pivot Insert



PFIT70
Panel Glass to Glass



PFIT34
Transom - Wall Mount



PPIV401-2H
Top Free Swing Pivot
2 Holes



PFIT20ADJ
Top Patch with Adjustable
Closer Insert



PFIT40
Transom - Glass Mount



PFIT41L
Transom With Left Fin Support
Glass Mount



PFIT41R
Transom With Right Fin Support
Glass Mount



Patch Fittings & Transom



Finishes

Brushed Stainless

Matte Black

Satin Brass

Polished Stainless

Satin Anodized



PPIV401

Top Free Swing Pivot
3 Holes



PFIT20C

Top Patch
With Closer Insert



PFIT60HD

L-Shape Connector
With HD Door Stop



PFIT80

Panel Glass to Glass
4-Way Connector



PFIT94

Ceiling Mounted Support
Fin Connector



PFIT81

4-Way With Fin Connector



PPIV402

Bottom Free
Swinging Pivot for Floor Mount



PFIT61

L-Shape Connector - No Door Stop



PFIT60

L-Shape Connector With Door Stopper



Patch Fittings & Transom



Finishes



PPIV403

Bottom Door Free Swinging Pivot



PFITGASKET

Gaskets For Wall Mount Top & Bottom Patch



PFINTOP

Top Hole For Patch Pivots



PFINDC

Top Hole For Commercial Door Closers



PFINBOT

Bottom Hole for Patch Pivots




PFINDS

Top Door Stops



PFINTOPPIV


Top Patch Pivots



Electromagnetic Entry Door Lock



Finishes



Product Overview

NE-600S Single Door Magnetic Lock with LED indicator and door status signal output. Compatible with glass, wood, metal, and fire doors. Hoisting design allows quick, easy installation. Includes accessories for inward, frameless, and narrow doors. Anti-residual magnetism ensures safer, more reliable access control.



ML600SGL

Single Door Magnetic Lock - 600Kg



ML600DBLSA

Double Door Magnetic Lock - 600Kg



MLSGZLBRKT

Single Door Magnetic Lock Strike Brackets



MLDBLZLBRKT

Double Door Magnetic Lock Strike Brackets





03 STOREFRONT & ENTRANCES HARDWARE

Commercial U-Channels

Commercial U-Channel & End Cap **182**

Vinyl Roller Tool & Mall Clamps **183**



Commercial U-Channels

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.




Finishes



Specification

- **Versatile Applications:** Ideal for glass partitions, wine rooms, architectural installations, retail store fronts, conference rooms, and glass balustrades.
- **Low-Profile Design:** Shallow 1", 1.5" & 2" height options for a minimalistic look while ensuring stability.
- **Glass Compatibility:** Suitable for glass thicknesses of 10mm (3/8") and 12mm (1/2").

144" & 240" Length



CU1X1,
CU1X1.5,
CU1X2

Commercial U-Channel

Dimension

SKU

1 X 1" (144" Length)

CU1X1

1 X 1-1/2" (144" Length)

CU1X1.5

1 X 2" (144" Length)

CU1X2

1 X 1" (240" Length)

CU1X1-240


1 X 1-1/2" (240" Length)

CU1X1.5-240

1 X 2" (240" Length)

CU1X2-240

10mm / 12mm / Custom



CURUB

Roll-In Rubber

Dimension

SKU

12mm

CURUB12

12mm
500' Length Roll

CURUB10-500

10mm

CURUB10

10mm
500' Length Roll

CURUB10-500

0.200"
1' Length

CURUBCUSTOM

0.200"
500' Length Roll

CURUBCUSTOM500

ROLLER01 *

Vinyl Roller Tool

Mall Clamps








Finishes

- Brushed Stainless
- Matte Black
- Custom Finishes

Specification


- Versatile Glass Compatibility:** Works with 3/8" to 3/4" (10 to 19 mm) thick monolithic tempered glass; special-order studs available for thicker applications.
- Secure and Stable Joint:** Connects vertical glass panels to reduce movement and improve structural integrity.
- Durable Build:** Constructed from Grade 304 Stainless Steel for lasting strength, offered in brushed or polished finishes.
- Simple Installation:** Comes with flat head Phillips screws (included), making for a quick and secure setup.
- Safety Gap Recommendation:** A minimum gap of 7/32" (5.6 mm) between panels is suggested for optimal stability.

 <div>MC180 180° Fixed Clamp</div>	 <div>MC90 90° Fixed Clamp</div>	 <div>MC135 135° Fixed Clamp</div>	 <div>MCWALL Wall Mount, Offset</div>
 <div>AMC180 * Acrylic 180° Fixed Clamp</div>	 <div>AMC90 * Acrylic 90° Fixed Clamp</div>	 <div>AMC135 * Acrylic 135° Fixed Clamp</div>	



03 STOREFRONT & ENTRANCES HARDWARE

Hulk Series



Hydraulic Hinges – Hulk Series

Hulk Series



Finishes

Brushed Stainless

Matte Black Anodized Aluminum

Polished Stainless

More Finishes Online

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Wall To Glass



Hold Type	Material	SKU
Non Holds Open	SS304	HULK90NHO
Holds Open	SS304	HULK90HO
Non Holds Open	SS316	HULK90NHO
Holds Open	SS316	HULK90HO

Glass To Glass



Hold Type	Material	SKU
Non Holds Open	SS304	HULK180NHO
Holds Open	SS304	HULK180HO
Non Holds Open	SS316	HULK180NHO
Holds Open	SS316	HULK180HO





03 STOREFRONT & ENTRANCES HARDWARE

Glass Door Locks

Glass Door Locks 188

Glass Display Hardware 190



Glass Door Locks



Finishes



Brushed
Stainless



Matte
Black



Satin
Brass



Polished
Stainless



Satin
Anodized



More
Finishes Online

For glass fabrication details, CAD files, and the latest product information, please visit our website.
 Stock and finish availability may vary by product.



GDL311GM

Glass Mount
Mounted Latch



GDL311WM

Wall Mount
Mounted Latch



DGDG

Digital Glass Door Lock
Glass & Wall Mount



GDLUSSET

American Style Cylinder
Patch Lock & Keeper Set



GDLUSK

Patch Lock Keeper
For American Style Cylinder



GDLUS

Patch Lock
With American Style Cylinder



GDLEU

Patch Lock With
European Style Design



GDLEUK

Patch Lock Keeper For
European Style Lock



GDLEUSET

European Style Patch
Lock & Keeper Set



Glass Door Locks



Finishes

Brushed Stainless

Matte Black

Satin Brass

Polished Stainless

Satin Anodized

More Finishes Online

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



GDLRD90D

Glass to Wall - Double Sided - Round



GDLRD180D

Glass to Glass - Double Sided - Round




GDLRD90S

Glass to Wall - Single Sided - Round



GDLRD180S

Glass to Glass - Single Sided - Round



GDLTT

Thumbturn Lock



GDLTTK

Thumbturn Keeper



GDLTTSET

Thumbturn Lock & Keeper Set



GTDLGM

Privacy Glass Door Lock for Washroom - Thumbturn



Glass Display Hardware



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



GDLMINI239
Showcase Glass Door Lock
Single Door



GDLMINI258
Showcase Glass Door Lock
Double Door

3/4" Ø Base
1-1/4" Ø Base



DSO1144
Glass Display Standoffs



JEN037JR
Square Full Plate
Wall to Glass



CARA01
Square Pivot
Floor / Ceiling to Glass

**BEST
SELLER**



DK100
100 Style Back to Back Knob


NEW



DK106
106 Style Back to Back Knob



DK140
140 Style Back to Back Knob



DKSQ
SQ Style Back to Back Knob



03 STOREFRONT & ENTRANCES HARDWARE

Commercial Center Lock

Storeroom Center Lock **192** Affordable Center Lock **194**
Classroom Center Lock **193**



Storeroom Center Lock

Commercial Center Lock with Electric Strike



Finishes

Brushed Stainless

Matte Black Anodized Aluminum

Polished Stainless

Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.

LH-Storeroom



GDLC SINL

Inswing, Left Hand - LH

LHR-Storeroom



GDLC SOUTL

Outswing, Left Hand - LHR

RH-Storeroom



GDLC SINR

Inswing, Right Hand - RH

RHR-Storeroom



GDLC SOUTR

Outswing, Right Hand - RHR

Manual Strike Box




GDLCSTK

Manual Strike Box

All In One Strike



12V / 24V / Fail Safe / Fail Secure



HES5200C

HES5200C Electric Strike Complete Pack

Electric Strike Box



GDLCCECSTKL

Electric Strike Box - Left Handed

Electric Strike Box



GDLCCECSTKR

Electric Strike Box - Right Handed

Cover Only



GDLCCECSTKR

Electric Strike Box - Right Handed



Classroom Center Lock

Commercial Center Lock with Electric Strike



Finishes

Brushed Stainless

Matte Black Anodized Aluminum

Polished Stainless

Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.

LH-Classroom



GDLCCLNL

Inswing, Left Hand - LH

LHR-Classroom



GDLCCLOUTL

Outswing, Left Hand - LHR

RH-Classroom



GDLCCLNR

Inswing, Right Hand - RH

RHR-Classroom



GDLCCLOUTR

Outswing, Right Hand - RHR

Manual Strike Box



GDLCSTK

Manual Strike Box

All In One Strike



12V / 24V / Fail Safe / Fail Secure



HES5200C

HES5200C Electric Strike Complete Pack

Electric Strike Box



GDLCCECSTKL

Electric Strike Box - Left Handed

Electric Strike Box



GDLCCECSTKR

Electric Strike Box - Right Handed

Cover Only



GDLCCECSTKR

Electric Strike Box - Right Handed





Striker Center Lock Series

Commercial Center Lock with Electric Strike

Finishes

Brushed Stainless

Matte Black Anodized Aluminum

Polished Stainless

Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Passage



LH5X45PAS *
Lever & Latch Lock - Without Keyed Lock

Manual Strike



LHKPR *
Manual Strike Box

Electric Strike



LHESAFE, LHESECURE *
Electric Strike Box

Entrance

Storeroom


Classroom



LH5X45ENT, LH5X45STRM & LH5X45CLRM *
Lever & Latch Lock - With Keyed Lock



Note: Visit ggshardware.com For Glass Fabrication & Product Information.



* For the most up-to-date product availability, visit our website.

Commercial Ladder Pulls

Ladder Pulls-Back To Back	196	Ladder Pulls - Square - SQS Series	200	Ladder Pulls - Offset & Curved	204
Ladder Pulls - Offset Back to Back	197	Ladder Pulls - Square - SQR Series	201		
Ladder Pulls - ADA Locking	198	Ladder Pulls - Tubular	202		
Ladder Pulls - Single-Sided	199	Sauna Handle	203		




Ladder Pulls-Back To Back

Commercial Ladder Pulls



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.


Specification

- **Suitable for Glass Thickness:** 3/8" to 3/4" (10mm - 19mm)
- **Suitable for Wood/Aluminum Door Thickness:** 1-3/4" (44mm)
- **Available in Sizes:** 12", 24", 30", 36", 48", 60", 72", 84" and custom 96" length
- Constructed from durable 304 Grade Stainless Steel, [check ggshardware.com](https://www.ggshardware.com) for 316 Stainless Steel
- Prepped for back-to-back mounting, includes two mid-posts and fasteners for simple installation



LP36
36" (24" CTC)
Back To Back


Overall	CTC	SKU
12"	6"	LP12
24"	12"	LP24
30"	18"	LP30
36"	24"	LP36
48"	36"	LP48
60"	48"	LP60
72"	60"	LP72
84"	72"	LP84
96"	84"	LP96



SCREW-LADDERBOLT
M8 x 3-in Phillips Flat Head
Screws for Aluminum Doors



CW14
Finishing Cap Washer - Single



Available in Custom Lengths (X) and Diameters (Y) To Match Your Design Specifications.


Choose from premium finish options, leather wraps, and powder-coated colors for a tailored architectural look.

Ladder Pulls – Offset Back to Back

Commercial Ladder Pulls




Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website.
 Stock and finish availability may vary by product.

Specification

- **Suitable for Glass Thickness:** 3/8" to 3/4" (10mm - 19mm)
- **Suitable for Wood/Aluminum Door Thickness:** 1-3/4" (44mm)
- **Material:** Durable 304 Grade Stainless Steel
- **Offset Design:** Offers a distinctive, modern aesthetic
- Prepped for back-to-back mounting, includes two mid-posts and fasteners for simple setup



OSLP36
 36" (24" CTC)
 Offset Back to Back

Overall	CTC	SKU
24"	12"	OSLP24
36"	24"	OSLP36
48"	36"	OSLP48
60"	48"	OSLP60
72"	60"	OSLP72




OSLPKIT
 Offset Kit



SCREW-LADDERBOLT
 M8 x 3-in Phillips Flat Head
 Screws for Aluminum Doors




CW14
 Finishing Cap Washer - Single



Available In Custom Lengths (X) and Diameters (Y) To Match Your Design Specifications.

Choose from premium finish options, leather wraps, and powder-coated colors for a tailored architectural look.



Ladder Pulls – ADA Locking

Commercial Ladder Pulls



Finishes

- Brushed Stainless Steel


Polished Stainless Steel
- Matte Black Anodized Aluminum

Custom Finishes

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Specification

- **Suitable for Glass Thickness:** 1/2" (12mm) to 3/4" (19mm) tempered glass
- **Fully Concealed Deadbolt Locking System:** Includes top-mounted keyed thumb turn and bottom locking mechanism
- **Material:** 304 Grade Stainless Steel for superior durability and corrosion resistance
- **ADA Compatible:** Ensures accessibility compliance for various environments

<div>48" Overall</div> <div>36" CTC</div> <div>  </div>	Overall	CTC	SKU
	48"	36"	LOCKLP48
	60"	48"	LOCKLP60
	72"	60"	LOCKLP72


LOCKLP48

48" ADA Locking Ladder Pull - Back to Back

72" ADA Locking Ladder Pull - Back to Back


LPDPK **

Dust proof Keeper




ICCOREBS


IC Core Lock Cylinder - 7 Pin SFIC



Interchangeable Core

Best Option to lock a Sliding Door 7 Pin SFIC (Small Format Interchangeable Core)





USE ONLY MONOLITHIC TEMPERED GLASS

Ladder Pulls – Single-Sided

Commercial Ladder Pulls




Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.

Specification

- **Suitable for Glass Thickness:** 3/8" to 3/4" (10mm - 19mm)
- **Available Sizes:** 8", 16", 24", 36", 48", 60", and 72" overall lengths
- **Material:** Durable 304 Grade Stainless Steel
- **Simple Installation:** Prepped for back-to-back mounting with two mid-posts and fasteners included
- Custom lengths and finishes available (email: products@ggshardware.com)

 SSLP36 36" (24" CTC) - Single Sided	Overall	CTC	SKU
	16"	12"	SSLP16
	24"	12"	SSLP24
	36"	24"	SSLP36
	48"	36"	SSLP48
	60"	48"	SSLP60
	72"	60"	SSLP72



SSLPRDCAP *
SSLPSQCAP *
Single Sided Ladder Pull Cap - Round/Square Option

For Aluminum Door



CW14
Finishing Cap Washer - Single



Ladder Pulls – Square – SQS Series

Commercial Ladder Pulls




Finishes




For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.

Specification

- **Suitable for Glass Thickness:** 3/8" to 3/4" (10mm - 19mm)
- **Suitable for Wood/Aluminum Door Thickness:** 1-3/4" (44mm)
- **Available Sizes:** 24", 36", 48", and 72" overall lengths
- **Material:** High-quality 304 Grade Stainless Steel
- **Simple Installation:** Ready for back-to-back mounting with mid-posts and fasteners included.

 <p>SQSLP36 36" (24" CTC) Square Back to Back</p>	Overall	CTC	SKU
	24"	12"	SQSLP24
	36"	24"	SQSLP36
	48"	36"	SQSLP48
	60"	48"	SQSLP60
	72"	60"	SQSLP72



SSLPSQCAP *
Single Sided Ladder Pull Cap - Square



CW14
Finishing Cap Washer - Single




Ladder Pulls – Square To Round – SQR Series

Commercial Ladder Pulls



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Specification

- **Suitable for Glass Thickness:** 3/8" to 3/4" (10mm - 19mm)
- **Suitable for Wood/Aluminum Door Thickness:** 1-3/4" (44mm)
- **Material:** High-quality 304 Grade Stainless Steel
- **Simple Installation:** Prepped for back-to-back mounting with two round mid-posts and fasteners included



SQRLP48

48" (36" CTC) Back to Back

Overall

CTC

SKU

24"

12"

SQRLP24

36"

24"

SQRLP36

48"

36"

SQRLP48

60"

48"

SQRLP60

72"

60"

SQRLP72




SSLPRDCAP

Single Sided Ladder Pull Cap – Round



CW14

Finishing Cap Washer – Single




Ladder Pulls – Tubular

Commercial Ladder Pulls



Finishes



Specification

- **Material:** High-grade SS304 stainless steel for enhanced durability
- **Tubular Diameter:** 1.25" (32mm) for a sleek, modern look
- **Suitable for Various Applications:** Ideal for wine cellars, gyms, and commercial business spaces

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

12" Overall

12" CTC



RCM12X12

12" Tubular Commercial Pull - 12" CTC

18" Overall

18" CTC




RCM18X18

18" Tubular Commercial Pull - 18" CTC

24" Overall

24" CTC



RCM24x24

24" Tubular Commercial Pull - 24" CTC

Single Side Handle Option




LPHS

Cap For Single Sided Handles

Grey Goat Color Sample Tower
Available at ggshardware.com



**USE ONLY
MONOLITHIC
TEMPERED GLASS**



Sauna Handle

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



SAUN19LP12
Sauna Handle 12" Ladder Pull Handle


Specification

- **Heat and Moisture Resistant:** Constructed from materials designed to thrive in sauna conditions.
- **Ergonomic Grip:** Provides a secure and comfortable feel during use.
- **Sleek Design:** Perfectly suited for modern and traditional sauna aesthetics.
- **Hustle Free Installation:** Includes all necessary mounting hardware for easy installation.

Finishes



Don't Burn Your Hand!
Use Grey Goat Sauna Handles.



SAUN25LP12
Sauna Handle 12" Tubular Ladder Pull Handle



SAUN33R17
Sauna Handle 17" Tubular Ladder Pull Handle



SAUN30S19
Sauna Handle 19" Square Handle



SAUN19LP24
Sauna Handle 24" Square Ladder Pull Handle



SAUN25LP24
Sauna Handle 24" Tubular Ladder Pull Handle



SAUN38S31
Sauna Handle 31" Square Handle



SAUN39R31
Sauna Handle 31" Tubular Ladder Pull Handle



SAUN39R47
Sauna Handle 47" Tubular Ladder Pull Handle

Ladder Pulls-Offset & Curved Ladder Pull Handle



Commercial Ladder Pulls

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

12" Overall



OSTUB12

12" Offset Tubular Commercial Pull


Specification

- **Material:** Premium SS304 stainless steel for superior durability
- **Tubular Diameter:** 1" (25.4mm) for a modern and comfortable grip
- **Suitable for Glass Thickness:** 3/8" - 3/4" (10mm - 19mm) tempered glass
- **Suitable for Wood/Aluminum Door Thickness:** Up to 1-3/4" (44mm)
- **Offset:** 3" (76 mm) Center-to-Center
- **Simple Installation:** Prepped for back-to-back mounting with included fasteners

Finishes



20" Overall



CURLP20

Curved Ladder Pull Handle 20" (11" CTC)

Specification

- **Contemporary Design:** Enhances the look of any door with its smooth, curved aesthetic.
- **Durable Construction:** Made from premium materials for reliable performance and longevity.
- **Comfortable Grip:** Designed for a secure and ergonomic hold.
- **Versatile Applications:** Ideal for a wide range of door styles and settings.
- **Easy Installation:** Includes M6 thread for hassle-free mounting.

Finishes



CW14

Finishing Cap Washer - Single



03 STOREFRONT & ENTRANCES HARDWARE

Mechanical U-Channels

Economy Series 206

Comfort Series 207

Additional Components 208



Economy Series – Fixed

Mechanical U-Channels




Finishes




Specification

- **Overall Cross Section Size:** 1-9/16" x 1-7/16" with Short Cladding.
- **Overall Cross Section Size:** 4-1/2" x 1-7/16" with Tall Cladding.
- **Glass Compatibility:** Suitable for 3/8" to 1/2" (10 to 12 mm) monolithic tempered glass
- **No Glass Drilling Required:** Eliminates the need for holes in the glass, streamlining installation
- **Available Length:** 10FT (120") header length for versatile application




MECU10

Mechanical U-Channel
1-9/16" Cladding - 120" Length




MECU12

Mechanical U-Channel
1-9/16" Cladding - 120" Length




MECU10LRG

Mechanical U-Channel
4-1/4" Cladding - 120" Length



MECU12LRG

Mechanical U-Channel
4-1/4" Cladding - 120" Length



Comfort Series – Adjustable

Mechanical U-Channels




Finishes




Specification

- **Overall Cross Section Size:** 1-9/16" x 1-7/16" with Short Cladding.
- **Overall Cross Section Size:** 4-1/2" x 1-7/16" with Tall Cladding.
- **Glass Compatibility:** Suitable for 3/8" to 1/2" (10 to 12 mm) monolithic tempered glass
- **No Glass Drilling Required:** Eliminates the need for holes in the glass, streamlining installation
- **Available Length:** 10FT (120") header length for versatile application




MECUADJ10

Mechanical U-Channel - Adjustable
1-9/16" Cladding - 120" Length




MECUADJ12

Mechanical U-Channel - Adjustable
1-9/16" Cladding - 120" Length



MECUADJ10LRG

Mechanical U-Channel - Adjustable
4-1/4" Cladding - 120" Length



MECUADJ12LRG

Mechanical U-Channel
4-1/4" Cladding - 120" Length










Additional Components

Mechanical U-Channels



Finishes

- Brushed Stainless
- Matte Black
- Satin Anodized
- Custom Finishes

 <p>MECUCLD Additional Set of Cladding - 1-9/16" Height</p>	 <p>MECUCLDLRG Additional set of Cladding - 4-1/8" Height</p>	 <p>MECUSB Additional Blocks for Mechanical U-Channel</p>	
 <p>MECUEND Additional Endcaps for 1-9/16" Height</p>	 <p>MECUENDLRG Additional Large Endcaps for 4-1/4" Height</p>	 <p>MECUBR Additional Brackets 1/2" or 3/8"</p>	 <p>MECU Additional Extrusion Body</p>



03 STOREFRONT & ENTRANCES HARDWARE

Sliding Door Kits – LAG Series

LAG Series - Glass Mount 210

LAG Series - Wall Mount 211

LAG Series - Double Door Wall Mount 212



LAG Series – Glass Mount

Sliding Door Kits - LAG Series

For glass fabrication details, CAD files, and the latest product information, please visit our website.
 Stock and finish availability may vary by product.



Kit Includes

- 6 x Glass Mount Brackets
- 1 x Sliding Tube
- 1 x Left Door Stop
- 1 x Right Door Stop
- 2 x Door Rollers
- 1 x Thru-Glass Pull
- 1 x Floor Guide

Key Features

- High-Quality Materials:** Crafted from Grade 316 Stainless Steel for exceptional corrosion resistance and longevity.
- Hustle Free Installation:** The kit contains all essential hardware required for a seamless installation of 3/8" or 1/2" (10 or 12 mm) tempered glass panels.
- Versatile Applications:** Suitable for both interior and exterior installations.

Specification

SKU NO.	Stainless Steel Rod	Weight Capacity	Maximum Door Height
LAGGM108	108" length, 3/32" thickness	Supports doors up to 220 lbs (100 kg)	98-7/16" (2.5 m)

Finishes

- Brushed Stainless
- Matte Black
- Polished Stainless
- Satin Brass
- Custom Finishes

Included in Kit



LAGGM
Glass Mount Bracket

Included in Kit



LAGH108
LAG Series - Header Bar - 108" Length

Included in Kit



LAGDSL
Left Door Stop

Included in Kit



LAGDSR
Right Door Stop

Included in Kit



LAGRO
LAG Series - Door Roller

Included in Kit



GLASSPULL
Thru-Glass Pulls

Included in Kit




LAGFG
Floor Guide

Included in Kit



LAGHEC *
End Cap

Note: Visit ggshardware.com For Glass Fabrication & Product Information.



USE ONLY MONOLITHIC TEMPERED GLASS

LAG Series – Wall Mount

Sliding Door Kits - LAG Series

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.



Kit Includes

- 5 x Wall Mount Brackets
- 1 x Sliding Tube
- 1 x Left Door Stop
- 1 x Right Door Stop
- 2 x Door Rollers
- 1 x Thru-Glass Pull
- 1 x Floor Guide
- 2 x End Cap
- 1 x Tube Support

Key Features

- High-Quality Materials:** Crafted from Grade 316 Stainless Steel for exceptional corrosion resistance and longevity.
- Hustle Free Installation:** The kit contains all essential hardware required for a seamless installation of 3/8" or 1/2" (10 or 12 mm) tempered glass panels.
- Smooth Sliding Mechanism:** Designed and made for seamless and quiet movement.

Specification

SKU NO.	Stainless Steel Rod	Weight Capacity	Maximum Door Height
LAGWM108	108" length, 3/32" thickness	Supports doors up to 220 lbs (100 kg)	98-7/16" (2.5 m)

Finishes

- Brushed Stainless
- Matte Black
- Polished Stainless
- Satin Brass
- Custom Finishes

Included in Kit



LAGWMB

Wall Mount Bracket

Included in Kit



LAGH108

LAG Series - Header Bar - 108" Length

Included in Kit



LAGDSL

Left Door Stop

Included in Kit



LAGDSR

Right Door Stop

Included in Kit



LAGRO

LAG Series - Door Roller

Included in Kit



GLASSPULL

Thru-Glass Pulls

Included in Kit



LAGFG

Floor Guide

Included in Kit



LAGHEC *

End Cap

Included in Kit



LAGWM

Tube Support



USE ONLY
MONOLITHIC
TEMPERED GLASS

LAG Series – Double Door Wall Mount

Sliding Door Kits - LAG Series



Kit Includes

5 x Wall Mount Brackets
1 x Sliding Tube
1 x Left Door Stop
1 x Right Door Stop
4 x Door Rollers
1 x Thru-Glass Pull
1 x Floor Guide
2 x End Cap
1 x Tube Support

Key Features

- **High-Quality Materials:** Crafted from Grade 316 Stainless Steel for exceptional corrosion resistance and longevity.
- **Hustle Free Installation:** The kit contains all essential hardware required for a seamless installation of 3/8" or 1/2" (10 or 12 mm) tempered glass panels.
- **Smooth Sliding Mechanism:** Designed and made for seamless and quiet movement.

Specification

SKU NO.	Stainless Steel Rod	Weight Capacity	Maximum Door Height
LAGDDWM216	216" length, 3/32" thickness	Supports doors up to 220 lbs (100 kg)	98-7/16" (2.5 m)

Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Included in Kit



LAGWMB

Wall Mount Bracket

Included in Kit



LAGH216

LAG Series - Header Bar - 216" Length

Included in Kit



LAGDSL

Left Door Stop

Included in Kit



LAGDSR

Right Door Stop

Included in Kit



LAGRO

LAG Series - Door Roller

Included in Kit



GLASSPULL

Thru-Glass Pulls

Included in Kit



LAGFG

Floor Guide

Included in Kit



LAGHEC

End Cap

Included in Kit



LAGWM

Tube Support



03 STOREFRONT & ENTRANCES HARDWARE

Soft-Closing Sliding Door System



Soft-Closing Sliding Door System



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Key Features:

- **Soft-Closing Mechanism:** Included in Kit, the Hydraulic Damper ensures gentle and noiseless door movement.
- **High Load Capacity:** Supports glass panels up to 264.5 lb (120 kg).
- **Universal Compatibility:** Suitable for tempered glass with a thickness of 3/8" to 1/2" (10 to 12 mm).
- **Track Length:** 3 meters for flexible installation options.
- **Durable Construction:** Made from premium aluminum for long-lasting performance.



03 STOREFRONT & ENTRANCES HARDWARE

EZY Sliding Door Kits




EZY1 Sliding Door Kits – Facia Mount

Designers
Selected



Finishes




Specification


- **Regular & Heavy Duty Rating:** Supports up to 80 kg & 120 kg of weight for reliable performance.
- **Glass Compatibility:** Suitable for 3/8" to 1/2" (10 mm to 12 mm) monolithic tempered glass.
- **Header Track Length: 118"**




EZYS1SD
Single Sliding Door Kit




EZYS1HSDS (Heavy Duty)
Single Sliding Door Kit




EZYS1HSD
Single Sliding Door Track (118" Length)




EZYS1HSDP
Single Door + Panel Track (118" Length)



EZYS1DD
Double Sliding Door Kit




EZYS1HDD (Heavy Duty)
Double Sliding Door Kit




EZYS1HDD
Double Sliding Door Track (118" Length)



EZYS1END
Endcap for EZY1 Series Sliding Door Kit



EZYS1SDP
Single Door + Fixed Panel Kit



EZYS1HSDP (Heavy Duty)
Single Door + Fixed Panel Kit



EZYS1RDKIT
Sliding Door Kit - Regular Duty



EZYS1HDKIT (Heavy Duty)
Sliding Door Kit - Heavy Duty



EZYS1WM
Wall Mount Bracket

Grey Goat Color Sample Tower
Available at ggshardware.com




EZY2 Sliding Door Kits – Ceiling Mount

Cladding Option Available



Finishes



Specification


- **Regular & Heavy Duty Rating:** Supports up to 80 kg & 120 kg of weight for reliable performance.
- **Glass Compatibility:** Suitable for 3/8" to 1/2" (10 mm to 12 mm) monolithic tempered glass.
- **Header Track Length: 118"**



EZY2SD
Single Sliding Kit




EZY2HSD (Heavy Duty)
Single Sliding Kit




EZY2SDP
Single Sliding + Fixed Panel Kit




EZY2HSDP (Heavy Duty)
Single Sliding + Panel Track (118") / HD




EZY2CLSD
Single Sliding Kit with cladding



EZY2HDCLSD (Heavy Duty)
Single Sliding Kit with Cladding



EZY2CLSDP
Single Sliding + Fixed Panel Kit with Cladding




EZY2HDCLSDP (Heavy Duty)
Single Sliding + Panel Kit with Cladding



EZY2HSD
Single Sliding Track (118" Length)



EZY2HSDP
Fixed Panel Track (118" Length)



EZY2CLD
Extra Cladding (118" Length)



EZY2END2
Endcap for EZY2 Series Sliding Door Kit



EZY2RDKIT
Sliding Door Kit - Regular Duty



EZY2HDKIT
Sliding Door Kit - Heavy Duty





03 STOREFRONT & ENTRANCES HARDWARE

Continuous Gear Hinge




Continuous Gear Hinge

NEW



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Specification

- **Durable Construction:** Supports doors up to 200 lbs for long-lasting strength and performance.
- **Full-Length Hinge Design:** Applied along the entire door length to balance and distribute weight evenly.
- **Seamless Aesthetic:** The hinge is mounted to the frame rabbet and door edge, concealing both leaves.
- **Installation-Ready:** Includes all necessary fasteners for quick and straightforward installation.
- **Maximum allowed swing:** 80°

83" / 96" / 120" Long



GH1083

Continuous Gear Hinge - 10 Series


83" / 96" / 120" Long



GH2083

Continuous Gear Hinge - 20 Series

83" / 96" / 120" Long



GH3083

Continuous Gear Hinge - 30 Series

83" / 96" / 120" Long



GH4083

Continuous Gear Hinge - 40 Series



03 STOREFRONT & ENTRANCES HARDWARE

Grey Goat – Samples



Door Rails & Sidelite Rails

DLUX 4" Door Rail System	224	4" Taper Door Rail	230
DLUX 6" Door Rail System	227	4" Sidelite Rail	231



DLUX 4" Door Rail System



Finishes



*For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



Key Features:


- **Durable Build:** Constructed from high-quality 6060 T6 Aluminum for superior strength and corrosion resistance.
- **Efficient Installation:** Designed for quick and easy installation with no expensive tools required, ensuring time and cost savings.
- **Locking Mechanism:** Includes a built-in locking mechanism, offering enhanced security for glass doors.
- **Compact Dimensions:** 35-3/4" length for compatibility with standard installations.
- **Endcap (Included):** The specially designed endcap [DLUX4DEND], included in all finishes as of Base Shoe is used to securely attach at the ends for a clean and finished look

Cylinder Lock Accessory Options (Sold Separately):

- **Keyed Lock Cylinder [DLUXCYLK]:** Provides secure locking with a traditional key for enhanced security in high-traffic areas.
- **Thumb turn Cylinder [DLUXCYLT]:** Offers easy access with a thumb-turn mechanism, ideal for interior doors and low-traffic applications.
- **Dummy Cylinder [DLUXCYLD]:** A non-functional cylinder designed for aesthetic purposes, used when a locking mechanism is not required.

Kit Includes

- 1 X DLUX4D35 or 37 or 48
- 2 X DLUX4DEND
- 1 X DLUX4DPSB




DLUX4D35, 37, 48

DLUX 4" Door Rail - Without Lock

Kit Includes

- 1 X DLUX4D35 or 37 or 48
- 2 X DLUX4DEND
- 1 X DLUX4DPSB
- 1 X DLUXCYLMT



Sold Separate

- DLUXCYLK
- DLUXCYLT
- DLUXCYLD

DLUX4D35L, 37L, 48L

DLUX 4" Door Rail - With Lock

Without Lock - Dimension		SKU	With Lock - Dimension		SKU
35-3/4"		DLUX4D35	35-3/4"		DLUX4D35L
37-3/4"		DLUX4D37	37-3/4"		DLUX4D37L
48"		DLUX4D48	48"		DLUX4D48L

DLUX 4" Door Rail – Accessories



Finishes




Custom
Fabrication
Available

Included in Kit



DLUX4DEND
Door Rail Endcap

Included in Kit



DLUXCYLMT
Door Rail Lock

Included in Kit



DLUX4DPSB
Door Rail System - Pivot Slide Block

Sold Separate



DLUX4HWRENCH
3/16" Hex Wrench

Sold Separate



DLUXCYLK
Key Lock Cylinder

Sold Separate



DLUXCYLT
Thumbturn Lock Cylinder


Sold Separate



DLUXCYLD
Dummy Cylinder



Note: Visit ggshardware.com
For Glass Fabrication & Product Information.



DLUX 4" Sidelite Rail System



Finishes




Specification

- **Compatible with:** The 4" Architectural Door Rail System for seamless storefront installations.
- **Length:** 120" (10ft) & 240" (20ft)
- **Clearance Options:** Includes a reversible saddle for 1/4" or 3/4" clearance
- **Roll-In Gasket:** Includes roll-in gasket for 1/2" or 3/8" glass
- For glass fabrication details, CAD files, and the latest product information, please visit our website.
- Stock and finish availability may vary by product.

Kit Includes

1 X DLUX4SL120
1 X DLUX4SLSAD120
1 X ARUB12 (10FT)




DLUX4SL120

DLUX 4" Sidelite Rail -
120" (10ft) Length


Kit Includes

1 X DLUX4SL240
2 X DLUX4SLSAD120
1 X ARUB12 (20FT)



DLUX4SL240

DLUX 4" Sidelite Rail -
240" (20ft) Length



Included in Kit

1/2"(12mm) Glass



ARUB12

Architectural Roll-In Gasket for 1/2" (12mm) Glass


3/8"(10mm) Glass



ARUB10

Architectural Roll-In Gasket for 3/8" (10mm) Glass

Included in Kit



DLUX4SLSAD120

Additional Saddle for DLUX 4" Sidelite Rail
10' & 20' Length



AUSB4

Architectural Neoprene Setting Block - 4" Length

Sold Separate



DLUX4SLEND

Endcap for DLUX 4" Sidelite Rail

DLUX 6" Door Rail System



Finishes



*For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.



Key Features:

- **Durable Build:** Constructed from high-quality 6060 T6 Aluminum for superior strength and corrosion resistance.
- **Efficient Installation:** Designed for quick and easy installation with no expensive tools required, ensuring time and cost savings.
- **Locking Mechanism:** Includes a built-in locking mechanism, offering enhanced security for glass doors.
- **Compact Dimensions:** 35-3/4" length for compatibility with standard installations.
- **Endcap (Sold Separately):** The specially designed endcap [DLUX4DEND], available in all finishes as of Base Shoe is used to securely attach at the ends for a clean and finished look

Cylinder Lock Accessory Options (Sold Separately):

- **Keyed Lock Cylinder [DLUXCYLK]:** Provides secure locking with a traditional key for enhanced security in high-traffic areas.
- **Thumb turn Cylinder [DLUXCYLT]:** Offers easy access with a thumb-turn mechanism, ideal for interior doors and low-traffic applications.
- **Dummy Cylinder [DLUXCYLD]:** A non-functional cylinder designed for aesthetic purposes, used when a locking mechanism is not required.

Kit Includes

- 1 X DLUX6D35 or 37 or 48
- 2 X DLUX6DEND
- 1 X DLUX6DPSB



DLUX6D35

DLUX 6" Door Rail - Without Lock

Kit Includes

- 1 X DLUX6D35 or 37 or 48
- 2 X DLUX6DEND
- 1 X DLUX6DPSB
- 1 X DLUXCYLMT

Sold Separate

- DLUXCYLK
- DLUXCYLT
- DLUXCYLD



DLUX6D48L

DLUX 6" Door Rail - With Lock

Without Lock - Dimension		SKU	With Lock - Dimension		SKU
35-3/4"		DLUX6D35	35-3/4"		DLUX6D35L
37-3/4"		DLUX6D37	37-3/4"		DLUX6D37L
48"		DLUX6D48	48"		DLUX6D48L

DLUX 6" Door Rail Lock Accessories



Finishes




Included in Kit



DLUX4DEND
Door Rail Endcap

Included in Kit



DLUXCYLMT
Door Rail Lock

Included in Kit



DLUX4DPSB
Door Rail System - Pivot Slide Block

Sold Separate



DLUXCYLK
Key Lock Cylinder

Sold Separate



DLUXCYLT
Thumbturn Cylinder

Sold Separate



DLUXCYLD
Dummy Cylinder

Sold Separate



DLUX4HWRENCH
3/16" Hex Wrench

Sold Separate




DLUX4HTDF
Standard Top Door Rail Pivot Arm

Sold Separate



PPIV401-2H
Top Free Swing Pivot - 2 Holes

Short Arm / Long Arm




DLUX4HARMS
DLUX4HARML
Concealed Closer Arm

DLUX 6" Sidelite Rail System



Finishes




Specification

- **Compatible with:** The 6" Architectural Door Rail System for seamless storefront installations.
- **Length:** 120" (10ft)
- **Clearance Options:** Includes a reversible saddle for 1/4" or 3/4" clearance
- **Roll-In Gasket:** Includes roll-in gasket for 1/2" & 3/8" glass

Kit Includes

- 1 X DLUX6SL120
- 1 X DLUX6SLSAD120
- 1 X ARUB12 (10FT)



DLUX6SL120

DLUX 6" Sidelite Rail - 120" (10ft) Length



1/2" (12mm) Glass

Included in Kit



ARUB12

Architectural Roll-In Gasket for 1/2" (12mm) Glass

3/8" (10mm) Glass



ARUB10

Architectural Roll-In Gasket for 3/8" (10mm) Glass


Sold Separate



DLUX6SLEND

Endcap for DLUX 6" Sidelite Rail

Included in Kit



DLUX4SLSAD120

Additional Saddle for DLUX 4" Sidelite Rail - 10' & 20' Length

Sold Separate



AUSB4

Architectural Neoprene Setting Block - 4" Length

4" Taper Door Rail



Finishes

Clear Anodized

Matte Black

- **Durable Build:** Constructed from high-quality 6060 T6 Aluminum for superior strength and corrosion resistance.
- **Efficient Installation:** Designed for quick installation with no expensive tools required, ensuring time and cost savings.
- **Locking Mechanism:** Includes a built-in locking mechanism, offering enhanced security for glass doors.

Kit Includes

1 X DLUX4T35 or 37 or 48
2 X DLUX4TEND
1 X DLUX4DPSB
1 X DLUXCYLMT

Sold Separate

DLUXCYLK
DLUXCYLT
DLUXCYLD



Matching Finishes Available

Kit Includes

1 X DLUX4T35 or 37 or 48
2 X DLUX4TEND
1 X DLUX4DPSB




DLUX4T35L, 37L & 48L

Door rail taper 4" with lock



DLUX4T35, 37 & 48

Door rail taper 4" without lock



Sold Separate



DLUX4TEND

Taper Door Rail Endcap

1/2" (12mm) Glass



ARUB12

Architectural Roll-In Gasket for 1/2" (12mm) Glass



Included in Kit

DLUX4SLSAD120

Additional Saddle for DLUX 4" Sidelite Rail - 10' & 20' Length

3/8" (10mm) Glass



ARUB10

Architectural Roll-In Gasket for 3/8" (10mm) Glass



Sold Separate


AUSB4

Architectural Neoprene Setting Block - 4" Length

4" Sidelite Rail



Finishes



Specification

- **Compatible with:** The 4" Taper Architectural Door Rail System for seamless storefront installations.
- **Length:** 120" (10ft) & 240" (20ft)
- **Clearance Options:** Includes a reversible saddle for 1/4" or 3/4" clearance
- **Roll-In Gasket:** Includes roll-in gasket for 1/2" (12mm) or 3/8" (10mm) glass

Kit Includes

1 X DLUX4TSL120
1 X DLUX4SLSAD120
1 X ARUB12 (10FT)

Kit Includes

1 X DLUX4TSL240
2 X DLUX4SLSAD120
1 X ARUB12 (20FT)



DLUX4TSL120
DLUX4TSL240

4" Taper Sidelite - 120" (10ft) or 240" (20ft) Length




Sold Separate



DLUX4TEND

Taper Door Rail Endcap

1/2"(12mm) Glass



ARUB12

Architectural Roll-In Gasket for 1/2" (12mm) Glass

3/8"(10mm) Glass



ARUB10

Architectural Roll-In Gasket for 3/8" (10mm) Glass

Included in Kit



DLUX4SLSAD120

Additional Saddle for DLUX 4" Sidelite Rail - 10' & 20' Length

Sold Separate



AUSB4

Architectural Neoprene Setting Block - 4" Length

P13 Frameless Shower Door
P85 Railing Hardware

P163 Storefront & Entrance System
P223 Door Rails & Architectural Hardware

P261 Stock Glass Doors
P271 Glazing Supplies

03 Storefront & Entrances Hardware



04 DOOR RAIL & ARCHITECTURAL HARDWARE


DLUX 1-3/4" X 4" Header System



DLUX 1-3/4" X 4" Header System



Finishes




Specification

- **Standard Length:** Components available in 120" (10 FT) & 240" (20 FT) stock length for convenient purchasing.
- **Custom Fabrication:** Customizable 4" Architectural Door Header Systems tailored to your specifications.
- **Pre-Fabricated Options:** Ready-to-install single and double-door header systems for faster project completion.


DLUX4H120

DLUX 1-3/4 X 4" Header - 120" Length



DLUX4H240

DLUX 1-3/4 X 4" Header - 240" Length



DLUX4HPP120

DLUX 1-3/4 X 4" Header System - Pocket Plate - 120" Length



DLUX4HCP

DLUX 1-3/4 X 4" Header System - Closer Cover Plate - 14" Length



DLUX4HFP120

DLUX 1-3/4 X 4" Header System - Flat Plate - 120" Length



Header With Flat Plate

Header With Pocket Plate

Header With Flat Plate +
Concealed Closer Plate



Custom Header
Fabrication
Available



DLUX 1-3/4" X 4" Header System



Finishes



Specification

- **Ease of Installation:** Quick and hassle-free setup saves time and money; no expensive tools are required.
- **Complete Kit:** Includes mounting clips, screws, and detailed instructions for a seamless assembly experience.
- **Material:** Made from durable solid brass for long-lasting performance.

HO/NHO Complete With All Fasteners



ASSA ABLOY

DLUX4HDC90HOEXT

Concealed Overhead Header Door Closer Extended


Heavy Duty



DLUX4HDC90NHOEXTHD

ROCKWOOD 304 Heavy-Duty Overhead Concealed Door Closer


HO/NHO Complete With All Fasteners



DLUX4HDC90

Concealed Overhead Header Door Closer / Custom header fabrication Available

HO/NHO Complete With All Fasteners



DLUX4HDC9034

Concealed Overhead Header Door Closer / Custom header fabrication Available



DSTOP2


Door Rail System - Single Door Stop



DSTOP6

Door Rail System - Single Door Stop

Complete With All Fasteners




DLUX4WMB

DLUX Header System - Wall Mount Bracket

DLUX 1-3/4" X 4" Header System



Finishes



Specification

- Quick and easy installation
- Available in Short & Long Size
- No expensive tools required
- Designed to work with concealed closers
- Compatible with 4" Architectural Header System and Sidelite Rail System

Short Arm/Long Arm



DLUX4HARM

Concealed Closers Arm (Short Arm & Long Arm)



DLUX4H609ARM

ROCKWOOD Overhead Closer Arm (OHC-609-ARM)



DLUX4DP

Door Rail System - Pivot Slide Block

Heavy Duty



DLUXPIVHD

DLUX End Load Bottom Pivot



2SIDETAPE

Double-Sided Tape (1" x 175ft Long)




DLUXPIVWB

DLUX Door Rail Top Pivot - Walking Beam Pivot



DLUX4HTDF

Standard Top Door Rail Pivot Arm



DLUXPIVDP

Dual Purpose Pivot Kit



DLUXPIVADJ1434

Adjustable Bottom Pivot - 1/4"-3/4"

Smoke Baffle




Finishes



Specification:

- **Durable Build:** Constructed from high-quality 6060 T6 Aluminum for superior strength and corrosion resistance.
- Endcap sold separately.



Partition Sliding System




Format Sliding Door Entrance System

- The Format Sliding Door Entrance System offers a modern, durable solution for creating expansive glass entrances in both commercial and residential settings.
- Equipped with 4" tapered Series door rails on both top and bottom.
- Utilizes the Glass Securing System for reliable glass retention.
- Available in seven architectural finishes to complement various design themes.
- Bottom-rolling system ensures smooth operation and durability.
- Suitable for various commercial and residential entrance applications.

Door Configurations:

- X: Single sliding panel.
- XX: Two sliding panels on a single or double track.
- XO / OX: One sliding panel paired with a fixed panel.
- XXX: Sliding panels on both ends with a fixed center panel.
- OXO: Fixed panels on both ends with a central sliding panel.
- OXXO: Two central sliding panels flanked by fixed panels on each side.
- XXXX: Four-panel system with multiple sliding and fixed panel combinations.





03 STOREFRONT & ENTRANCES HARDWARE

Continuous Gear Hinge



Continuous Gear Hinge

INSTALLER'S
FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272



Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Specification

- **Durable Construction:** Supports doors up to 200 lbs for long-lasting strength and performance.
- **Full-Length Hinge Design:** Applied along the entire door length to balance and distribute weight evenly.
- **Seamless Aesthetic:** The hinge is mounted to the frame rabbet and door edge, concealing both leaves.
- **Installation-Ready:** Includes all necessary fasteners for quick and straightforward installation.
- **Maximum allowed swing:** 80°

83" / 96" / 120" Long



GH1083

Continuous Gear Hinge - 10 Series


83" / 96" / 120" Long



GH2083

Continuous Gear Hinge - 20 Series


83" / 96" / 120" Long



GH3083

Continuous Gear Hinge - 30 Series

83" / 96" / 120" Long



GH4083

Continuous Gear Hinge - 40 Series



04 DOOR RAIL & ARCHITECTURAL HARDWARE

Exposed Door Closer



Exposed Door Closer

INSTALLER'S
FAVORITE!
GOAT Drill & Spade Bits,
Refer Page Number: 272



Finishes



Key Features

- **Regular Arm Configuration:** Smooth, consistent closing for standard setups.
- **Back Check Function:** Prevents forceful opening to protect door and walls.
- **Non Hold Open Mechanism:** Auto-closes door for security and efficiency.

Non Hold Open Include Back Check Feature

- **Max Door Width:** 950mm (37-3/16")
- **Max Door Weight:** 65 kg (143lbs)



EDC016

Exposed Door Closer - Size 3 - Non Hold Open


Non Hold Open Include Back Check Feature

- **Max Door Width:** 1100mm (43-1/4")
- **Max Door Weight:** 80 kg (176lbs)



EDC017

Exposed Door Closer - Size 4 - Non Hold Open



DP017

Exposed Door Closer - Drop Plate



04 DOOR RAIL & ARCHITECTURAL HARDWARE

Rim Panic Device




Rim Panic Device

For glass fabrication details, CAD files, and the latest product information, please visit our website.
Stock and finish availability may vary by product.




Finishes



Specification

- **Stainless Steel Finish:** Provides a sleek, durable, and corrosion-resistant surface.
- **Door Compatibility:** Suitable for use with aluminum narrow style, wood, or hollow metal doors.
- **Installation Fasteners Included:** Comes complete with all necessary fasteners for easy installation.
- **Latch Mechanism:** Ensures quick, secure exit with minimal force.



RPD003SS

Rim Panic Device - Stainless Steel



RPLT012SS

Rim Panic Lever Trim - Stainless Steel

Commercial Ladder Pulls

12" Overall

12" CTC



OSTUB12

12" Offset Tubular Commercial Pull Handle

Specification

- **Material:** Premium SS304 stainless steel for superior durability
- **Tubular Diameter:** 1" (25.4mm) for a modern and comfortable grip
- **Suitable for Glass Thickness:** 3/8" - 3/4" (10mm - 19mm) tempered glass
- **Suitable for Wood/Aluminum Door Thickness:** Up to 1-3/4" (44mm)
- **Simple Installation:** Prepped for back-to-back mounting with included fasteners
- **Environment:** Perfect fit for Double Aluminum Door opening with two offset handle side by side for comfortable opening

Finishes



04 DOOR RAIL & ARCHITECTURAL HARDWARE

Architectural U-Channels



Architectural U-Channels




Finishes



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Specification

- **Compatible with:** The 4" Architectural Door Rail System for seamless storefront installations.
- **Length:** 240" (20ft)
- **Clearance Options:** Includes a reversible saddle for 1/4" or 3/4" clearance
- **Roll-In Gasket:** Includes roll-in gasket for 1/2" glass




AU120 & AU240

Architectural U-Channels with Roll-In Gaskets - 120" & 240" Length



1/2"(12mm) & 3/8"(10mm) Glass



ARUB12 & ARUB10

Architectural Roll-In Gasket for 1/2" (12mm) & 3/8" (10mm) Glass



ROLLER01 *

Vinyl Roller Tool




AUEND

Endcaps for Architectural U-Channels



2SIDETAPE

Double-Sided Tape (1" X 175ft Long)



AUSB4

Architectural Neoprene Setting Block - 4" Length

04 DOOR RAIL & ARCHITECTURAL HARDWARE

Commercial Spider Fittings




Commercial Spider Fittings – SPY Series



For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.

Finishes




Specification

- **Versatile Applications:** Ideal for commercial building facades, glass canopies, and interior partition walls.
- **High Load Capacity:** Designed to hold large glass panels securely, maintaining structural integrity and aesthetic appeal.
- **Durable Finish:** Available in brushed or polished stainless steel to suit different environment needs and withstand the elements.
- **Engineered data Available**

[Engineered Data Sheet Available!](#)

 <p>SPYFM4 Fin Mount Spider Fittings Quad Arm</p>	 <p>SPYFM2V Fin Mount Spider Fittings Double Arm V-Shape</p>	 <p>SPYFM2Y Fin Mount Spider Fittings Double Arm Y-Shape</p>	 <p>SPYFM1R Fin Mount Spider Fittings Single Arm Right</p>	 <p>SPYFM1L Fin Mount Spider Fittings Single Arm Left</p>
 <p>SPYFM2 Fin Mount Spider Fittings Double Arm</p>	 <p>SPYFM1 Fin Mount Spider Fittings Single Arm</p>	 <p>SPYPM4 Post Mount Spider Fittings Quad Arm</p>	 <p>SPYPM4C Post Mount Spider Fittings Quad Arm Corner</p>	




Commercial Spider Fittings – SPY Series

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.










Finishes



Specification

- **Versatile Applications:** Ideal for commercial building facades, glass canopies, and interior partition walls.
- **High Load Capacity:** Designed to hold large glass panels securely, maintaining structural integrity and aesthetic appeal.
- **Durable Finish:** Available in brushed or polished stainless steel to suit different environment needs and withstand the elements.


 <p>SPYPM3 Post Mount Spider Fittings Triple Arm</p>	 <p>SPYPM2V Post Mount Spider Fittings Double Arm V-Shape</p>	 <p>SPYPM2 Post Mount Spider Fittings Double Arm</p>	
 <p>SPYPM2C Post Mount Spider Fittings Double Arm Corner</p>	 <p>SPYPM1 Post Mount Spider Fittings Single Arm</p>	 <p>SPYPM1R Post Mount Spider Fittings Single Arm Left or Right</p>	

SPY Series Fasteners – SPY Series

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.




Finishes



Specification

- **High-Quality Material:** Made from 316 Alloy Stainless Steel for superior strength and weather resistance.
- **Fastening Mechanism:** Interior/exterior fixed or swivel mount that can tilt 6° for even stress distribution.
- **Suitable Glass Thickness:** 5/16" to 7/8" (8mm to 23mm)

	(5/16" to 19/32")	5/16" to 11/16"	11/16" to 1-1/32"	5/8" to 7/8"
 <p>SPYFARIG818 Rigid For 8mm to 18mm Glass</p>	 <p>SPYFASWEXT1523 Exterior Swivel For 8mm to 15mm Glass</p>	 <p>SPYFASW1826 Interior Swivel For 8mm to 18mm Glass</p>	 <p>SPYFASWEXT815 Interior Swivel For 18mm to 26mm Glass</p>	 <p>SPYFASW818 Exterior Swivel For 15mm to 23mm Glass</p>



04 DOOR RAIL & ARCHITECTURAL HARDWARE

Glass Canopy Brackets



Double Arm Connector



Finishes



- **Premium Material:** Made from high-quality stainless steel for strength and long-lasting durability.
- **Removable Round Adapter:** Allows easy customization for round or flat posts for versatile installation.

Adjustable



PROARMADJ

Double Arm Glass Connector - Adjustable

Fixed



PROARM

Double Arm Glass Connector - Fixed

Canopy Bracket

Finishes



*Custom configuration and size available based upon request products@ggshardware.com



Custom
Fabrication
Available

24"



GC2401

Glass Canopy Bracket (24" Height)

36"



GC3601

Glass Canopy Bracket (36" Height)



Ask us about
FACTORY DIRECT PROGRAM

04 DOOR RAIL & ARCHITECTURAL HARDWARE

Windows Hardware



Window Hardware

- **Durable Aluminum Frame:** Can be cut to fit various height openings.
- **Pre-Assembled Components:** Includes pre-installed rollers and corners for easy setup.
- **Secure & Functional:** Comes with locking handle and bug strip for added protection.



SDK20
Heavy-Duty Extruded Sliding Screen Door Kit



CGNCR
Nylon Combination Roller



SSLATCH
Sliding Screen Latch & Pull with Screw Holes




CFSM36100
Charcoal Fiberglass Screen Mesh
36" Width - 100' Roll



SRS125500
Screen Retainer Spline - 0.125" Ø - 500' Length



FCSS120500
Foam Core Screen Spline - 0.12" Ø - 500' Length



DO-IT-YOURSELF
Sliding Screen
Door Kit

04 DOOR RAIL & ARCHITECTURAL HARDWARE

Drive Thru Windows & Speak Thru



Drive Thru Windows & Speak Thru Series

For glass fabrication details, CAD files, and the latest product information, please visit our website. Stock and finish availability may vary by product.




Finishes




Specification

- **Opening Operation:** Auto/manual bi-parting or single-side options to suit any need.
- **Glass:** 1" (25 mm) clear tempered glass and 1/4" (6 mm) prep.
- **Design:** Thin stile panels for a contemporary, clean appearance.
- **Counter & Apron:** Stainless steel counter and metal apron for durability.
- **Electrical:** Requires 120VAC, 60 cycle, single-phase, 15-amp service; average current draw is under 2 amps. Up to 5 units may be connected to 1 circuit.




Exterior Elevation




Floor Plan

DTW8100TS

Drive-Thru Window - Automatic Biparting - 8100TS Flush Mount




Exterior Elevation




Floor Plan

DTW8200TS

Drive-Thru Window - Automatic Biparting - 8200TS Projected




Exterior Elevation




Floor Plan

DTW8300

Drive-Thru Window - Security Single Slide - 8300 Projected




Exterior Elevation




Floor Plan

DTW8100

Drive-Thru Window - Automatic Single Slide - 8100 Flush Mount



Exterior Elevation



Floor Plan

DTW8900

Drive-Thru Window - Manual Single Slide - 8900 Flush Mount

Brushed Stainless



ST5

Speak Thru

Specification

- **Minimal Framing:** Provides a sleek design with minimal support for a contemporary glass canopy.
- **24" Protrusion:** Ample coverage for various applications, offering protection while maintaining an open feel.
- **Durable Construction:** Crafted from high-quality 316 Stainless Steel for strength, corrosion resistance, and long-lasting durability.
- **Glass Compatibility:** Designed for 1/2" thick glass with a 3/4" diameter hole for easy installation.

Partition System


This product is currently in development. The image shown may differ from the final product. For the latest specifications and availability, please refer to our website.

Door Configurations:

- **Minimalist Design:** Slim-profile frames provide a clean, contemporary look that complements various interior styles.
- **Maximized Transparency:** Large glass panels allow for abundant natural light, creating open and airy environments.
- **Efficient Installation:** System-specific accessories and snap-on covers facilitate quick and straightforward assembly.
- **Customization Finishes:** Available in a range of finishes to match your design preferences and project requirements.
- **Versatile Applications:** Ideal for offices, meeting rooms, and other interior spaces where both openness and separation are desired.

Format Sliding Door Entrance System

Enhance your interior spaces with our sleek and modern Glass Partition System, designed to offer both functionality and aesthetic appeal.



ADA Compliant Hardware



ADAMIRROR

ADA-Compliance Mirror

Key Features

- **Surface Options:** Electroplated Brass, Brushed Silver
- **Mirror Type:** 5mm Copper-Free Silver Mirror with Explosion-Proof Film
- **Size Options:** 610 × 862 mm, 610 × 915 mm, 711 × 1016 mm, or Custom Sizes
- **Frame:** Constructed from 304 Stainless Steel for enhanced durability
- **Frame Front Width:** 10 mm
- **Backing:** Explosion-Proof Film for added safety
- **Weld Point:** Invisible weld point for a sleek and smooth appearance
- **Hanging:** Double Fixed Metal Hooks for easy installation

Finishes

Brushed
Stainless

Custom
Finishes





05 STOCK GLASS

Railing Glass Panels (1/2")

34" - 46" Railing Glass Panel 262

46" Glass Panel With Hinge Cutout 263

Glass Panel With Hinge & Latch Cutout 264




1/2" (12mm) Railing Glass Panel

Railing Glass Panels (1/2")



34" Height




Railing Glass Panel - 34" Height

Dimension

SKU

18X34	RG18X34
22X34	RG22X34
26X34	RG26X34
30X34	RG30X34
34X34	RG34X34
36X34	RG36X34
42X34	RG42X34
44X34	RG44X34
48X34	RG48X34
50X34	RG50X34
54X34	RG54X34
56X34	RG56X34
60X34	RG60X34
66X34	RG66X34
72X34	RG72X34

41" Height



Railing Glass Panel - 41" Height

Dimension

SKU

Dimension

SKU

12X41	RG12X41	44X41	RG44X41
14X41	RG14X41	46X41	RG46X41
16X41	RG16X41	48X41	RG48X41
18X41	RG18X41	50X41	RG50X41
20X41	RG20X41	52X41	RG52X41
22X41	RG22X41	54X41	RG54X41
24X41	RG24X41	56X41	RG56X41
26X41	RG26X41	58X41	RG58X41
28X41	RG28X41	60X41	RG60X41
30X41	RG30X41	62X41	RG62X41
32X41	RG32X41	64X41	RG64X41
34X41	RG34X41	66X41	RG66X41
36X41	RG36X41	68X41	RG68X41
38X41	RG38X41	70X41	RG70X41
40X41	RG40X41	72X41	RG72X41
42X41	RG42X41		

1/2" (12mm) Railing Glass Panel

Railing Glass Panels (1/2")




<div> <div>46" Height</div> <div>Railing Glass Panel - 46" Height</div> </div>	Dimension		SKU
	32X46		RG32X46
	48X46		RG48X46
	54X46		RG54X46
	60X46		RG60X46
	70X46		RG70X46
	72X46		RG72X46

1/2" (12mm) Railing Glass Panel With Hinge Cutout only

<div> <div>34" Height With Hinge Cutout</div> <div>Railing Glass Panel - 46" Height with Hinge Cutouts</div> </div>	Dimension		SKU
	32X46		RG32X46-2H
	48X46		RG48X46-2H
	54X46		RG54X46-2H
	60X46		RG60X46-2H


1/2" (12mm) Railing Glass Panel With Hinge & Latch Cutout

Railing Glass Panels (1/2")



RG32X46-2HL

1/2" Railing Glass Panel (Size: 32" x 46") With
Hinge & Latch Cutout 32X46-2HL



Refer to local building codes for product compliance
and installation requirements.

Factory Order Program

Factory Direct Savings on Volume Orders

Take advantage of our Factory Direct Program and save big on large-scale shower door orders. Whether you're working on condos, high-rises, or residential developments, we make the process easy, fast, and cost-effective

What You Get

01 Full Crates of Glass Shipped Directly to You

- Delivered fast and hassle-free - right to your shop or job-site.

02 Order Today – Just Give Us a Call

- Our team is ready to assist with quotes, coordination, and delivery planning.

Contact us to enroll: sales@ggshardware.com

Speak with our program manager: 1-905-264-1600

Ask about our MOQ charts, lead time options, and program perks.




05 STOCK GLASS

Stock Glass Doors

Shower Stock Door - 24" Width **266**

Shower Stock Door - Sliding Door **268**

Shower Stock Door - 26" Width **267**




Shower Stock Door – 24" Width



Glass Thickness: 3/8" (10mm) Tempered Safety Glass.

Beveled and Polished Edges, Prefabricated for either 6" or 6x18" handle combinations

24" Width - 2 Hole




X Height

SKU

64-2H	SD24X64-2H
66-2H	SD24X66-2H
68-2H	SD24X68-2H
70-2H	SD24X70-2H
72-1H	SD24X72-1H
72-2H	SD24X72-2H
74-2H	SD24X74-2H
76-2H	SD24X76-2H
78-2H	SD24X78-2H
80-2H	SD24X80-2H
82-2H	SD24X82-2H
84-2H	SD24X84-2H

24" Width - 3 Hole



X Height

SKU

64-3H	SD24X64-3H
66-3H	SD24X66-3H
68-3H	SD24X68-3H
70-3H	SD24X70-3H
72-3H	SD24X72-3H
74-3H	SD24X74-3H
76-3H	SD24X76-3H
78-3H	SD24X78-3H
80-3H	SD24X80-3H
82-3H	SD24X82-3H
84-3H	SD24X84-3H


Shower Stock Door – 26" Width



Glass Thickness: 3/8" (10mm) Tempered Safety Glass.

Beveled and Polished Edges, Prefabricated for either 6" or 6x18" handle combinations

26" Width - 2 Hole




X Height

SKU

64-2H	SD26X64-2H
66-2H	SD26X66-2H
68-2H	SD26X68-2H
70-2H	SD26X70-2H
72-2H	SD26X72-2H
74-2H	SD26X74-2H
76-2H	SD26X76-2H
78-2H	SD26X78-2H
80-2H	SD26X80-2H
82-2H	SD26X82-2H
84-2H	SD26X84-2H

26" Width - 3 Hole



X Height

SKU

64-3H	SD26X64-3H
66-3H	SD26X66-3H
68-3H	SD26X68-3H
70-3H	SD26X70-3H
72-3H	SD26X72-3H
74-3H	SD26X74-3H
76-3H	SD26X78-3H
78-3H	SD26X78-3H
80-3H	SD26X80-3H
82-3H	SD26X82-3H
84-3H	SD26X84-3H


Shower Stock Door – Tranquility Series



Glass Thickness: 3/8" (10mm) Tempered Safety Glass.

Beveled and Polished Edges, Prefabricated for tranquility series sliding door kit.

30" Fixed Panel



X Height

SKU

60-PANEL

SD30X60PANEL

62-PANEL

SD30X62PANEL


66-PANEL

SD30X66PANEL

76-PANEL

SD30X76PANEL

30" Width - 1 Hole Sliding Panel



X Height

SKU

60-1H

SD30X60DOOR-1H

62-1H

SD30X62DOOR-1H

66-1H

SD30X66DOOR-1H

76-1H

SD30X76DOOR-1H

76-2H

SD30X76DOOR-2H

05 STOCK GLASS

Shower Glass Shelves (3/8")




Shower Glass Shelves (3/8")



SGS10X10

Stock Glass Shelves
10" X 10" - Round (Quarter Circle)



SGS9X9

Stock Glass Shelves
9" X 9" - Round (Quarter Circle)

Shower Shelf Clamps




- **Material:** Solid Brass for exceptional strength and resistance to corrosion
- **Glass Thickness Range:** 1/4" to 3/8" (6 to 10 mm) to accommodate a variety of glass shelf thicknesses
- **No Glass Fabrication Required:** Clamps tighten easily using nylon-tipped screws, streamlining installation without the need for custom glass fabrication

Finishes



SCSQ

Shower Shelf Clamp - Square
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



SCRD

Shower Shelf Clamp - Round
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



SCFL *

Shower Shelf Clamp - Falcon
Glass Thickness Range: 1/4" to 3/8" (6mm to 10mm)



06 GLAZING SUPPLIES







Glazing Supplies

Carbide Tip Dill & Spade Bits	272	Tremco 440 Tape	274
High Bond Tape	273	SS Cleaners & Adhesives	275



Carbide Tip GOAT Drill & V Tip Spade Bits



<div>GOAT Drill Bits</div>    <div>FEATURE PRODUCTS</div>	Dimension		SKU
	3/16" X 4"		GBIT-3/16X4 GBIT-3/16X4-10PACK
	3/16" X 6"		GBIT-3/16X6 GBIT-3/16X6-10PACK
	1/4" X 4"		GBIT-1/4X4 GBIT-1/4X4-10PACK
	1/4" X 6"		GBIT-1/4X6 GBIT-1/4X6-10PACK
	5/32" X 4"		GBIT-5/32X4 GBIT-5/32X4-10PACK
<div>GOAT Spade Bits</div>   	Dimension		SKU
	3/16" x 4"		SBIT-3/16X4 SBIT-3/16X4-10PACK
	3/16" X 6"		SBIT-3/16X6 SBIT-3/16X6-10PACK
	1/4" X 4"		SBIT-1/4X4 SBIT-1/4X4-10PACK
	5/32" x 4"		SBIT-5/32X4 SBIT-5/32X4-10PACK
	5/32" x 6"		SBIT-5/32X6 SBIT-5/32X6-10PACK

GOAT – High Bond Tapes



Acrylic Adhesive Tape
Hi-Bond Clear - For Flat Bar Mounting

Dimension	SKU
1/2" Wide - 108FT Length 0.040" Thick	AHB04012
1/4" Wide - 108FT Length 0.040" Thick	AHB04014
1/2" Wide - 32FT Length 0.040" Thick	AHB04012-32
1/4" Wide - 32 FT Length 0.040" Thick	AHB04014-32
3/4" Wide - 108FT Length 0.050" Thick	AHB05034



Foam Adhesive Tape
Black Foam Tape - For Mirror Mounting

Dimension	SKU
6.5mm x 12mm 1/4" Thick & 10 Meter	FT1412BL
6.5mm x 19mm 1/4" Thick & 10 Meter	FT1434BL
3mm x 12mm 1/8" Thick & 20 Meter	FT1812BL
1.5mm x 12mm 1/16" Thick & 40 Meter	FT11612BL

Tremco® 440 Tape



Finishes



Specification

- **Premium Dimensions:** 1/16" thick x 3/8" wide, providing precise coverage and sealing.
- **Generous Roll Length:** 50 feet per roll to accommodate large-scale or multiple projects.
- **Superior Adhesion:** Made for excellent bonding to metal, glass, and other building materials.
- **Architectural-Grade Performance:** Delivers weather-resistant, airtight, and watertight seals, ideal for demanding applications.
- **Versatile Use:** Perfect for construction, glazing, curtain wall systems, and other architectural applications.
- **Durable and Flexible:** Maintains performance under various environmental conditions while ensuring easy application.



Dimension	SKU
1/8"X1/2" / 25FT	TREMCO440 1/8x1/2-BLK
1/16"X3/8" / 50FT	TREMCO440 1/16-BTAPE-50FT
1/16"X3/8" x20 / 50FT Contain 20 Rolls	TREMCO440 1/16-BTAPE-CASE
1/8"X3/8" / 25FT	TREMCO440 1/8-BTAPE-25FT
1/8"X3/8" x20 / 25FT Contain 20 Rolls	TREMCO440 1/8-BTAPE-CASE



Dimension	SKU
1/16"X3/8"	TREMCO440-1/16 GREYTAPE-50FT
1/16"X3/8" x20 Contain 20 Rolls	TREMCO440-1/16 GREYTAPE-CASE
1/8"X3/8"	TREMCO440-1/8 GREYTAPE-50FT
1/8"X3/8" x20 Contain 20 Rolls	TREMCO440-1/8 GREYTAPE-CASE

P13 Frameless Shower Door

P163 Storefront & Entrance System

P261 Stock Glass Doors

P85 Railing Hardware

P223 Door Rails & Architectural Hardware

P271 Glazing Supplies

06 GLAZING SUPPLIES

Stainless Steel Cleaners & Adhesives



Stainless Steel Cleaners & Adhesives



Specification

- **Effective Cleaning:** Removes dirt, grease, and stains effortlessly from stainless steel surfaces.
- **Brilliant Finish:** Polishes to a high shine, leaving surfaces looking clean and professional.
- **Protective Barrier:** Forms a long-lasting protective layer to guard against corrosion, fingerprints, and watermarks.
- **Versatile Use:** Suitable for use on stainless steel, aluminum, and other metal surfaces.
- **Convenient Application:** 400ml spray can for easy, even application on large or small surfaces.

Single / Pack of 12



WEICON-MULTICLEANER
Weicon® Multi Foam Cleaner

Single / Pack of 12



WEICON-SSCARE
Weicon® Stainless Steel Care Spray

Single / Pack of 12



WEICON-POWERCLEANER
Weicon® Power Cleaner S Spray



Single / Pack of 12



WEICON-RK1500
RK-1500 KIT

Stainless Steel Repair Kit



WEICON-SSREPAIR
Stainless Steel Repair

UV BOND



PERMABOND-UV620
UV620 Light Curing Adhesive

UV LAMP



UVSINGLELAMP
UV Single Tube Lamp

Glass Silicone Sealants

General Electric Sealants	278	Palmer Mirror Mastic / Sprayway	280
Tremco Sealants	279		




General Electric Sealants



Specification

- **Durable Seal:** Provides lasting flexibility and strong adhesion to block moisture, even in heat and humidity.
- **Waterproof and Heat Resistant:** Stands up to extreme temperatures and weather, ensuring reliable performance in challenging environments.
- **Mold and Mildew Resistant:** Infused with fungicide to inhibit growth, making it perfect for sanitary and wet area applications.
- **Versatile Bonding:** Securely adheres to glass, tile, metal, plastics, and composites.
- **One-Part, Acetoxo Cure:** Easy to apply with no mixing required, offering a quick tack-free time and a smooth, professional finish.

<div> <div> <div></div> <div>Clear</div> </div> <div> <div>Single / Bulk of 24</div> </div> </div> <div> </div> <div> <p>GE-SCS1700 GE SCS 1700 Sanitary Silicone Sealant</p> </div>	<div> <div> <div></div> <div>Black</div> </div> <div> <div>Single / Bulk of 24</div> </div> </div> <div> </div> <div> <p>GESCS1000 GE SCS 1000 Contractors Sanitary Silicone Sealant</p> </div>	<div> <div> <div></div> <div>Clear</div> </div> <div> <div>Single / Bulk of 24</div> </div> </div> <div> </div> <div> <p>GESCS2800 SCS2800 SiGlaze II Sealant Neutral-Cure</p> </div>	<div> <div> <div></div> <div>White</div> </div> <div> <div>Single / Bulk of 24</div> </div> </div> <div> </div> <div> <p>GESCS2000 GE SCS 2000 SilPruf Sealant</p> </div>
---	--	--	--













Tremco® Sealants

Specification

- **Neutral-Cure Formula:** Non-corrosive and compatible with sensitive materials for long-term performance.
- **Medium Modulus:** Provides the perfect balance of flexibility and strength for secure and durable seals.
- **Single-Component Convenience:** Ready to use with no mixing required, ensuring quick and clean application.
- **Fast Cure Time:** Accelerates production processes and reduces project downtime.
- **Excellent Tooling:** Easy to apply and smooth, ensuring professional-grade finishes.

<div> <input type="checkbox"/> Clear </div> <div>Single / Bulk of 30</div>  <div> TREMCOSPEC2 Tremco Spectrum II </div>	<div> <input type="checkbox"/> Clear </div> <div>Single / Bulk of 15</div>  <div> TREMCOSPEC2SSG Tremco Spectrum II Sausage </div>	<div> <input type="checkbox"/> Clear <input type="checkbox"/> Black </div> <div>Single / Bulk of 30</div>  <div> TREMSIL600 Tremco Tremsil® 600 </div>	
<div> <input type="checkbox"/> Clear </div> <div>Single / Bulk of 30</div>  <div> TREMCOPROGLAZE Tremco Proglaze </div>	<div> <input type="checkbox"/> Limestone </div> <div>Single</div>  <div> TREMFLEX834LIMESTONE Tremco Tremflex 834 (Limestone) </div>	<div> <input type="checkbox"/> White </div> <div>Single</div>  <div> TREMFLEX834WHITE Tremco Tremflex 834 (White) </div>	<div> <input type="checkbox"/> Clear <input type="checkbox"/> Black </div> <div>Single / Bulk of 30</div>  <div> TREMSIL-200 Tremco Tremsil® 200 - Acetoxy Sealant </div>

Palmer Mirror Mastic / Sprayway

Palmer



Specification

- **Reliable Adhesion:** Formulated for secure, long-lasting bonding of mirrors to multiple surface types.
- **Proven Compatibility:** Field and lab-tested for use with leading mirror brands and backing paints.
- **Convenient Application:** The 11 fl oz cartridge offers precision and ease, making installations faster and cleaner.
- **Industry Standard:** Trusted by professionals for delivering exceptional results in both residential and commercial projects.
- **Trusted Performance:** Field-tested and laboratory-approved for reliability in all types of mirror applications.

Single / Bulk of 24



MASTIC-BLUE

Mirro-Mastic
11 fl oz Cartridge

Single / Bulk of 24



MASTIC-QWIKSET

Mirro-Mastic QwikSet
10.1 oz Cartridge

Single / Bulk of 24



MASTIC-SUPERSET

Mirro-Mastic SuperSet
10.1 oz Cartridge



MASTIC-1G

Mirro-Mastic 1 Gallon
(3.78 L) Container



MASTIC-STIK

Palmer Mastic Stik

Single / Bulk of 24



SPRAYWAY-SW050

Sprayway - SW050 - Glass Cleaner



06 GLAZING SUPPLIES

Silicone Setting Blocks



Silicone Setting Blocks



Product Overview

- **Material:** High-quality silicone for durable cushioning
- **Temperature Range:** -30°F to +200°F (-34°C to 93°C) for versatile use
- **Available Sizes:** 1/16", 1/8", 3/16", 1/4", 3/8", 1/2", 7/16" & 1-1/8"
- **Function:** Protects glass during installation by absorbing shock and providing support
- **Ideal For:** Preventing damage to glass and ensuring secure placement during installation



SB-SIL-6

Silicone Setting Blocks - (1/2")

Dimension (X)

SKU

1/16"	SB-SIL-1
1/8"	SB-SIL-2
3/16"	SB-SIL-3
1/4"	SB-SIL-4
3/8"	SB-SIL-5
1/2"	SB-SIL-6
7/16"	SB-SIL-7
1-1/8"	SB-SIL-8
1/4 × 1/2" x 4"	SB-SIL-9
1/8 × 1/2" x 4"	SB-SIL-10



SB-SIL-8

Silicone Setting Blocks - (1-1/8")

Dimension

SKU

1/16" (Pack of 50)	SB-SIL-1-50PACK
1/8" (Pack of 50)	SB-SIL-2-50PACK
3/16" (Pack of 50)	SB-SIL-3-50PACK
1/4" (Pack of 50)	SB-SIL-4-50PACK
3/8" (Pack of 50)	SB-SIL-5-50PACK
1/2" (Pack of 50)	SB-SIL-6-50PACK
7/16" (Pack of 50)	SB-SIL-7-50PACK
1-1/8" (Pack of 50)	SB-SIL-8-50PACK
1/4 × 1/2" x 4" (Pack of 50)	SB-SIL-9-50PACK
1/8 × 1/2" x 4" (Pack of 50)	SB-SIL-10-50PACK

EPDM Setting Blocks



Product Overview

- **Material:** Durable EPDM rubber with excellent weather and moisture resistance
- **Available Sizes:** 1/16", 1/8", 3/16", 1/4", 3/8", 1/2", 7/16" & 1-1/8"
- **Application:** Widely used in frameless shower installations to provide stable and secure support for glass panels
- **Function:** Prevents direct contact between glass and hard surfaces, reducing the risk of damage or cracking
- **Ideal For:** Ensuring proper alignment and cushioning in frameless glass shower setups, **even in wet or humid conditions.**



SB-EPDM-6

EPDM Setting Blocks - (4" X 1-1/8" X 1/2")

Dimension (X)

SKU

1/16"

SB-EPDM-1

1/8"

SB-EPDM-2

3/16"

SB-EPDM-3

1/4"

SB-EPDM-4

3/8"

SB-EPDM-5

1/2"

SB-EPDM-6

4" X 7/16" X 1/2"

SB-EPDM-7

4" X 1-1/8" X 1-1/8"

SB-EPDM-8

4" X 1-1/8" X 5/8"

SB-EPDM-9



SB-EPDM-8

EPDM Setting Blocks - (4" X 1-1/8" X 1-1/8")

Dimension

SKU

1/16" (Pack of 50)

SB-EPDM-1-50PACK

1/8" (Pack of 50)

SB-EPDM-2-50PACK

3/16" (Pack of 50)

SB-EPDM-3-50PACK

1/4" (Pack of 50)

SB-EPDM-4-50PACK

3/8" (Pack of 50)

SB-EPDM-5-50PACK

1/2" (Pack of 50)

SB-EPDM-6-50PACK

4" X 7/16" X 1/2" (Pack of 50)

SB-EPDM-7-50PACK

1-1/8" (Pack of 50)

SB-EPDM-8-50PACK

5/8" (Pack of 50)

SB-EPDM-9-50PACK



Suction Cup



Wood's Power Grip



Specification

- **Fast Attach and Release:** Quickly secures to flat surfaces and releases effortlessly, improving work efficiency.
- **Red-Line Indicator:** Warns users of any significant vacuum loss, ensuring safety and reliability during use.
- **Protective Carrying Case:** Supplied with a durable case to protect the cup when not in use, ensuring longevity.
- **8-Inch Diameter:** Ideal for lifting and maneuvering glass, metal, and other smooth, flat materials.




WPG4950

Wood's Power-Grip 8" Hand Cup for Flat Surfaces



WPG5450

Wood's Power-Grip 9" Hand Cup for Flat Surfaces



MRTA8

Wood's Power-Grip MRTA8
Wood's Power-Grip - Glass Vacuum Lifter

Factory Order

All Wood's power products are available for factory order's - Contact us on

orders@ggshardware.com

Program Highlights:


- Direct-from-factory pricing for large-scale commitments
- Flexible order forecasting and inventory planning
- Custom labeling and product configurations
- Scheduled shipments based on your project phases
- MOQ (Minimum Order Quantity) applies – ask us for details

Contact us to enroll:

sales@ggshardware.com

Speak with our program manager: +1 905-264-1600

Ask about our MOQ charts, lead time options, and program perks.



Cut Resistance Gloves



Key Features

- **High-Level Cut Resistance:** Engineered with advanced materials to withstand sharp edges and reduce the risk of injuries.
- **Comfortable Fit:** Lightweight, breathable fabric ensures all-day comfort during use.
- **Excellent Grip:** Textured surface for a secure hold on tools, materials, and equipment.
- **Durable and Reusable:** Built to last through multiple uses without losing performance.
- **Versatile Use:** Ideal for kitchen work, construction, carpentry, metalworking, glass handling, and more.



GLOVES-BLK

Multifunctional Sealant Tool (5in1)



GLOVES-BLU

Multifunctional Sealant Tool (5in1)



Multifunctional Sealant Tool (5in1) & Magic Eraser



Specification

- **5-in-1 Functionality:** Combines multiple tools for repairing gaps, removing excess sealant, and achieving smooth finishes.
- **Sliding Switch Design:** Easily switch between the trowel and squeegee functions to adapt to various tasks.
- **Sealant Finishing Tools:** Includes 4 different soft head sizes (3R, 6R, 10R, 13R, 17R) for a variety of smoothing needs.
- **Reusable and Durable:** Made from high-quality plastic, the tool is easy to clean and built for long-lasting use.
- **Versatile Applications:** Ideal for use in kitchens, bathrooms, windows, sinks, and other home improvement projects.




SEALANT-TOOL

Multifunctional Sealant Tool (5in1)



ALERASER

Aluminum Magic Eraser For Scratch Removal



3M Scotch Brite



3MHANDPAD

3M Scotch Brite General Purpose Hand Pads

Specification

- **Superior to Traditional Methods:** Outlasts steel wool, wire brushes, and sandpaper for cleaning, finishing, and surface preparation.
- **Versatile Applications:** Effective on rubber, composites, wood, metal, plastics, ceramics, porcelain, and glass.
- **Reusable and Long-Lasting:** Resists tearing, splintering, shredding, loading, and corrosion, providing a long useful life.
- **Flexible Design:** Can be folded, stacked, or rolled for efficient cleaning or conditioning on flat, uneven, or contoured surfaces.

Cork Pads



100 Roll / 1000 Roll / 5000 Roll



CORKPAD

3M Scotch Brite General Purpose Hand Pads

Specification

- **Superior to Traditional Methods:** Outlasts steel wool, wire brushes, and sandpaper for cleaning, finishing, and surface preparation.
- **Versatile Applications:** Effective on rubber, composites, wood, metal, plastics, ceramics, porcelain, and glass.
- **Reusable and Long-Lasting:** Resists tearing, splintering, shredding, loading, and corrosion, providing a long useful life.
- **Flexible Design:** Can be folded, stacked, or rolled for efficient cleaning or conditioning on flat, uneven, or contoured surfaces.


Dimension	SKU
Cork Pads 5000 per roll	CORKPAD5000
Cork Pads 1000 per roll	CORKPAD1000
Cork Pads 100 per roll	CORKPAD100



Horseshoe Shims



HORSESHOE1/4
Horseshoe Shim Tile Spacers
(1/4" Thick)



HORSESHOE1/8
Horseshoe Shim Tile Spacers
(1/8" Thick)



HORSESHOE1/16
Horseshoe Shim Tile Spacers
(1/16" Thick)



STKS16
GGG 1/16" x 3-1/2"
Stackable Shims



06 GLAZING SUPPLIES


Grey Goat – Tools



Grey Goat – Tools



GCSTENSIONER
Torq Tool Tensioner - Fencing Tool



SOWRENCH
Wrench




ALHRAIL-TOOL
Fix Tool For Aluminum Handrail



SSOKIT
Tool Kit for Solid Standoffs (1.5" & 2" Diameter)



CAMI-TOOL
CAM Series - Tool Kit



TISM-TOOL
Socket Tool



ADJFITTOOL
Flex Tool



DLUX4HWRENCH
3/16" Hex Wrench



LAGWRENCH
Adjustable Wrench For Rollers



GCSCUT
Cable Cutter

Grey Goat – Tools



CGLIGHT

Lightweight Composite Body Dripless Caulking Guns



CGSTEEL / CGSS

Dripless Caulking Guns Rugged Steel Body



LFWIPE

Lint-Free Glass Wipes



SQGE10

Shower Squeegee



DOLLY1

Plate Glass Dolly



Screws And Bolts



TISCREWMBL
Set Screw



SCREW-ST10X100
Countersunk Wood Screw



BOLT-M10X84
Countersunk Anchor Bolts

SS316 & ZINC



ADJ12M-HB-5/8x1-1/2
Hanger Bolt

SS316 & ZINC



ADJ12M-HB-5/8x2-1/2
Hanger Bolt

SS316 & ZINC




ADJ12M-HB-5/8x3-1/4
Hanger Bolt



SCREW-HINGE
Set Screws For Shower Hinges



SCREW-M8X20
Replacement Allen Screws





SCREW-LADDERPULL
Flat Head Screws





SCREW-WALL
Wall Mount Screws

Screws And Bolts



<div>SS316 & ZINC</div>  <div>Hanger Bolt</div>	Dimension		SKU
	2" Ø~ X 1/4"		SSO2X0.25
	2" Ø~ X 1/2"		SSO2X0.5
	2" Ø~ X 3/4"		SSO2X0.75
	2" Ø~ X 1"		SSO2X1
	2" Ø~ X 1-1/4"		SSO2X1.25
	2" Ø~ X 1-1/2"		SSO2X1.5
	2" Ø~ X 1-3/4"		SSO2X1.75
	2" Ø~ X 2"		SSO2X2
	2" Ø~ X 2" with 1/2 H		SSOH2X2
	2" Ø~ X 2" with 1/2 H		SSOH2X2
<div>SS316</div>  <div>Threaded Rod</div>	Dimension		SKU
	3/8" X 6"		TR38X6-SS316
	1/2" X 6-1/4"		TR12X6.25SS



06 GLAZING SUPPLIES

Acrylic Mirror Plates



Acrylic Mirror Plates



AMPDEC1
Single Decorator



AMPDEC2
Double Decorator



AMPDEC3
Triple Decorator



AMPDEC4
Quad Decorator



AMPT1
Single Toggle



AMPT2
Double Toggle



AMPTDEC1
Single Toggle - Decorator Combo



AMPDUP1
Duplex



Appendix



0-9

1/2" (12mm) Railing Glass Panel	113
• With Hinge & Latch Cutout	116
12"x12" Shower Handles	45
18" X 18" Shower Towel Bars	46
24" x 24" Shower Towel Bar	46
2"x2" Glass Clamps	34
3M Scotch Brite	288
4" Taper Door Rail	230
4" Sidelite Rail	231
6"x6" Shower Handles	40
6"x18" Shower Handle Towel Bar Combo	42
• 8"x18" Shower Handle Towel Bar Combo	42
6"x24" Shower Handle Towel Bar Combo	43
69 Series - Components & Accessories	88
86 Series - Components & Accessories	89
8"x8" Shower Handles	41

A

Acrylic Mirror Plates	296
Adjustable - Jennifer Series	15
Adjustable - Beverly Series	17
Adjustable - Vivian Series	19
Adjustable - Colette Series	21
Adjustable - Valerie Series	22
Additional Components - Mechanical U-Channel	208
ADA Compliant Hardware	259
Aluminum Flat Bars - Grid Showers	63
Aluminum Caprail - Rectangle	145
Aluminum Posts	151
Aluminum Caprail - Square - 1-9/16" (40mm)	144
Arch-Loc Series	85
Arch-Loc Spigot	95
Arc Series Standoffs	104
Architectural Railing Post - Blank	118
Architectural Railing Posts - Square	119
Architectural Railing Posts - Round	120
Architectural Railing Posts - Side Mount	121
Architectural Railing Post - For Stairs	122

A

Architectural Railing Post - Accessories	123
Architectural Railing Posts - Double Arm Posts	124
Architectural U-Channels	246
ASSA ABLOY	163

B

Base Shoe Installation Application	90
Beverly Series	16
Betty Series	23

C

CAMI Series	71
Caprail - Round - 1-5/8" (42.4mm) Ø	139
Caprail - Square - 19' - (40mm)	140
Caprail - Rectangle - 2-3/8"x1-9/16" (60X40mm)	141
Caprail - Square - 1"x1" (25x21mm)	142
Cara Series	24
Cara Series - Heavy Duty	25
Colette Series	20
Commercial U-Channels	181
Commercial Ladder Pulls	195
Continuous Gear Hinge	218

D

Display Standoffs	112
Double Arm Connector	125
DLUX 4" Door Rail System	224
DLUX 4" Door Rail - Accessories	225
DLUX 4" Sidelite Rail System	226
DLUX 6" Door Rail System	227
DLUX 6" Door Rail Lock Accessories	228
DLUX 6" Sidelite Rail System	229
DLUX 1-3/4" X 4" Header System	234
Drive Thru Windows & Speak Thru Series	256

Appendix



E

Economy Series - Fixed Mechanical U-channel	206
Electromagnetic Entry Door Lock	179
EPDM Setting Blocks	283
Exposed Door Closer	243
EZY1 Sliding Door Kits - Facia Mount	216
EZY2 Sliding Door Kits - Ceiling Mount	217

F

Factory Order Program	82
Flat Bar For Grid Showers	62
Floating Headers	168

G

Gaskets & Accessories - Standoffs	110
G-AWS Aluminum Windscreen System	128
General Electric Sealants	278
GGH LED System	101
Glass Shower Door Stoppers	67
Glass Door Locks	187
Glass Display Hardware	190
Goat Cable Rail System	154
GOAT - High Bond Tapes	273
Grey Goat Color Samples Kit	83
Grey Goat - Tools	292

H

Handle Accessories	53
Hanger Bolts & Threaded Rod - Standoffs	109
Handrail Brackets - Wall Mount	148
Handrail Brackets - Glass Mount	149
Handrail Brackets	150
Handrail - Round - 1-5/8" (42.4mm) Ø	134
Handrail - Round - 1-1/2" (38.1mm) Ø	136
Handrail - Square - 1-9/16" (40mm)	137
Handrail - Rectangle - 2" X 1" (50x25mm)	138
Header Kit Accessories	61
Horseshoe Shims	289
Hydraulic Hinges - Hulk Series	157

J

Jennifer Series	14
Junior Jennifer Series	28

L

Ladder Pulls-Back To Back	196
Ladder Pulls - Offset Back to Back	197
Ladder Pulls - ADA Locking	198
Ladder Pulls - Single-Sided	199
Ladder Pulls - Square - SQS Series	200
Ladder Pulls - Square To Round - SQR Series	201
Ladder Pulls - Tubular	202
Ladder Pulls-Offset & Curved Ladder Pull Handle	204
LAG Series - Glass Mount	210
LAG Series - Wall Mount	211
LAG Series - Double Door Wall Mount	212
Latches with Lock	160
Latches Without Lock	161
Latches Hinges	162
LED Mirrors	58
LUNA Series	73

M

Mall Clamps	183
Mirror L & J Channels	56
Modern Elegance Series - Aluminum Posts	152
Modern Elegance Series Accessories - Aluminum Posts	153
Multifunctional Sealant Tool (5in1) & Magic Eraser	287

P

Palmer Mirror Mastic / Sprayway	280
Partition Sliding System	238
Partition System	258
Patch Fittings Configurations	174
Patch Fittings Configurations	175
Patch Fittings & Transom	176

Appendix



P

Piper Series	26
Piper Series - Heavy Duty	27
Pool Fencing - Brackets	132

R

Railing Mini Post	126
Railing Clamps Accessories	131
Rim Panic Device	244
Romeo Juliet Balcony System	146
Rockwood Handles	169

S

Sauna Handle	47
Screws And Bolts	294
Shower Door Knobs & Combo & Robe Hooks	52
Shower End Cap & Threshold	55
Shower Glass Shelves (3/8")	81
Shower Header Kit	60
Shower Hinge Accessories & Back Plates	29
Shower Sweeps - Ultra Clear 3/8" (10mm) Glass	30
Shower Sweeps - Ultra Clear Magnetic Sweeps - 3/8" & 1/2" (10-12mm) Glass	32
Shower Support Bar - Adjustable	66
Shower Stock Door - 24" Width	78
Shower Stock Door - For Sliding Door	80
Shower Shelf Clamps	81
Shower U Channels	55
Single Sided Towel Bars	44
Silicone Setting Blocks	282
Slim Series Handles	51
Smoke Baffle	233
Solid Standoffs	106
Solid Standoff Base	108
Solidity Hydraulic Bottom Patch	172
Soft-Closing Sliding Door System	214
Striker Center Lock Series	194
Storeroom Center Lock	192
SQ-Transom Glass Clamps	36

Square Railing Clamps	130
Stylish Series Handles	51
Standoffs With Mounting Plate	111
Storeroom Center Lock	192
Stainless Steel Cleaners & Adhesives	276

T

Tartarian & Atlantis Series - Towel Bar	48
Tartarian Series	49
Tartarian Series - Towel Bar	50
Templating Sheet	290
Titan Series - SQ/RD Top Mount Spigots	94
Titan Series - Stair Mount Spigots	96
Titan Series - Side Mount Spigots	97
Titan Series - Edge Mount Spigots	98
Titan Series - Core Mount Spigots	99
Titan Series Spigot Height Guide	100
Tranquility Series	70
Tranquility Series - Heavy Duty	74
Tremco® 440 Tape	274
Tremco® Sealants	279

V

Valerie Series	22
Vivian Series	18

W

Window Hardware	255
Wood's Power Grip	286

Catalogue Contributors

Jinu Jung (Design & Layout), **Harmil Patel** (Technical Data),
Smit Rathod (3D Rendering and Illustrations), **Bo Yee Wong** (Content Writer),
Jeffrey Lai (Digital Integration) **Pradeep Kushwaha** (Project Lead & Technical)

Our Locations

Canada's Trusted [Glazing Hardware Distributor](#)

With distribution centers in Toronto, Montreal, and Calgary, Grey Goat Hardware ensures fast and efficient service - wherever your project takes you.



Contact Us

Trusted by [2,000+](#) glazing contractors across North America

TORONTO WAREHOUSE

606 Rivermede Rd, UNIT #1 & 2, Concord,
ON L4K 2H6

☎ Phone: 1-905-264-1600

✉ Textline: 1-877-999-4628

✉ Email: cs.toronto@ggshardware.com

🌐 Website: www.ggshardware.com

MONTREAL WAREHOUSE

8145 Avenue Marco-Polo, Montreal, QC
H1E 5Y8

☎ Phone: 1-514-547-3422

✉ Textline: 1-877-999-4628

✉ Email: cs.montreal@ggshardware.com

🌐 Website: www.ggshardware.com

CALGARY WAREHOUSE

2880 45 Ave SE, Unit # 248, Calgary, AB
T2B 3M1

☎ Phone: 1-905-264-1600

✉ Textline: 1-877-999-4628

✉ Email: cs.calgary@ggshardware.com

🌐 Website: www.ggshardware.com

www.ggshardware.com

Scan For Real-Time

Get instant access to key tools and info — right from your phone.

[Scan to Order](#) | [Real-Time Inventory](#) | [Custom Pricing](#) | [Volume Discounts](#) | [Orders Tracking](#)
| [3D CAD Models](#) | [Technical Drawings](#) | [Factory Order Programs](#) | [Full Product Catalog](#)



GGH GLAZING
SUPPLY
COMPANY

TORONTO • MONTREAL • CALGARY



GGH PRODUITS
VERRIERS

TORONTO • MONTREAL • CALGARY